

## N O T I C E


THIS DOCUMENT HAS BEEN REPRODUCED FROM  
MICROFICHE. ALTHOUGH IT IS RECOGNIZED THAT  
CERTAIN PORTIONS ARE ILLEGIBLE, IT IS BEING RELEASED  
IN THE INTEREST OF MAKING AVAILABLE AS MUCH  
INFORMATION AS POSSIBLE

NASA CR-

160579

# SPACE CONSTRUCTION SYSTEM ANALYSIS

PART 2 FINAL REPORT  
CONSTRUCTION ANALYSIS  
APRIL 1980



Rockwell International

Space Operations and  
Satellite Systems Division  
Space Systems Group  
12214 Lakewood Boulevard  
Downey, CA 90241



(NASA-CR-160579) SPACE CONSTRUCTION SYSTEM  
ANALYSIS. PART 2: CONSTRUCTION ANALYSIS  
Final Report (Rockwell International Corp.,  
Downey, Calif.) 776 p HC A99/MF A01

N80-22375

CSCL 22A G3/12

Unclas  
16691



SSD 80-0038

SPACE CONSTRUCTION SYSTEM ANALYSIS

PART 2, FINAL REPORT

Construction Analysis

APRIL 1980

NAS9-15718

Principal Arthur: J. A. Roebuck

Satellite Systems Division  
Space Systems Group



Rockwell  
International

## FOREWORD

This report summarizes the construction analysis procedures and results for the Engineering Technology Verification Platform (ETVP). The ETVP was selected at the end of Part I of the study for use as a model system to study space construction concepts and processes. The construction requirements, platform design definition, and related rationale in this analysis are the study products from Task 8 of Contract NAS9-15718, Space Construction System Analysis Study. This contract effort was conducted by the Space Operations and Satellite Systems Division, Space Systems Group of Rockwell International Corporation for the National Aeronautics and Space Administration, Johnson Space Center. The work was administered under the technical direction of the Contracting Officer's Representative (COR), Mr. Sam Nassiff, Spacecraft Systems Office, Spacecraft Design Division, Johnson Space Center.

The study was performed under the direction of Ellis Katz, Study Manager. The following persons made significant contributions toward completion of the analyses reported herein.

P. A. Buck	A. N. Lillenas
C. H. Fritz	C. K. McBaine
G. W. Gimlich	H. L. Myers
H. S. Greenberg	D. W. Peebles
R. J. Hart	J. A. Roebuck, Jr.
J. Indrikis	A. J. Stefan
A. E. LeFever	R. R. Thompson

Major documents resulting from Part II of the contract effort are listed below:

Space Construction System Analysis, Part 2, Platform Definition,  
Final Report SSD 80-0037

Space Construction System Analysis, Part 2, Construction Analysis, Final Report	SSD 80-0038
--	-------------

Space Construction System Analysis, Part 2, Cost and Programmatic,  
Final Report SSD 80-0039

Space Construction System Analysis, Final Report, Space Construction  
Experiments Concepts SSD 80-0040

Space Construction System Analysis, Part 2, Executive Summary,  
Final Report SSD 80-0041



## CONTENTS

<u>Section</u>	<u>Page</u>
1.0 INTRODUCTION	1-1
2.0 CONSTRUCTION REQUIREMENTS	2-1
3.0 CONSTRUCTION STRATEGY	3-1
4.0 GUIDELINES & ASSUMPTIONS	4-1
5.0 FIRST CONSTRUCTION MISSION	5-1
6.0 SECOND CONSTRUCTION MISSION	6-1
7.0 THIRD CONSTRUCTION MISSION	7-1
8.0 COMPOSITE CONSTRUCTION ANALYSIS	8-1
9.0 CONCLUSIONS & RECOMMENDATIONS	9-1

## APPENDIXES

A. ENGINEERING CONCEPT DRAWINGS	A-1
B. CONSTRUCTION ACTIVITY DATA SHEETS & SUPPORTING DATA PACKAGES	B-2
C. MASS PROPERTIES STATEMENTS	C-1

## ILLUSTRATIONS

<u>Figure</u>		<u>Page</u>
1.2-1	Iterative Construction Process	1-2
3.1-1	Construction Fixture Systems	3-2
3.1-2	Station 1 Construction Fixture & Equipment	3-3
3.1-3	Station 2 Construction Fixture & Equipment	3-4
3.2-1	Longitudinal Beam Fabrication	3-5
3.2-2	Crossbeam Fabrication & Assembly	3-5
3.2-3	Fixture Untended Configuration	3-6
3.2-4	SCM Installation	3-7
3.2-5	Bracing Strut Installation	3-7
3.2-6	Attach Port Alignment	3-8
3.2-7	RCS Module Installation	3-8
4.1-1	Typical Mission Ascent Trajectory Data	4-2
4.1-2	Total Maximum Phasing Time	4-5
4.1-3	Orbiter Attitude-Hold Capabilities	4-12
4.2-1	Crew Cabin Arrangement	4-18
4.2-2	Aft Flight Deck Configuration	4-19
4.4-1	Manned Maneuvering Unit	4-25
4.4-2	MMU/FSS Configuration in Payload Bay	4-27
4.4-3	MMU Reference Coordinate System	4-30
4.4-4	OCP-Data General Arrangement	4-32
4.4-5	Foot Restraint	4-34
4.4-6	EMU Reach Capability	4-35
4.4-7	Three-Degree-of-Freedom Stabilizer	4-36
4.4-8	Orbiter/RMS/OCP Block Diagram	4-38
4.4-9	Orbiter Remote Manipulator System	4-40
4.4-10	RMS Location	4-41
4.4-11	RMS Arm Dimensions & Joint Angle Limits	4-42
4.4-12	Standard End Effector	4-44
4.4-13	Standard Grapple Fixture & Target	4-45
4.4-14	RMS Standard End Effector & Grapple Fixture Envelope Schematic	4-46
4.4-15	Snare End Effector, Capture & Rigidize Sequence	4-47
4.4-16	RMS Standard End Effector/Special-Purpose Electrical End Effector Interface	4-48
4.4-17	Control Coordinate Reference System	4-51
4.4-18	RMS Operator Station	4-54
4.4-19	RMS CCTV Wrist Camera & Light Subassembly Design Configuration	4-55
4.4-20	CCTV Camera Mounting Options	4-57
4.4-21	Cyclic Feed Fabricator Functional Schematic	4-58
4.4-22	SCAFEDS Beam Builder Concept	4-59



ILLUSTRATIONS  
(Continued)

<u>Figure</u>		<u>Page</u>
5.1-1	Planned Configuration of ETVP at End of First Construction Mission	5-2
5.1-2	Engineering & Technology Verification Platform Construction Logic - First Mission	5-4, 5-5
5.2-1	Initial Conditions for Construction - First Mission	5-7
5.2-2	RMS Transporting the Construction Fixture to Operational Location	5-8
5.2-3	RMS Transporting Beam Builder to Deployed Construction Fixture	5-10
5.2-4	Fabricating the First Longitudinal Beam & Setting Up Construction Station No. 2	5-11
5.2-5	Fabrication of 2nd Longitudinal Beam During Wire Laying on First Longitudinal Beam	5-12
5.2-6	Moving Beam Builder to Construction Station No. Station No. 2	5-14
5.2-7	Fabrication of First Transverse Beam	5-15
5.2-8	Transport & Installation of First Transverse Beam During Fabrication of Second	5-16
5.2-9	Procedure for Joining Crossbeams & Transverse Beams to Longitudinal Beams	5-17
5.2-10	Fabrication of Crossbeam & Installing Bracing Cords	5-18
5.2-11	EVA Connection of Electrical Lines - Crossbeam to Longitudinal	5-19
5.2-12	Translation of Platform Structural Assembly	5-20
5.2-13	Bracing Cord Installation	5-21
5.2-14	Preparation for Untended Operation	5-23
5.3-1	End-to-End Construction Activity Analysis	5-24
5.4-1	Integration Analysis Process	5-27
5.4-2	Integration Activity Timeline - First Mission	5-31, 5-32
5.4-3	Representative Cycle of Repetitive Construction Activity - First Mission	5-33, 5-34
5.4-4	Baseline Crew Activity Schedule - First Mission	5-36
5.4-5	Alternate (4-Man) Crew Activity Schedule - First Mission	5-39, 5-40
5.4-6	Typical Time Allocation for Shuttle EVA Work Day	5-41
5.4-7	Lighting & TV Camera Locations for Construction - First Mission	5-43, 5-44
5.4-8	Payload Energy/Power Availability	5-45
5.4-9	Power Profile for First Mission	5-47, 5-48
5.4-10	Remote Manipulator System Modifications	5-51

<u>Figure</u>		<u>Page</u>
5.4-11	Construction Station No. 1 & Beam Builder Machine	5-52, 5-53
5.4-12	Construction Station No. 2	5-54
5.4-13	Additional Construction Support Equipment	5-55
5.5-1	First Mission Manifest	5-67
5.5-2	Center-of-Gravity Locations	5-68
6.1-1	Configuration of Engineering & Technology Verification Platform at the End of the Second Mission	6-2
6.1-2	Logic Diagram for Construction Activities During Second Mission	6-4
6.2-1	Installation of Forward Strut Assembly	6-6
6.2-2	Installation of Systems Control Module	6-7
6.2-3	Installation of Cross Beam Bracing Struts	6-9
6.2-4	Installation of the TT&C Antenna Adjacent to Thrust Structure	6-10
6.2-5	Perform Electrical Continuity Checks	6-12
6.2-6	Measure Structural Misalignments	6-13
6.2-7	Second Mission Assembly Sequence	6-14
6.5-1	Cargo Center-of-Gravity Locations	6-31
6.5-2	Second Mission Manifest	6-32
7.1-1	ETVP Configuration at Completion of Third Mission	7-2
7.1-2	Logic Diagram for Construction Activities During Third Mission	7-4
7.2-1	Installation of RCS Modules	7-5
7.2-2	Removal of Umbilical Following Platform Checkout & Activation	7-7
7.2-3	Third Mission Assembly Sequence	7-8
7.4-1	Integration Activity Timeline	7-11, 7-12
7.4-2	Power Profile - Third Mission	7-15, 7-16
7.4-3	Key Construction Support Equipment for Third Mission	7-18
7.5-1	Cargo Center of Gravity Locations	7-20
7.5-2	Third Mission Manifest	7-21
8.2-1	ETVP Mission Scenario	8-5
8.2-2	Installation of Orbit Transfer Propulsion Module	8-8
8.5-1	Beam-to-Beam Joining Concepts	8-13
8.5-2	Automated Connector Concept	8-14
8.5-3	Self-Insertion Connector Concept	8-16
8.5-4	Modularity	8-17
8.6-1	Resource Utilization Summary	8-19

# TABLES

<u>Table</u>		<u>Page</u>
4.1-1	Guidelines & Assumptions for Payload Bay Packaging	4-1
4.1-2	Mission Ascent Timeline (Rendezvous with 12 Hr Phasing)	4-4
4.1-3	Mission Ascent Timeline Without Rendezvous	4-10
4.1-4	Entry Timeline	4-13
4.2-1	Orbiter Support Services for Space Construction	4-16
4.2-2	Crew Accommodation Assumptions for Space Construction Using the Orbiter	4-17
4.3-1	Guidelines & Assumptions for EVA Construction Operations Hardware & Supplies	4-20
4.3-2	Guidelines & Assumptions for IVA Construction Operations Hardware & Supplies	4-21
4.3-3	Guidelines & Assumptions for Crew Work/Rest Cycles During Construction	4-22
4.3-4	Assumptions Related to Crew Assignments	4-23
4.4-1	MMU Flight Characteristics	4-28
4.4-2	Force/Torque Capability at End Effector	4-49
4.4-3	Beam Builder Preliminary Design & Performance Data	4-60
5.1-1	Detail Construction Requirements for First Mission	5-3
5.3-1	Tri-Beam Cable Pretension Loads	5-26
5.4-1	Orbiter Housekeeping Time Requirements	5-41
5.4-2	Key Assumptions & Estimating Procedures for Power Demand/Energy Analysis - First Mission	5-46
5.4-3	Total Energy & Average Power - First Mission	5-49
5.4-4	Construction Support Equipment Usage - First Mission	5-62
5.4-5	Flight Support Equipment Categories for First Construction Mission	5-63
5.5-1	Cargo Manifest Weight Summary	5-65
6.1-1	Construction Requirements - Second Mission	6-3
6.4-1	Total Energy & Average Power - Second Mission	6-25
6.5-1	Cargo Manifest Weight Summary	6-29
7.1-1	Construction Requirements for the Third Mission	7-3
7.4-1	Total Energy & Average Power - Third Mission	7-13
7.5-1	Cargo Manifest Weight Summary	7-19



<u>Table</u>		<u>Page</u>
8.1-1	Summary of Mission Time Required to Perform Basic Construction Missions	8-1
8.1-2	Mission Time Analysis for Construction - First Mission	8-2
8.1-3	Mission Time Analysis for Construction - Second Mission	8-2
8.1-4	Mission Time Analysis for Construction - Third Mission	8-3
8.1-5	Summary of Construction Power and Energy - Basic Construction Missions	8-3
8.4-1	Equipment Usage as a Function of Mission	8-11
8.6-1	Uncertainty Issues	8-21
9.2-1	Design Drivers Summary	9-3



## 1.0 INTRODUCTION

This report presents the system analyses of space construction which were performed as Task 8 of Part 2 of the contract study, Space Construction System Analysis (Contract NAS9-15718). Closely associated with this task effort is the design effort to define a model project called the Engineering and Technology Verification Platform (ETVP). The design studies and definition of this platform described in a separate companion report, which will be referenced herein where appropriate (Reference 1-1).

### 1.1 PURPOSE AND SCOPE

This report describes the construction methods and results specific to the end-to-end construction process derived for building the ETVP in low earth orbit, using the Space Shuttle Orbiter as a construction base. The majority of analyses concern three missions required to build the basic platform. However, consideration is also given to later orbiter missions which will update and revise payloads in low earth orbit and will install propulsion units for transfer of the platform to geosynchronous orbit under its own guidance. Provisions are also included for servicing and changeout of payloads in geosynchronous orbit using a teleoperator vehicle. However, details of such operations are not developed herein. Design features of the platform are discussed only in regard to construction requirements.

### 1.2 STUDY METHOD

The system analysis study approach was based on postulating a design concept for a specific construction project (the ETVP), then developing a logical plan for performing the construction within realistic constraints and cost minimization considerations. As the study proceeded, selected design changes and detail definitions of hardware concepts were developed to accommodate or facilitate specific construction processes and/or equipment. This iterative study process, which has been previously described in Rockwell reports (Reference 1-2), is illustrated in Figure 1.2-1. The detail design and construction analysis process proceeded in chronological sequence, mission by mission, from initiation of construction through checkout, with foreknowledge of expected needs and techniques from previous studies in Part 1 of this study contract (References 1-2 through 1-6). Selected major construction steps were analyzed and documented as separate activities including power, time and crew requirements. These data packages, described later in Section 5.3, formed a core of information for an end-to-end integration of each mission, incorporating additional requirements for lighting, television, power, crew rest and ingress-egress periods. The results of these analyses were summarized in terms of integrated timelines, power profiles, energy requirements and construction equipment needs.




Figure 1.2-1. Iterative Construction Process

In parallel with the analyses of on-orbit construction, trajectory analyses were conducted to determine time from launch to beginning of construction, on-orbit delays for entry opportunities and the descent/landing time. Such data formed the basis for overall mission consumables requirements, total launch weight estimates and relative costs. Details of these analyses are described later.

### 1.3 ORGANIZATION OF CONTENTS

The book is organized with the general philosophy of first presenting requirements, then analyses, then a summary of results. Section 2.0 provides overall, general construction requirements and those related to the platform design concept. Section 3.0 presents the general strategy selected for construction. Section 4.0 provides specific guidelines and assumptions, divided according to mission phases, and functions of the orbiter, crew and construction equipment. Sections 5.0 through 7.0 describe the analyses for each of the construction missions. The content of these sections has a common format, describing the overall construction plan, individual construction processes, integration analyses and the cargo manifest.

A composite summary of the overall construction project activity including the construction system/equipment definition, corresponding resource requirements, orbiter mods and platform servicing operations related to the construction system design is presented in Section 8.0. Section 9.0 summarizes the conclusions and recommendations.

Three appendixes are provided. The first (Appendix A) contains copies of design drawings which are specific to construction equipment and techniques. Appendix B contains copies of all the Construction Activity Data Sheets which provide details on what is done, sketches of hardware concepts, and estimates of time, power and energy for key equipment items. Also noted therein is an indication of crew workload. Appendix C presents the detail mass properties summary tables for each of the three construction missions.

References are listed as appropriate at the end of each major section (e.g., 1.0, 2.0, 3.0, etc.), and are numbered in a separate sequence for each section.

### 1.4 REFERENCES

- 1-1 Space Construction System Analysis, Part 2 report, Platform Definition, SSD 80-0037, Rockwell International, March 1980
- 1-2 Space Construction System Analysis, Project Systems and Mission Descriptions, Task 1 Final Report, SSD 79-0077. Rockwell International, Satellite Systems Division, 26 April 1979
- 1-3 Space Construction System Analysis, Task 2 Final Report, System Analysis of Space Construction, SSD 79-0123, Rockwell International, Satellite Systems Division, June 1979

- 1-4 Space Construction System Analysis, Task 3 Final Report,  
Construction System Shuttle Integration, SSD 79-0124,  
Rockwell International, Satellite Systems Division, June 1979
- 1-5 Space Construction Data Base, SSD 79-0125, Rockwell International,  
Satellite Systems Division, June 1979
- 1-6 Space Construction System Analysis, Special Emphasis Studies,  
Final Report, SSD 79-0126, Rockwell International, Satellite  
Systems Division, June 1979



## 2.0 CONSTRUCTION REQUIREMENTS

Specific construction requirements were established for both the platform configuration and for the construction activities. These requirements are discussed in the following sections.

### 2.1 PLATFORM CONFIGURATION REQUIREMENTS

From the previous Part I analysis, a linear platform configuration was determined to be the easiest configuration to construct and was structurally adequate to perform as a communications platform. Consequently, a linear platform was utilized as the model for the construction analysis.

The primary structure was required to be assembled from beams fabricated by the automatic beam fabrication device—beam builder—being developed by the General Dynamics Corporation. The structure would utilize lap joints, rather than butt joints, to simplify the construction process. The material thickness would be defined by a structural analysis, and variations from the basic GD beam fabricated from the beam builder would be coordinated with GD to verify the feasibility of producing the required beam size.

The crossbeams of the platform will be located in a common plane rather than being staggered. This requirement is imposed because it reduces the size of the construction fixture, reduces the time of construction, and minimizes the complexity of installing the diagonal cord members.

The platform was sized to accommodate communications antennas up to 20 m in diameter. The platform configuration must also be sized to be within the reach envelope of the orbiter RMS. The combination of these requirements was instrumental in determining the length of the long crossbeams to which the payloads are mounted and also the distance between crossbeams - bay spacing.

All of the electrical lines distributing power to the payload attach ports, RMS modules, and orbit transfer propulsion modules interface will be run along only one of the longitudinal members. Data distribution lines will also be run along the same member with sufficient spacing to prevent EMI interference. This will concentrate the wire laying activity in one location, thus minimizing the installation effort and equipment required to perform this function.

A system control module (SCM) was required to house all of the systems necessary to operate the platform. This module will include the solar array power generation, the power regulation and distribution electronics, and the power storage battery system. GN&C controls, sensors, and CMG's would also be included as well as the TT&C system. This requirement concentrates all of the systems into a single module that can be installed as an integral unit. This requirement also provides a single location for servicing and maintenance of the

equipment. All of the systems would be packaged into LRU modules. These modules would be configured for removal and replacement by the orbiter RMS in LEO and by remote or manned servicing vehicles in GEO.

In addition to platform systems servicing provisions are also required for LEO and GEO servicing of the payloads. LEO servicing will be accomplished via the orbiter RMS and cherry picker while berthed to the construction fixture. GEO servicing provisions must be compatible with both remote and manned concepts.

Implementation of these requirements resulted in the platform configuration described in detail in the Engineering Test and Verification Platform Definition (Section 3.0 of Reference 2-1).

## 2.2 CONSTRUCTION ACTIVITY REQUIREMENTS

The construction activity requirements considered both the construction system/equipment design and the construction/assembly processes. The principal activity requirements are as follows.

The platform shall be constructed from the orbiter as the construction facility. The orbiter shall provide all of the power and construction control and software necessary to perform the construction/assembly, and checkout operations.

All of the construction activities shall be performed in the immediate vicinity of the orbiter. This requirement permits the concentration of the construction equipment in one general location and allows the utilization of the orbiter facilities to support the operations. The opportunity to have direct visibility of the construction activities is also available.

The construction operations consider the utilization of the construction support equipment that is currently being developed and will be available in the late 1980's - the estimated period for construction. This includes such items as the beam builder, the manned remote work station (cherry picker), the manned maneuvering unit (MMU), and the RMS. As the construction analysis develops, recommended modifications to these items will be defined.

During construction a free-drift mode shall be utilized. Consequently, the orbiter will not be required to maintain a prescribed orientation; thus simplifying the orbiter operations and minimizing the utilization of expendables. Studies from Part I have verified the feasibility of performing construction in this mode.

The construction operations shall be arranged to minimize the time of construction. This requirement will reduce the time on orbit with the associated reduction of electrical energy, crew expendables and mission costs.

EVA shall be considered for those activities where increased construction effectiveness and/or construction system simplicities can be expected.



Where feasible, the direct visibility of the construction activities is desirable, rather than observing the activity via CCTV.

Between flights, contact with the project shall be maintained. The capability to stabilize the project for revisit berthing is required. The project must be stabilized within a residual rate of approximately 0.01-0.02 deg/sec. This rate permits the capture of the platform with the orbiter RMS.

Safety of the crew and of the orbiter shall be considered when deriving the construction activities.

The implementation of these requirements is reflected in the construction strategy (Section 3.0), and in the three construction missions (Sections 5.0, 6.0, and 7.0) of this report.

## 2.3 REFERENCES

- 2-1 Space Construction System Analysis, Part 2, Platform Definition, Final Report No. SSD 80-0037, Satellite Systems Division, Rockwell International, March 1980

### 3.0 CONSTRUCTION STRATEGY

The construction strategy for the ETVP was evolved from previous analyses during Part I of this study. The major construction strategy issues identified and the decisions which were made for the ETVP analysis concerning these issues are presented in this section. In general, it was found that construction strategy is inseparable from the design of the platform and the construction equipment as well as the mission operations scenario and the space environment. Also, the economics and logistics of Shuttle operations are major drivers in selecting construction strategy. The importance of these interactions is apparent in the following discussion.

#### 3.1 CONSTRUCTION FIXTURE SYSTEMS AND WORK PLACE GEOMETRY FACTORS

The principal concepts for space construction fixture systems were derived from earlier analyses of a space-fabricated communications platform design; they are listed and discussed below.

1. To the degree feasible, the platform will be constructed using the Space Shuttle orbiter as the major base of on-orbit operations (as compared to a separate, manned, on-orbit facility). This "going-in" decision was based upon the magnitude of the construction effort, size of the platform, and evaluational nature of the platform as a construction project and as a communications equipment platform. As will be brought out during the discussion of analyses, some base support functions were necessary for a construction fixture, which is left on orbit between orbiter visits.
2. The construction is to be performed during free-drift conditions, rather than using a stabilized platform concept. This decision was based on considerations of potential stress loads and equipment requirements for handling large objects during periods when thrusting would be required for stabilization, considerations of costs and complexity of control systems, weight, and volume requirements for RCS fuel during construction.
3. A compact work area is desirable in order to limit travel time of the principal construction equipment and EVA personnel, and to minimize power requirements for lighting. This led to the general concept of "bringing the work to the work place" (as in a factory assembly line) by mechanically moving the platform through a compact construction fixture.

The physical embodiment of this concept was envisioned as a primary construction fixture having multiple functions, as illustrated in Figure 3.1-1. Details of the various functions and the overall construction fixture deployment and operation are presented in later mission analyses discussions.






Figure 3.1-1. Station 1 Construction Fixture and Equipment

4. The benefits of automation available in automatic beam builder machines should be employed where feasible. Platform designs featuring long, uninterrupted beam spans take advantage of this capability and are compatible with Item 3.
5. Efforts to reduce mission time on orbit are likely to be cost effective since they minimize the amount of boiloff of cryogenic fuel, minimize the need for stowage volume and weight for crew supplies and breathing gas, minimize fuel for orbiter systems maintenance, and generally minimize daily on-orbit costs. As regards construction equipment, the basic strategy concept resulting was that automation and parallel operations should be used, where appropriate, to minimize construction time.

This concept is reflected in the developed construction system by utilization of two major construction stations, as illustrated in Figure 3.1-2. Transverse beam subassemblies are fabricated at Station No. 2; they are then transported to, and assembled, at Station No. 1 while additional transverse beams are being fabricated.

### 3.2 GENERAL CONSTRUCTION SEQUENCE GUIDELINES

The following general guidelines apply to setting up an effective construction sequence:

1. Set up construction fixture early in the project (probably first activity).
2. Construct basic structure prior to attaching subsystem modules and flexible items such as electrical power and signal lines. Note that paralleling electrical power and signal lines can be installed as a beam is fabricated and/or installed.
3. Consider thermal constraints on flexible plastic wire coverings, and other materials which might be brittle at low temperatures. Schedule for deployment during periods of solar heating when required (or provide thermal conditioning).
4. Install nickel-hydrogen batteries toward end of construction project, provide for thermal conditioning (radiator) at time of installation, and put them on line as soon as possible to avoid extended periods of storage in charged condition.
5. Deploy large area solar arrays as late as possible to avoid destabilizing influence of drag forces.
6. Install orbit transfer modules as the last installation to minimize boiloff of cryogenic propellants.




Figure 3.1-2. Construction Fixture Systems

7. It is desirable to manufacture all three longitudinal beams first to avoid the necessity of storing transverse beams and crossbeams and/or using two beam machines simultaneously.

### 3.3 OPERATIONS AND LOGISTICS CONSIDERATIONS

The overall construction strategy includes considerations of cost-effective use of orbiter and crew time on orbit, weight and volume carrying capacity, and constraints on power and total energy resources. The following general concepts were applied.

1. Minimizing time on orbit minimizes daily costs of orbiter operations and effectively utilizes the orbiter energy resources and cryogenic supplies. In general, crew utilization for construction is enhanced by multiple-shift operations. Therefore, the general strategy employed was to attempt to provide a maximum number of crew shifts per day with a minimum size crew, so as to supervise and monitor automated equipment and thus continue construction, maximizing machine time and serial EVA crew time each day.
2. To avoid weight and cost of storage racks on construction fixtures or other on-orbit facilities, the orbiter bay packaging should be selected to include only that equipment and material which can be utilized for construction during the given Shuttle flight.

Thus, the early missions must carry up the basic construction fixtures and structure fabrication materials, while later missions include equipment modules installed on the structure, checkout equipment, and payloads.

### 3.4 DESIGN-RELATED CONSIDERATIONS

An important consideration in planning the strategy for construction involves the detail design features of the platform itself which affect construction equipment design, assembly processes, power demand, and total energy. Table 3.1-1 lists several key design concepts which affect and interact with construction processes, and briefly summarizes the construction implications.

Table 3.1-1. Construction Implications of Design Features

FEATURE	CONSTRUCTION IMPLICATIONS
<p>BERTHING PORT DEVICES FOR INSTALLATION OF MAJOR SYSTEMS MODULES &amp; COMPONENTS.</p>	<ul style="list-style-type: none"> <li>• REQUIRES LOAD-SPREADING INTERFACE STRUCTURE BETWEEN BERTHING PORT RING AND BASIC STRUCTURE. ADDITIONAL STOWAGE AND ASSEMBLY FUNCTIONS REQUIRED FOR EACH PORT.</li> <li>• PROVIDES POSSIBILITY OF SOFT BERTHING FLY-IN INSTALLATION BY REMOTELY CONTROLLED VEHICLE OR DIRECT ATTACH BY RMS, CHERRY PICKER, OR OTHER MECHANISM.</li> <li>• PROVIDES MEASURE OF SELF-ALIGNMENT. INSTALLATION DEVICE MUST GIVE WAY/YIELD TO ACCEPT THIS FEATURE.</li> <li>• MODULES MAY BE INSTALLED DURING STRUCTURE ASSEMBLY OR LATER AS DESIRED OR APPROPRIATE.</li> </ul>
<p>ANTENNAS DESIGNED FOR SINGLE-POINT ATTACH TO BASIC STRUCTURE (BERTHING PORT), POWER, SIGNAL, ETC., CONNECTIONS INTEGRATED WITH ATTACHMENT. (SEPARATE FUNCTIONS WHICH OCCUR SHORTLY AFTER MECHANICAL ATTACHMENT).</p>	<ul style="list-style-type: none"> <li>• ANTENNAS HANDLED AS SINGLE MODULES FROM LOADING INTO ORBITER THROUGH INSTALLATION TO SPACECRAFT STRUCTURE.</li> <li>• CONSIDERATIONS OF INSTALLING LARGE MODULES APPLY.</li> <li>• DEPLOYMENT FOLLOWS INSTALLATION TO BASIC STRUCTURE.</li> <li>• CONCEPT IS ESSENTIAL FOR SUCCESS IN GEOSYNCHRONOUS, REMOTELY CONTROLLED INSTALLATION.</li> </ul>
<p>RCS UNITS DESIGNED FOR SINGLE-POINT ATTACH TO BASIC STRUCTURE.</p>	<ul style="list-style-type: none"> <li>• RCS UNITS HANDLED AS SINGLE MODULES.</li> <li>• CONSIDERATIONS OF INSTALLING LARGE MODULE APPLY.</li> </ul>
<p>BEAMS FORMED OF SPACE-FABRICATED MATERIAL BY AUTOMATIC MACHINE</p>	<ul style="list-style-type: none"> <li>• REQUIRES DEVICES TO HOLD AND POSITION MACHINE AND BEAMS, TRANSLATE AND TRANSPORT BEAMS AND BEAM BUILDER MACHINE.</li> <li>• PROVIDES POSSIBILITY OF CONTROLLING CONFIGURATION BY SOFTWARE INPUTS TO BEAM BUILDER MACHINE.</li> <li>• FAVORS AUTOMATIC INSTALLATION OF END FITTINGS, JOINT FITTINGS, WIRES, AND SPECIAL REINFORCEMENT FEATURES.</li> <li>• REQUIRES MEANS TO JOIN BEAMS TO FORM STRUCTURES.</li> </ul>
<p>LONG, NARROW TRUSS WORK STRUCTURE CONFIGURATION OF PLATFORM</p>	<ul style="list-style-type: none"> <li>• FAVORS UNINTERRUPTED LONGITUDINAL BEAM FABRICATION.</li> <li>• REQUIRES MEANS TO TRANSLATE STRUCTURE WITH RESPECT TO CONSTRUCTION FIXTURE.</li> </ul>
<p>MULTIPLE ELECTRICAL CABLE CONNECTIONS, CROSS-BRACE CORD INSTALLATION AND TENSIONING</p>	<ul style="list-style-type: none"> <li>• FAVORS DIRECT MANUAL OPERATION (EXTRAVEHICULAR ACTIVITY).</li> </ul>

## 4.0 GUIDELINES AND ASSUMPTIONS

This section describes guidelines and assumptions significant to the planning and end-to-end analyses of the construction operations and equipment.

### 4.1 PRELAUNCH, ASCENT, RENDEZVOUS, BERTHING, DEORBIT, AND ENTRY FUNCTIONS

Prelaunch and ascent functions significantly affect how much and in what way construction equipment and materials are carried aboard the orbiter, their accessibility for construction, and their deployment requirements. Also affected are crew activity timelines and planning for consumables. Therefore, considerations of guidelines and assumptions relative to these functions, as accomplished with the orbiter, is pertinent to the overall system analysis of space construction. Similar considerations apply also to deorbit and entry functions which are also discussed here.

#### 4.1.1 Payload Bay Packaging

Table 4.1-1 lists pertinent guidelines and assumptions relative to cargo bay packaging for space construction.

Table 4.1-1. Guidelines and Assumptions for Payload Bay Packaging

- Cargo center-of-mass locations must be compatible with requirements of Volume XIV (Reference 4-1).
- EVA access space in the forward portion of the payload bay may be obstructed by stowed cargo items if emergency provisions are included for remotely controlled jettisoning or removal of such obstructions.
- Provisions must be incorporated to permit rendezvous with the construction fixture and berthing of the primary construction fixture to the orbiter's berthing facility.
- Emergency provisions for jettisoning must be included for any deployable modules or equipment which could obstruct closing of payload bay doors by failure to be stowed or retracted.
- Packaging should be designed to permit ready access to equipment and materials as needed for construction.
- Packaging shall permit stowage of return cargo so as to be compatible with c.g. location limits per Volume XIV (Reference 4-1).

#### 4.1.2 Flight Performance

Ascent and descent trajectory data are presented in order to establish complete mission profiles for the end-to-end construction analysis. These are representative data based on current preliminary orbiter operating rules and procedures. In some cases judgemental logic was applied to select typical values for parameters which could vary over a range of high and low extremes, e.g., ascent phasing, pre-entry thermal conditioning, etc.

Typical ascent trajectory data characteristics are illustrated in Figure 4.1-1. It is noted that the load factor is limited to 3 g by means of orbiter engine throttling.




Figure 4.1-1. Typical Mission Ascent Trajectory Data

For all except the first mission, the ascent profile will be that in which the orbiter must rendezvous and berth with the construction fixture/platform assembly. The timeline development for this type of mission is considered first.

The Space Shuttle trajectory is optimized for *intact abort* capability. This provides an abort-once-around (AOA) capability at the time the return-to-launch-site (RTLS) capability is lost.

As part of the nominal mission profile mission, the orbiter is always initially injected into a 93x182-km elliptical orbit. At the apogee of this orbit, an OMS circularization burn is performed to place the orbiter in a more stable 182-km circular orbit. Any necessary phasing and orbiter checkout with ground stations are performed at this altitude.

The phasing requirements depend on mission geometry at launch and on the target orbit altitude. This relationship is illustrated in Figure 4.1-2 for the worse-case geometry. However, it is felt that considerably shorter phasing periods will actually be required as launch time will be completely arbitrary. It is assumed that 50% of the maximum phasing time is more than adequate for construction mission planning purposes.




Figure 4.1-2. Total Maximum Phasing Time

After completion of necessary phasing and/or checkout of the orbiter, a go-ahead is given to proceed to the mission altitude. This ascent scenario does not preclude missions where direct ascent-to-mission altitude is performed without going through the intermediate 182-km circular parking orbit. Such missions obviously shorten the time from liftoff to insertion in the mission orbit, but affect the mission planning analysis only in a superficial manner.

#### Reference Ascent Profile

A typical profile timeline for a rendezvous mission with an arbitrary 12-hour phasing is presented in Table 4.1-2.

A detailed description of the activity in each phase follows.



Table 4.1-2. Mission Ascent Timeline  
(Rendezvous with 12-hr Phasing)

MISSION PHASE SUBPHASE EVENT/OPERATION	MISSION G.E.T.	DURATION	REMARKS & COMMENTS
● POWERED ASCENT			
MATED ASCENT			
LIFTOFF	00 00 00	00 00 00	
CLEAR LAUNCH TOWER	00 00 05	00 00 00	LAUNCH TOWER IS ASSUMED TO BE IN HEIGHT
PERFORM PITCH PROGRAM (TRAJ. SHAPING)	00 00 05	00 00 10	
MAXIMUM DYNAMIC PRESSURE	00 00 54	00 00 00	
WATER BOILER ACTIVATION	00 01 45	00 00 00	30 km ALTITUDE- UP TO THIS POINT NO ACTIVE COOLANT LOOP
SRB TAILOFF	00 01 53	00 00 05	
SRB-ORBITER/ET SEPARATION			
BEGIN ORBITER TVC	00 02 00	00 00 00	
INITIATE SRB STAGING SEQUENCE	00 02 03	00 00 00	
SRB JETTISON	00 02 05	00 00 00	
ORBITER/ET ASCENT			
VERIFY ENGINE THRUST	00 02 06	00 00 04	
REACH 3G	00 07 13	00 00 00	
ORBITER MAIN ENGINE CUTOFF (MECO)	00 08 04	00 00 00	
ORBITER-ET SEPARATION			
OPEN FORWARD RCS COVERS	00 08 04	00 00 22	
ET STRUCTURAL RELEASE	00 08 26	00 00 00	
PERFORM RCS SEPARATION ELEV	00 08 26	00 00 08	
ORBITER MANEUVER (RCS) TO OMS BURN ATTITUDE AND COAST	00 08 34	00 00 15	
● INITIAL ORBIT INSERTION			
PERFORM OMS BURN	00 08 49	00 01 06	
PERFORM MPS LO2 DUMP	00 08 59	00 02 30	
ORBIT INSERTION-OMS SHUTDOWN	00 09 55	00 00 00	INSERTION ORBIT IS 50 x 100 N.MI 93 x 182 km
● COAST TO APOGEE			
DISARM OMS-VERIFY ORBIT INSERTION PARAMETERS	00 09 55	00 00 15	
SELECT ORBITAL RATE MODE	00 10 10	00 00 10	
PURGE MPS ENGINE	00 11 39	00 00 10	
PERFORM MPS LH2 DUMP	00 11 49	00 00 40	
VERIFY MPS DUMP COMPLETE	00 12 29	00 00 10	
SECURE MPS ENGINE	00 12 39	00 00 15	
POSITION MPS ENGINE FOR DEORBIT	00 12 54	00 00 30	
DEACTIVATE APU'S	00 13 24	00 00 15	
OPEN PAYLOAD BAY DOORS	00 13 51	00 04 00	
ACTIVATE PAYLOAD MONITORING AND CONTROL FUNCTION	00 14 01	00 00 30	MAY HAVE TO BE DE- LAYED UNTIL AFTER CIRCULARIZATION

Table 4.1-2. Mission Ascent Timeline (Cont.)  
(Rendezvous with 12-Hour Phasing)

MISSION PHASE SUBPHASE EVENT/OPERATION	MISSION G.E.T.	DURATION	REMARKS & COMMENTS
INITIALIZE STAR TRACKERS	00 14:30	00 00 10	
SELECT WIDE DEADBAND	00 14:40	00 00 10	3.0 DEG. DEADBAND
ORIENT TO TARGET STAR FIELD	00 15:00	00 03 00	
PERFORM IMU ALIGNMENT	00 18:00	00 15 00	
ACTIVATE RADIATOR COOLING	00 19:10	00 00 00	
● CIRCULARIZATION			
ORIENT TO OMS BURN ATTITUDE	00 24 18	00 03 00	
SELECT INERTIAL ATTITUDE HOLD	00 27 18	00 00 10	1.0 DEG. DEADBAND
PERFORM PRETHRUST FUNCTION	00 30 00	00 02 00	
SELECT NARROW DEADBAND	00 33 38	00 00 10	0.5 DEG. DEADBAND
ENABLE ENGINE IGNITION CIRCUIT	00 33 48	00 00 10	
PERFORM OMS BURN $\Delta V = 91 \text{ fps}$ $= 28 \text{ m/s}$	00 34 18	00 00 56	RESULTANT ORBIT IS 182 x 182 km. 100 x 100 N.MI (Start Phasing) 12 HRS
POST THRUST FUNCTIONS	00 36 00	00 00 30	
NULL RESIDUAL VELOCITY	00 38 00	00 00 10	
DISABLE ENGINE IGNITION CIRCUIT	00 39 00	00 00 15	
SELECT WIDE DEADBAND	00 40 00	00 00 10	
● ORBIT AND P.L. CHECKOUT WITH GROUND STATIONS	00 43 00	03 45 00	
PERFORM IMU ALIGNMENT	03 00 00	03:03:00	
PLANE CHANGE (IF REQUIRED)	03 10 00		
PERFORM IMU ALIGNMENT	10:21:38		
PERFORM PHASING CORRECTION (IF REQUIRED)	11:06:08		
OMS burn attitude maneuver	12:24:k8	00:03:00	

Table 4.1-2. Mission Ascent Timeline (Cont.)  
(Rendezvous with 12-Hour Phasing)

MISSION PHASE SUBPHASE EVENT/OPERATION	MISSION G.E.T.	DURATION	REMARKS & COMMENTS
OMS BURN HEIGHT MANEUVER 1 $\Delta V = 246 \text{ fps} = 75 \text{ m/sec}$	12:34:18	00:05:00*	RESULTANT ORBIT is 100 x 240 N.MI
OMS BURN ATTITUDE MANEUVER	10:09:35	00:03:00	182 x 444 km
1st COELLIPTIC BURN $\Delta V = 244 \text{ fps} = 74 \text{ m/s}$	13:19:35	00:05:00*	RESULTANT ORBIT IS 240 x 240 N.MI 444 x 440 km
OMS BURN ATTITUDE MANEUVER	15:31:20	00:03:00	
CORRECTIVE COMBINATION BURN $\Delta V = 21 \text{ fps}$ 6.4 m/sec	15:41:20	00:00:26*	
OMS BURN ATTITUDE MANEUVER	16:08:20	00:03:00	
2nd COELLIPTIC BURN $\Delta V = 21 \text{ fps}$ 6.4 m/sec	16:18:20	00:00:26*	
START RENDEZVOUS PHASE	16:18:50	03:02:45	
TPI ATTITUDE MANEUVER	17:09:50	00:03:00	
TPI BURN	17:19:50		
1st BRAKING BURN	17:51:20		SIX BREAKING MAN- EUVERS $\Delta V \approx 1.5$ m/sec each
LAST BRAKING GATE	17:56:05		30 m from target
HARD DOCK	18:21:35		ORBIT ALTITUDE IS 250 x 250 N.MI 463 x 463 km
START OPERATIONS	19:21:35		

\* SINGLE OMS ENGINE BURN

	<u>PHASE START G.E.T.</u>			<u>PHASE DURATION</u>		
	<u>HR</u>	<u>MIN.</u>	<u>SEC</u>	<u>HR</u>	<u>MIN.</u>	<u>SEC</u>
1. ASCENT TO INSERTION	00	00	00	00	09	55

The Shuttle launch is assumed to occur from KSC on an azimuth of 90°. The orbiter is launched into an initial orbit of 93×182 km with an inclination of 28.5 degrees. Solid rocket booster (SRB) staging is performed at 00:02:05 G.E.T. at an altitude of approximately 140,000 feet. The SRB is jettisoned to impact into the Atlantic Ocean approximately 117 nmi down range. Ascent of the mated orbiter/ET continues to main engine cutoff (MECO) at 00:08:04 G.E.T. The ET separation sequence requires 45 seconds from MECO to OMS ignition. The sequence consists of opening the forward RCS doors, activation of all thrusters, structural/plumbing/electrical orbiter/ET tie releases, translation of the orbiter away from the ET by means of an 8-fps RCS -Z, ΔV, a delta pitch maneuver, and OMS ignition. The dual OMS burn is of 44 seconds duration, sufficient to insert the orbiter into a 93×182 km orbit at 00:09:55 G.E.T.

	<u>PHASE START G.E.T.</u>			<u>PHASE DURATION</u>		
	<u>HR</u>	<u>MIN.</u>	<u>SEC</u>	<u>HR</u>	<u>MIN.</u>	<u>SEC</u>
2. COAST TO APOGEE	00	09	55	00	14	23

Main engine propellants trapped in the orbiter lines after ET separation are dumped—LOX first and then LH<sub>2</sub>—commencing shortly after OMS insertion burn ignition. Dumping, purging, and vacuum inerting the lines require 300 seconds. After the main valves have been closed, the APU's are shut down at 00:13:24 G.E.T. The star tracker and cargo bay doors are opened immediately after completing clearing of the MPS lines. The EGLSS water boiler is then deactivated and cooling is subsequently provided by the radiators.

### 3. IMU ALIGNMENT

An IMU alignment is performed next by maneuvering the orbiter sufficiently to acquire three star sightings. It is estimated that the alignment can be performed in three minutes. A navigation update is performed at any convenient time during this period using the one-way doppler technique and any available STDN station.

	<u>PHASE START G.E.T.</u>			<u>PHASE DURATION</u>		
	<u>HR</u>	<u>MIN.</u>	<u>SEC</u>	<u>HR</u>	<u>MIN.</u>	<u>SEC</u>
4. ORBIT CIRCULARIZATION	00	24	18	00	10	10

At 00:24:18 G.E.T., the orbiter maneuvers to OMS burn attitude. OMS ignition occurs at 00:34:18. The burn is a horizontal in-plane posigrade of 28 m/s, lasting 56 seconds, which circularizes the orbit at 182×182 km.

	<u>PHASE START G.E.T.</u>			<u>PHASE DURATION</u>		
	<u>HR</u>	<u>MIN.</u>	<u>SEC</u>	<u>HR</u>	<u>MIN.</u>	<u>SEC</u>
5. PHASING	00	34	18	11	50	00

After circularization, the orbiter commences a phasing period to reach the proper position for rendezvous initiation. No specific attitude constraints are imposed other than those necessary for thermal conditioning. An IMU alignment using the star trackers is performed preceding each course correction, and navigation updates are acquired by one-way doppler on a station-available basis. A plane change, if required to correct insertion errors, would be performed at 03:10:00 G.E.T.

An IMU alignment is made and, if necessary, a phasing correction maneuver is performed at 11:06:08 G.E.T.

#### 6. HEIGHT ADJUSTMENT

The orbiter commences to maneuver to the required OMS burn attitude for the first of four height adjustments at 12:29:18 G.E.T., ten minutes prior to OMS ignition. All of these four OMS burns are posigrade, performed heads down with the thrust/sector essentially in plane. A tabulation of these burns follows. All of these burns are made with a single OMS engine.

<u>Identification</u>	<u>Delta-V</u>	<u>Begin Attitude Maneuver</u>	<u>Ignition</u>	<u>OMS Duration</u>
Height	75 m/s	12:24:18	12:34:18	5:00
Coelliptic	74 m/s	13:09:35	13:19:35	5:00
Corrective	6.9 m/s	15:31:20	15:41:20	00:26
Coelliptic	6.4 m/s	16:08:20	16:18:20	00:26

On completion of the listed burns, the orbiter will have transferred from the 182-km phasing orbit to a 463-km circular orbit 18 km less than that of the target satellite. At the last OMS cutoff, the orbiter will be both behind and below the target at a line-of-sight distance of about 152 km.

	<u>PHASE START G.E.T.</u>			<u>PHASE DURATION</u>		
	<u>HR</u>	<u>MIN.</u>	<u>SEC</u>	<u>HR</u>	<u>MIN.</u>	<u>SEC</u>
7. RENDEZVOUS	16	18	20	01	37	45

Immediately subsequent to the last coelliptic OMS burn, the orbiter is maneuvered to an attitude with the -Z axis pointed forward in the general direction of the target. The rendezvous sensor is deployed, activated, and lock-on the target obtained as soon as possible. The estimated lock-on time is less than two minutes. The target is tracked until the range has decreased to about 50 km and a terminal-phase-initiate (TPI) OMS burn solution derived. At 17:09:50 G.E.T., the orbiter commences to maneuver to the TPI OMS burn attitude. The TPI burn attitude is such that the thrust vector is along the line of sight to the target and is timed to occur when the line of sight is 27 degrees above local horizontal. Subsequent to the TPI OMS burn at 17:19:50,



the orbiter is maneuvered to bring the braking axis and optical sight into line with the target inertial attitude hold and narrow deadband is commanded. The theoretical braking delta-V is 9 m/s. Braking is accomplished in six increments of about 1.5 m/s each, with the first at 17:51:20 G.E.T. Cross-axis corrections are applied at the astronaut's discretion and the total delta-V is estimated at 17 m/s. The last braking gate occurs at 17:56:05 G.E.T. and on completion the orbiter will have achieved a stationkeeping position about 30 m from the target.

	PHASE START G.E.T.			PHASE DURATION		
	HR	MIN.	SEC	HR	MIN.	SEC
8. BERTHING	17	56	05	00	25	30

On achieving stationkeeping, the ETVP is given a visual inspection to assure that berthing may proceed. The target attitude is such that the berthing port axis is about 45 degrees away from the sun. Berthing aids, such as closed-circuit TV cameras and the manipulator arms, are activated. With the manipulator arm extended, the orbiter next approaches close enough to grapple the target. The fixture/platform assembly will have been stabilized by a libration damping system which is initiated by ground command at an appropriate time prior to launch of the orbiter. The attitude control systems of both the target and the orbiter are then commanded free and the manipulator arm is employed to assist in achieving a hard berth at 18:21:35 G.E.T. A special energy absorbing system may be required in the RMS mechanism or the end effector, unless very slow relative velocities can be assured at time of grapple. However, at this time it is assumed that use of the standard RMS end effector will be feasible. After berthing, the orbiter switches to wide deadband inertial attitude hold. Berthing aids are deactivated and stowed. Berthing has been timed to occur in sunlight although this does not negate use of floodlights to fill shadows.

The RMS is assumed capable of drawing the orbiter and fixture/platform together in order to perform a hard mechanical latching and electrical connection at the base of the construction fixture.

#### Ascent Timeline

The ascent timeline without rendezvous is essentially the same (see Table 4.1-3). It is assumed that orbiter and any payload checkout with ground stations will still be performed in the 182-km circular orbit before the transfer maneuver to the mission orbit is initiated. The orbiter achieves the 463-km circular mission orbit 5 hours, 45 minutes, and 20 seconds after launch.

Table 4.1-3. Mission Ascent Timeline without Rendezvous

MISSION PHASE SUBPHASE EVENT/OPERATION	MISSION G.E.T	DURATION	REMARKS & COMMENTS
● POWERED ASCENT			
MATED ASCENT			
LIFTOFF	00 00 00	00 00 00	
CLEAR LAUNCH TOWER	00 00 05	00 00 00	LAUNCH TOWER IS ASSUMED TO BE 90 METERS IN HEIGHT
PERFORM PITCH PROGRAM (TRAJ.SHAPING)	00 00 05	00 00 10	
MAXIMUM DYNAMIC PRESSURE	00 00 54	00 00 00	
WATER BOILER ACTIVATION	00 00 45	00 00 00	30 km ALTITUDE UP TO THIS POINT NO ACTIVE COOLANT LOOP
SRB TAILOFF	00 01 53	00 00 05	
SRB-ORBITER/ET SEPARATION			
BEGIN ORBITER TVC	00 02 00	00 00 00	
INITIATE SRB STAGING SEQUENCE	00 02 03	00 00 00	
SRB JETTISON	00 02 05	00 00 00	
ORBITER/ET ASCENT			
VERIFY ENGINE THRUST	00 02 06	00 00 04	
REACH 3G	00 07 13	00 00 00	
ORBITER MAIN ENGINE CUTOFF (MECO)	00 08 04	00 00 00	
ORBITER-ET SEPARATION			
OPEN FORWARD RCS COVERS	00 08 04	00 00 22	
ET STRUCTURAL RELEASE	00 08 26	00 00 00	
PERFORM RCS SEPARATION ELEV	00 08 26	00 00 08	
ORBITER MANEUVER (RCS) TO OMS BURN ATTITUDE AND COAST	00 08 34	00 00 15	
● INITIAL ORBIT INSERTION			
PERFORM OMS BURN	00 08 49	00 01 06	
PERFORM MPS LO2 DUMP	00 08 59	00 02 30	
ORBIT INSERTION-OMS SHUTDOWN	00 09 55	00 00 00	INSERTION ORBIT 50 x 100 N.MI 93 x 182 km.
● COAST TO APOGEE			
DISARM OMS-VERIFY ORBIT INSERTION PARAMETERS	00 09 55	00 00 15	
SELECT ORBITAL RATE MODE	00 10 10	00 00 10	
PURGE MPS ENGINE	00 11 39	00 00 10	
PERFORM MPS LH2 DUMP	00 11 49	00 00 40	
VERIFY MPS DUMP COMPLETE	00 12 29	00 00 10	
SECURE MPS ENGINE	00 12 39	00 00 15	
POSITION MPS ENGINE FOR DEORBIT	00 12 54	00 00 30	
DEACTIVATE APU'S	00 13 24	00 00 15	
OPEN PAYLOAD BAY DOORS	00 13 51	00 04 00	
ACTIVATE PAYLOAD MONITORING AND CONTROL FUNCTION	00 14 01	00 00 30	MAY HAVE TO BE DE- LAYED UNTIL AFTER CIRCULARIZATION

Table 4.1-3. Mission Ascent Timeline without Rendezvous (Cont.)

MISSION PHASE SUBPHASE EVENT/OPERATION	MISSION G.E.T	DURATION	REMARKS & COMMENTS
INITIALIZE STAR TRACKERS	00:14:30	00 00 10	
SELECT WIDE DEADBAND	00:14:40	00 00 10	3.0 DEG. DEADBAND
ORIENT TO TARGET STAR FIELD	00:15:00	00 03 00	
PERFORM IMU ALIGNMENT	00:18:00	00 15 00	
ACTIVATE RADIATOR COOLING	00:19:10	00 00 00	
● CIRCULARIZATION			
ORIENT TO OMS BURN ATTITUDE	00:24:18	00 03 00	
SELECT INERTIAL ATTITUDE HOLD	00:27:18	00 00 10	1.0 DEG. DEADBAND
PERFORM PRETHRUST FUNCTION	00:30:00	00 02 00	
SELECT NARROW DEADBAND	00:33:38	00 00 10	0.5 DEG. DEADBAND
ENABLE ENGINE IGNITION CIRCUIT	00:33:48	00 00 10	
PERFORM OMS BURN $\Delta V=91$ fps 28 m/s	00:34:18	00 00	RESULTANT ORBIT IS 100 x 100 N.MI 182 x 182 km
POST THRUST FUNCTIONS	00 36:00	00 00 30	
NULL RESIDUAL VELOCITY	00 38:00	00 00 10	
DISABLE ENGINE IGNITION CIRCUIT	00 39:00	00 00 15	
SELECT WIDE DEADBAND	00 40:00	00 00 10	
● ORBIT AND P.L. CHECKOUT WITH GROUND STATIONS	00 43 00	03 45 00	
● ORBITER READY TO CONTINUE	04:28:00		
IMU ALIGNMENT	04:30:00	00:15:00	
OMS BURN ATTITUDE	04:45:00	00:03:00*	
OMS BURN $\Delta V=264$ fps 80 m/s	04:55:00	00:05:20*	RESULTANT ORBIT IS 100 x 250 n.mi 182 x 463 km
OMS BURN ATTITUDE	05:30:20	00:03:00*	
OMS BURN $\Delta V= 261$ fps 80 m/sec	05:40:20	00:05:20*	RESULTANT ORBIT IS 250 x 250 n. mi 463 x 463 km
● ORBITER IN MISSION ORBIT	05:45:20		


\*SINGLE OMS ENGINE BURN

#### Entry Timeline

The entry phase is comparatively simpler than the ascent phase. The major variable here is the need for thermal conditioning of the orbiter prior to entry. The maximum time for this phase is 12 hours (Figure 4.1-3). However, considerably shorter time periods have been employed in other analyses.

Entry timeline showing a five-hour thermal conditioning or barbecue phase is shown in Table 4.1-4. Note that the event times assume that completion of rollout is the reference time zero, and that the events are listed in reverse chronological order from top to bottom of the table. All times shown are from completion of the roll at touchdown. Just as for the ascent profile, the events are based on a nominal representative entry profile. A detailed description of the events occurring during this period follows.





$$\beta \text{ MAX} = \pm (i + 23.5), \text{ DEG.}$$

$\beta$ RANGE DEGREES	ORBITER ORIENTATION	HOLD CAPABILITY HOURS	PREENTRY THERMAL CONDITIONING REQUIREMENTS HOURS
0 TO 60	ANY	$\geq 160$	$\leq 12$
60 TO 90	A. OTHER THAN 3-AXIS INERTIAL HOLDS	CYCLES OF 6-HOUR HOLDS FOLLOWED BY 3 HOURS OF THERMAL CONDITIONING FOR WORST THERMAL ATTITUDES	$\leq 7$
	B. 3-AXIS INERTIAL HOLDS	$\geq 160$	$\leq 12$

Figure 4.1-3. Orbiter Attitude-Hold Capabilities

Table 4.1-4. Entry Timeline

Complete roll	00:00:00
Rollout	00:02:00
At 16000 ft 4.9 km	00:04:39
At 47000 ft 14 km	00:07:55
At 100000 ft 30 km	00:12:36
Entry 400000 ft 122 km	00:38:07
Entry burn	01:11:35
Maneuver to burn attitude	01:21:35
IMU Alignment	01:36:35
Thermal Conditioning Mode	06:36:35
IMU Alignment	06:20:35
RCS Maneuver $\Delta V = 1$ m/s	08:06:35
Separation (undocking)	08:26:35

	PHASE START G.E.T.			PHASE DURATION		
	HR	MIN	SEC	HR	MIN	SEC
1. SEPARATION	08	26	35	01	50	00

After completion of operations, unberthing occurs at 08:26:35 and is accomplished with use of the manipulator arm. After release of the manipulator arm from construction fixture, a minimal RCS pulse is used to start the orbiter moving away from the platform. At 08:06:35, the orbiter RCS jets are used to generate a posigrade  $\Delta V$  of 1 m/s. During the ensuing revolution the orbiter first moves ahead, then above, and then drifts behind the platform a distance of about 15 km. During this drifting-away period, visual observation of the platform is maintained. The IMU is aligned using the star trackers at a convenient time during this period, and the state vector is updated using the one-way doppler technique and any available STDN station.

	<u>PHASE START G.E.T.</u>			<u>PHASE DURATION</u>		
	<u>HR</u>	<u>MIN</u>	<u>SEC</u>	<u>HR</u>	<u>MIN</u>	<u>SEC</u>
2. THERMAL CONDITIONING	06	36	35	05	15	00

All loose equipment is secured and stored, and fuel cell water is dumped. If necessary, the orbiter may be operated in a thermal barbecue mode for up to 12 hours at the end of this phase to minimize thermal gradients. A five-hour barbecue mode is shown here. The orbiter is next configured for deorbit including closing of cargo doors, forward RCS doors, and star tracker's protective doors. The APU's are activated for two minutes and the aerosurface controls checked.

	<u>PHASE START G.E.T.</u>			<u>PHASE DURATION</u>		
	<u>HR</u>	<u>MIN</u>	<u>SEC</u>	<u>HR</u>	<u>MIN</u>	<u>SEC</u>
3. DEORBIT	01	21	35	00	43	28

At 01:21:35, the orbiter maneuvers to the deorbit burn attitude, retrograde, heads-down. A single OMS engine is used with ignition at 01:11:35. Burn time is 411 seconds and resultant  $\Delta V$  is 110 m/s. The orbiter is then maneuvered to a heads-up, nose-first, pitch-up attitude specified for entry interface.

	<u>PHASE START G.E.T.</u>			<u>PHASE DURATION</u>		
	<u>HR</u>	<u>MIN</u>	<u>SEC</u>	<u>HR</u>	<u>MIN</u>	<u>SEC</u>
4. ENTRY	00	38	07	00	30	12

The orbiter passes through 122 km altitude at 00:38:07. The APU's are activated and aero surfaces powered. Throughout the remainder of the entry the GN&C steers to reach the landing site and controls to minimize accelerations and thermal heating. The ammonia boiler is activated as the orbiter passes through 30 km altitude at 00:12:36. Entry is completed as the orbiter passes over the minimum energy point (MEP) at approximately 14 km altitude at 00:07:55.

	<u>PHASE START G.E.T.</u>			<u>PHASE DURATION</u>		
	<u>HR</u>	<u>MIN</u>	<u>SEC</u>	<u>HR</u>	<u>MIN</u>	<u>SEC</u>
5. DESCENT	00	07	55	00	03	16

The orbiter maneuvers as it descends under control based on terminal area energy management (TAEM). It acquires the projection of the final approach trajectory at approximately 4.9 km altitude at 00:04:39.

	<u>PHASE START G.E.T.</u>			<u>PHASE DURATION</u>		
	<u>HR</u>	<u>MIN</u>	<u>SEC</u>	<u>HR</u>	<u>MIN</u>	<u>SEC</u>
6. FINAL APPROACH	00	04	39	00	02	39

Final approach, like the descent, is entirely nominal.

	<u>PHASE START G.E.T.</u>			<u>PHASE DURATION</u>		
	<u>HR</u>	<u>MIN</u>	<u>SEC</u>	<u>HR</u>	<u>MIN</u>	<u>SEC</u>
7. ROLLOUT	00	02	00	00	02	00

Landing rollout is complete at 00:00:00.

	<u>PHASE START G.E.T.</u>			<u>PHASE DURATION</u>		
	<u>HR</u>	<u>MIN</u>	<u>SEC</u>	<u>HR</u>	<u>MIN</u>	<u>SEC</u>
8. POST-LANDING	00	00	00	00	13	00

GSO hookup requires 13 minutes to the point where the fuel cells may be shut down.

#### 4.2 ORBITER FUNCTIONS

The basic construction facility is assumed to be the Space Shuttle orbiter vehicle, together with modifications described later. The orbiter provides stabilization and control (as required to initiate construction), housekeeping functions, various mission support services (utilities), and accommodations for crew habitability, command, and control. Such functional capabilities have a significant impact on what can be built, how long it takes to build, what crew size can be used, and what costs of constructions may be incurred. Guidelines and assumptions pertinent to construction analysis are presented and discussed in the following sections.

##### 4.2.1 Stabilization and Control

It is assumed that the nominal construction periods will be conducted under free-drift conditions. That is, no active RCS firings by the orbiter or construction fixture will be considered. During the first mission, rotational rate control will be limited to that inherent in the final residual stabilization of the orbiter as it assumes its orbital position for construction. During the first mission and all later missions the rotational rates will also depend on the combination of mass properties, relative motions, and drag effects of the combined orbiter and platform as the platform is being constructed. Analysis was conducted during the first part of this space construction system analysis to establish typical rates and attitudes for a similar (but larger) platform. The results indicated a probability of slow libration rates, which appear to be acceptable for crew operations and construction activity (Reference 4-2). By similarity, such acceptable rates are assumed applicable for this analysis.

##### 4.2.2 Mission Support Services

In the concept for construction of the ETVP, it is assumed that the orbiter provides several essential support services—some directly applicable to construction, and some indirectly related. Table 4.2-1 lists these services and their uses in construction.

Table 4.2-1. Orbiter Support Services for Space Construction


SERVICE	SPACE CONSTRUCTION USAGE
<p>ELECTRICAL POWER</p> <ul style="list-style-type: none"> <li>• 7 kW MAXIMUM, CONTINUOUSLY</li> <li>• 12 kW FOR 15 MINUTES WITHIN 3-HR PERIODS</li> <li>• 28 VDC</li> </ul>	<p>OPERATE CONSTRUCTION MACHINERY, ELECTRICAL HEATERS, LIGHTS ON CONSTRUCTION EQUIPMENT, AND SENSORS; PROVIDE FOR CONTROL AND DATA HANDLING FOR CONSTRUCTION</p>
<p>ILLUMINATION</p> <ul style="list-style-type: none"> <li>• SEVEN 200-W LAMPS IN PAYLOAD BAY</li> <li>• ONE 200-W DOCKING LAMP</li> <li>• ONE 173-W RMS WRIST CAMERA</li> </ul>	<p>ASSIST IN LOCATING, GRAPPLING, TRANSPORTING, AND STOWING CONSTRUCTION EQUIPMENT AND MATERIALS; ASSIST INSPECTION AND CHECKOUT. POWER FOR THESE LIGHTS IS CHARGED TO PAYLOAD (CONSTR.) OPERATIONS.</p>
<p>CLOSED-CIRCUIT TV, CAMERAS, DISPLAYS, AND CONTROL SYSTEMS</p> <ul style="list-style-type: none"> <li>• RMS</li> <li>• FORWARD BULKHEAD</li> <li>• AFT BULKHEAD</li> </ul>	<p>ASSIST IN GUIDING RMS AND OTHER DEVICES, OBSERVING CONSTRUCTION PROCESSES; POWER FOR THE RMS TV's AND THEIR ASSOCIATED HEATERS AND TILT/PAN MECHANISMS IS CHARGED TO PAYLOAD.</p>
<p>ELECTRICAL SIGNAL WIRE PATHS AND SWITCHING CONTROL</p>	<p>CONSTRUCTION OPERATIONS COMMAND AND CONTROL, DATA RECORDING</p>
<p>RF COMMUNICATIONS</p>	<p>STATUS REPORTS TO GROUND; REMOTE CONTROL OF STABILIZATION AND CHECKOUT FUNCTIONS; EVA—CABIN COORDINATION &amp; SAFETY MONITORING</p>
<p>BREATHING OXYGEN, N<sub>2</sub> AND ATMOSPHERIC PRESSURE FOR CREW</p>	<p>SUPPORT CREW FOR IVA CONSTRUCTION OPERATIONS AND RECHARGE EMU PRESSURE SUITS, MMU</p>
<p>WATER (FROM FUEL CELLS)</p>	<p>WATER FOR CREW METABOLIC/ PHYSIOLOGICAL NEEDS; COOLING FOR CABIN</p>
<p>COMPUTATION</p>	<p>SUPPORT CONSTRUCTION OPERATIONS THROUGH EXECUTIVE CONTROL OF MICROPROCESSORS</p>
<p>GUIDANCE/NAVIGATION</p>	<p>INFORMATION ON ATTITUDE, ALTITUDE, AND ROLL RATES</p>

#### 4.2.3 Crew Accommodations

The crew accommodations in the Space Shuttle orbiter provide limited on-site living quarters for construction workers. For purposes of this analysis, the basic volume constraints, seating, and sleeping provisions outlined in Volume XIV (Reference 2) have been assumed. These assumptions are briefly summarized in Table 4.2-2. Figure 4.2-1 illustrates the configurations assumed as potential provisions for up to seven crew members. Figure 4.2-2 illustrates the configuration assumed for the aft flight deck.

Table 4.2-2. Crew Accommodation Assumptions for  
Space Construction using the Orbiter

Item	Assumption
Nominal crew seating—ascend	7
Baseline crew (weight allowance)	4
Baseline stowage capacity	28 man-days
Cabin nominal maximum stowage volume capacity	42 man-days
Cabin pressure, normal	14.7 psi (10.14 N/cm <sup>2</sup> )
Cabin atmosphere	20% O <sub>2</sub> , 80% N <sub>2</sub>
Galley	Installed
Hygiene accommodations	Installed
Nominal EVA storage	Two suits
Airlock—two-man capacity	Installed—internal configuration
Aft flight deck	Standard—workspace for 4 persons






Figure 4.2-2. Aft Flight Deck Configuration



### 4.3 CREW FUNCTIONS

The following guidelines and assumptions regarding crew functions relate primarily to the construction operations periods. The specific concerns are divided into those associated with the EVA and IVA physical situations, the timelines and procedures related to work/rest cycles, and those related to crew skills and assignments.

#### 4.3.1 EVA Requirements

This section describes guidelines and assumptions dealing primarily with hardware and supplies for EVA. Crew timelines for EVA are considered in Section 4.3.3. Table 4.3-1 lists the major pertinent guidelines and assumptions relative to EVA operations hardware and supplies. The major impact on this set of equipment may come from introduction of a high-pressure suit (8 psi). Such a suit may require additional volume for stowage as well as revisions for the higher pressures. Also, the larger than standard number of suits required to support three shifts of EVA operations almost certainly would require stowage provisions in the payload bay for suits. Each EVA egress could also include fetching one or more such suits and placing the suit(s) into the airlock prior to repressurization.

Table 4.3-1. Guidelines and Assumptions for  
EVA Construction Operations Hardware and Supplies

- Extra (more than two) EVA suits may be stowed in the payload bay and retrieved for use by the EVA person upon egress.
- If required, to extend stowage capacity, additional LiOH, food, and other supplies may be stowed in the payload bay and retrieved by EVA
- A standard orbiter airlock and plumbing shall be provided, located internally to the crew cabin. Selective modifications may be required for the use of high-pressure (8-psi) suits.
- Two crewmen may occupy the airlock at the same time while wearing high-pressure suits and associated portable life support systems.
- The airlock shall be closed and repressurized after egress by an EVA crew member, so as to permit suit doffing of a returned EVA crew member, and suit donning by the crew member scheduled for the next shift.
- Individually assigned suits shall be provided for each designated EVA crew member and his designated IVA or EVA backup crew member. Nominally, the IVA backup crew is the IVA crew person performing construction operations. However, alternate designations may be made—such as a separate standby IVA crew member prebreathing 100% oxygen, or an exterior EVA "buddy."
- Additional nitrogen tanks shall be supplied for multiple repressurizations above the nominal baseline orbiter provisions of two. Each tank set provides for 4.5 repressurizations.

Whenever possible, depressurization and repressurization cycles include one (or more) crew ingressing as well as one (or more) egressing in order to minimize demands for gas supplies.

Contingency operations involving EVA were not studied in this analysis. It is recognized that such studies would result in detail requirements for additional hand rails, tethers, foot restraints, and other mobility aids on the construction equipment and the flight support equipment.

#### 4.3.2 IVA Requirements

Guidelines and assumptions relative to physical provisions for intra-vehicular construction operations are listed in Table 4.3-2. Crew habitability accommodations guidelines and assumptions were included in Section 4.2.4.

Table 4.3-2. Guidelines and Assumptions for IVA  
Construction Operations Hardware and Supplies

- The IVA construction operations shall be conducted primarily in the aft flight deck of the orbiter crew cabin using standard window provisions, control and display consoles, crew restraints, and accommodations.
- Console space provisions and wiring options dedicated to payload operations shall be utilized for controls and displays unique to the construction operations. These may be different for each mission.
- The standard orbiter RMS controls and displays shall be modified as required to incorporate the upper arm roll joint capability and tilt/pan capability of the camera.

In general, this study identified no unusual requirements for the crew aft flight deck accommodations. However, detailed analyses of controls and displays requirements, microprocessors, and software programs were not undertaken. It is assumed that time-shared displays and controls can be utilized, since the construction processes tend to be grouped in serial phases of operations. Such an approach will reduce the need for extensive area dedicated to controls and displays for the many primary control and backup construction functions such as latches, heaters, checkout, lights, cameras, transporters, etc.

#### 4.3.3 Crew Work/Rest Cycles

This section deals primarily with guidelines and assumptions specific to developing timelines for crew work/rest cycles. The key items of concern are listed in Table 4.3-3. These include considerations of IVA and EVA operations and their interactions. Options are listed for using low-pressure suits (4 psi) or high-pressure suits (8 psi or equivalent, which requires no pre-breathing operations). Although the latter type of suit system is recommended and used as a baseline for analysis, it was felt useful to indicate the assumptions used for the selection.

Table 4.3-3. Guidelines and Assumptions for  
Crew Work/Rest Cycles During Construction

- The crew will follow a 16-hr awake/8-hr sleep cycle.
- The crew workday is normally 10 hours, but may be extended to 11 hours for a few days (3 or 4).
- There will be 3/4-hour per day schedule for pre-sleep and post-sleep activities (1-1/2 hours total).
- All crewmen will be awake for all major burns.
- The crew meal periods will be scheduled for one hour at least twice per day.
- No scheduled exercise is planned for flights less than one week's duration.
- Crewmen will sleep and work in shifts as required.
- Designated sleeping volumes may be serially occupied by different crew members during a 24-hour cycle of multi-shift operations. Sleeping bags may be personal equipment items, rolled and stowed by each crew member at end of each of his sleep periods.
- Scheduled IVA crew activities will be allotted a minimum of 5 minutes duration and rounded off to 5-minute increments.
- Orbiter housekeeping duties are assumed to require no more than two hours and twenty minutes per 24 hours.
- EVA and equipment-related activities are allotted a minimum of one minute increments.
- EVA crew will have an average of at least 10 minutes rest per hour, preferably after 45 to 50 minutes work, and 20 minutes for a lunch (candy bar).
- Cabin crew works when EVA crew is outside and coordinates breaks with EVA schedule.
- EVA by a single crew member shall be permitted. However, an IVA crew member shall be available at all times to engage in rescue operations.
- For pressure suit operations at 4 psi, prebreathing of 100% O<sub>2</sub> shall be required for three hours prior to egress.
- IVA backup (rescue) crew shall not breathe 100% oxygen for more than six hours on a regular daily basis.
- Crew members required to prebreathe oxygen will be supplied with walk-around oxygen equipment permitting voice communication and minimal interference with orbiter housekeeping duties. IVA operations of RMS or control/display panels can be performed while prebreathing.
- EVA crew wearing 4-psi pressure suits is limited to six hours of external operations per 24-hour period. Pre- and post-EVA procedures are per orbiter standards.

Table 4.3-3. Guidelines and Assumptions for  
Crew Work/Rest Cycles During Construction (Cont.)

- EVA suit donning and doffing are each allotted 1.5 hours (total of 3 hours per EVA) for all types of suits.
- For pressure suit operations at 8 psi (or approximately one-half the cabin atmosphere pressure), prebreathing of 100% O<sub>2</sub> is not required.
- EVA periods of 8 hours are permitted by use of higher capacity portable life support systems or umbilicals to on-site supplies when using 8-psi pressure suits.
- No assembly activities or EVA activities are performed during orbiter translation from one assembly location to subsequent location.

#### 4.3.4 Crew Assignments, Proficiency, and Training

Table 4.3-4 lists guidelines and assumptions pertinent to crew assignments for the subject space construction analysis.

Table 4.3-4. Assumptions Related to Crew Assignments

- Each mission will have a designated commander, pilot, and mission specialist trained to handle the respective functions for ascent, rendezvous, berthing separation, deorbit, entry, and landing.
- IVA crew members are cross-trained to perform all required IVA crew functions and EVA rescue operations for the mission.
- EVA crew members are cross-trained to perform all EVA functions required for the mission.
- All crew members are trained to perform routine orbiter housekeeping functions.
- All crew members are trained to perform some aspect of construction and are considered part of the normal space construction crew complement.

Discussion of crew assignments in regard to space construction tends to raise the general question of skills selection for such repetitive "blue collar" type of activity. There is a considerable amount of repetitive activity to be considered in this construction project. However, it is doubtful these repetitions are so extensive for any one shift of operations in this particular project as to be unacceptable for pilot-trained crew members. Hindsight available at the time of this writing reveals that very few shift operations are required for any given crew member. It is concluded that special effort to select crew personnel who are tolerant of extended repetitive effort is not justified. Skills in time management, understanding of electronics, and mechanics of the construction process are probably the most critical concerns. However, physical skills in handling tools and performing close-tolerance assembly are indeed essential for the EVA operations. Special skills and special training to develop proficiency in IVA operations of the RMS and EVA operation involving the cherry picker are also essential.

Therefore, minimization of training costs suggests that crew assignments should be coordinated with specific skills and training. It is assumed that such has been the case for these analyses.

In preparations for space construction operations, funds and equipment must be allocated for crew training to develop a reasonable degree of proficiency in specific construction skills and overall procedures. This training improves productivity and enhances crew safety. It has been assumed for the analyses described later that the crew has received such adequate training. Possible increases in productivity due to on-site learning gained during the mission have not been incorporated into the timeline analyses although strong evidence for such improvements has resulted from Skylab experience. It was felt that the current accuracy of timeline predictions did not justify such fine-tuning of estimates.

#### 4.4 BASIC CONSTRUCTION SUPPORT EQUIPMENT

The construction analysis is based upon use of certain basic, multi-purpose support equipment items (some with appropriate modifications) which are being developed, or at least seriously studied, as likely candidates for future space operations. The major items include a manned maneuvering unit (MMU), open cherry picker version of a manned remote work station (MRWS), remote manipulator system (RMS), and beam builder machine. These baseline items of equipment and system components are described in the following pages to provide a basic understanding of the intended performance capabilities and configurations, and the assumptions upon which later modifications for space construction are based.

##### 4.4.1 Manned Maneuvering Unit (MMU)

The MMU is being developed by the Martin Marietta Corporation. The data presented below have been taken from their Users' Guide for the MMU, dated May, 1978 (MCR 78-517, NAS9-14593).

##### General

The principal elements of the MMU (Figure 4.4-1) are its basic structure, a propulsion subsystem, two hand controllers, and a control electronics assembly (CEA). Twenty-four fixed-position thrusters utilizing gaseous nitrogen ( $\text{GN}_2$ ) provide full six-degree-of-freedom control by reacting to commands from the three-axis translational hand controller (THC) and the three-axis rotational hand controller (RHC). Electrical power is supplied to the MMU subsystems from two batteries mounted at the top rear of the unit between the  $\text{GN}_2$  pressure vessels. Command logic, power conditioning equipment, and gyroscopes are mounted in the control electronics assembly (CEA) located behind and below the batteries.

The MMU is a fail-safe system in that any single failure does not preclude the astronaut from returning safely to the orbiter vehicle. The thrusters are separated into two independent systems (12 thrusters each), each of which provides full six-degree-of-freedom control in the event of a failure in the other system. The control electronics are also redundant such that at least one set of 12 thrusters can always be commanded.




Figure 4.4-1. Manned Maneuvering Unit

In addition to the manual commands which are applied by the astronaut from the hand controllers, an automatic attitude hold (AAH) capability is also available. By activating a switch located on top of the RHC grip, the astronaut can command attitude hold and the MMU will maintain attitude in three axes of rotation by firing thrusters automatically, as required. Three rate gyros sense rotations and attitudes in each rotational axis, and the MMU control logic uses these data to command the thrusters. If rotational rates are already present when attitude hold is commanded, the control logic will fire thrusters to cancel those rates.

The two propellant tanks contain a total of 40 lb (18 kg) of  $\text{GN}_2$  at 4500 psia and 70°F, on initial charge on the ground prior to a mission. These pressure vessels are rechargeable during EVA by an unassisted crew member. The initial charge provides sufficient propellant for an equivalent  $\Delta V$  of 110 to 135 fps; subsequent recharges on orbit will provide a minimum equivalent  $\Delta V$  of 72 fps (36 fps per  $\text{GN}_2$  tank). The control logic of the MMU is designed to maintain fuel consumption from each tank at a relatively even level. In addition, the logic is designed to select the optimum combination of thrusters in order to conserve propellant when mass offsets are present or multiple axis commands occur simultaneously.

The MMU is stowed for launch and reentry in the Flight Support Station (FSS) located in the payload bay of the orbiter (Fig. 4.4-2). The FSS structure provides environmental protection to the MMU during launch, on-orbit (nonoperational) periods, reentry and landing. The FSS also contains the necessary attachment provisions, foot restraints and handholds for donning/doffing and servicing the MMU in orbit by an unassisted EVA crew member. One FSS can be mounted on each side of the payload bay so two MMU's can be carried on each orbiter flight.

#### Flight Characteristics

The maneuvering unit responds to direct manual commands input by the crew member via the two hand controllers. For a nominal system mass, translation accelerations are  $0.3 \pm 0.05 \text{ ft/sec}^2$  and rotational accelerations are  $10.0 \pm 3.0 \text{ deg/sec}^2$ . Since the MMU operates in a direct flight mode, these acceleration levels are present whenever either hand controller grip is displaced from the center or null position. Acceleration commands are terminated when the grip is returned to the center position. Simultaneous commands in several axes (multi-axis commands) are possible at reduced acceleration levels.

Each MMU thruster develops approximately 1.4 lb of thrust; therefore, single axis translation commands generate 5.6 lb of thrust in the normal operations mode, and 2.8 lb of thrust in the backup operations mode. Rotational torques are the same for the prime and backup modes. For multi-axis commands up to six thrusters can be firing simultaneously.

The automatic attitude hold (AAH) capability of the MMU allows the crew member to maintain attitude in any or all of the axes of rotation. The MMU control logic automatically fires thrusters as required to hold a position within a deadband of  $\pm 0.5$  to  $\pm 2.0$  degrees (premission selectable) in any rotational axis, as sensed by the rate gyros. Drift rates across this deadband (if, for example, the crew member is relatively still while inspecting or photographing a payload) are on the order of 0.02 deg/sec.




Figure 4.4-2. MMU/FSS Configuration in Payload Bay





In the AAH mode, highly developed control logic incorporating limb motion filters and limited minimum impulse thrust repetition rates allows a tight limit cycle deadband that is relatively insensitive to large crew member limb motions and is fuel conservative in the presence of the cyclic disturbance torques.

Three-axis attitude hold can be commanded during translation in any axis. Attitude hold can be inhibited independently in the roll, pitch or yaw axes when the crew member inputs via the RHC a manual rotation command in that axis.

Table 4.4-1 summarizes the flight characteristics of the MMU.

Table 4.4-1. MMU Flight Characteristics

- Six-Degrees-of-Freedom Control Authority
- Spacecraft-type Piloting Logic
  - 3-Axis Translational Controller (Left Hand)
  - 3-Axis Rotational Controller (Right Hand)
  - Independent or Multiple Axis Commands
  - Pulse or Continuous Commands
- Manual (Direct) Translation and Rotation Control
- Automatic Attitude Hold
  - Deadband Adjustable  $\pm 0.5$  to  $\pm 2.0^\circ$
  - Inertial Drift less than  $0.01^\circ/\text{sec}$
- Response
  - Translational Acceleration  $0.3 \pm 0.05 \text{ ft/sec}^2$
  - Rotational Acceleration  $10.0 \pm 3.0^\circ/\text{sec}^2$
- Audio Feedback for Thruster Operation

#### Operational Guidelines

Although the MMU cold gas propulsion system is essentially noncontaminating, the EMU life support system does vent water vapor to space (approximately one pound of water per hour). In almost all cases for specific payload operations, this level and type of contamination is well within acceptable limits.

The MMU cannot be effectively utilized as a stable platform from which large forces and torques can be exerted; that is, the MMU should not be considered a mechanism through which large forces or torques can be reacted to do

work. Additional restraints are required in such cases. The MMU can be utilized, however, to counter light loads such as might occur during simple tasks.

#### Work Site Aids/Ancillary Equipment

The MMU contains provisions to attach cargo or equipment for transport during maneuvers. These attachments allow the crewmember's hands to remain free to operate the MMU hand controllers. Three types of attachments are available. Telescoping, lockable arms with grappling end effectors can be extended from each side of the MMU to hold cargo in front of and below the hand controllers. Soft tethers can be attached to the cargo and to the pressure suit waist ring, or the side of the MMU. Finally, attachment mechanisms can be mounted at the end of each handcontroller housing to carry a smaller cargo item directly in front of the crew member's hands.

These attachment provisions are generally intended to allow easy transport of relatively small (less than 50 lb) cargo items. The MMU system is capable, however, of transporting larger masses (up to several hundred pounds) when operating free of external forces. The MMU control system compensates for changes in center of gravity and the torques which result from attaching such additional cargo. Exact limiting criteria are dependent on the total task requirements (e.g., distances, time constraints), in addition to the cargo mass and location.

The electrical system of the MMU provides auxiliary power which can be utilized to operate tools or other equipment at the task site, once translation to the site has been accomplished. Two power outlets supply 28V dc and 2 amps maximum; each outlet is operated by a switch accessible to the crewmember in flight. In addition, a floodlight which provides local work site illumination is mounted over each shoulder of the crewmember in the MMU.

Tethers can be utilized to establish a soft attachment between the crewmember/MMU and work site. A temporary system is also available to establish a more rigid attachment between the MMU and the work site. This system is designed to allow the crewmember to apply moderate forces at the work site without generating intolerable reactions or torques. It should be noted that additional work site dedicated restraints may be required if large forces or torques must be applied by the crewmember at the site. These restraints must be supplied by the user, or be built into the work site. A variety of standard Shuttle equipment is available for such support (see JSC-10615, "Shuttle EVA Description and Design Criteria").

The arms on which the MMU hand controllers are mounted can be folded down to provide clearance for the crewmember to approach the work site more closely.

Additional functional capability can be kitted into the MMU if required by a specific operational mission. Additional propellant tanks and navigation aids can be attached to the baseline MMU system to allow extended excursions farther away from the orbiter vehicle. Although design concepts for these kits have not been finalized, potential MMU users should be aware that such capability will become available as part of the basic MMU configuration as the Shuttle flight program progresses.

## Servicing

The MMU can be serviced by a single crewmember while it is mounted in the FSS. Spare batteries, stowed in the pressurized crew compartment, can replace used batteries in the MMU; battery replacement takes less than five minutes. Two fully charged batteries provide 540 watt-hours of power; the nominal MMU load is 30 watts. (Battery recharge, if required, is accomplished in the pressurized airlock of the orbiter using the EMU recharge system. Up to 16 hours are required to establish a full charge.)

Recharge of the MMU nitrogen propellant tanks can be performed at the FSS using a pressurized nitrogen supply (3000 psi maximum) available from the orbiter. A quick disconnect establishes the connection between the orbiter supply and the MMU. Gauges and toggle valves mounted on the MMU and FSS are utilized to monitor and control repressurization. Propellant recharge of both tanks can be completed in less than 10 minutes.

Since the orbiter supply (3000 psi maximum) is less than the initial ground charge of the MMU (4500 psi), the delta velocity available from the recharge will typically be 80 to 100 fps. A full ground charge provides 110 to 135 fps delta velocity capability.

## Mass Properties

The total weight of the MMU is approximately 243 lb (110 kg), including a full charge of propellant (40 lb  $\text{GN}_2$ ). Fig. 4.4-3 depicts the reference coordinate axis and shows the location of the center of mass of the EMU/MMU system. The maneuvering unit will accommodate personnel within the range of the 5th percentile based on anthropometric data for 1968 USAF women officers, to the 95th percentile based on data for 1980 male flying officers.




Figure 4.4-3. MMU Reference  
Coordinate System

For each MMU carried aboard the orbiter, a Flight Support Station (FSS) is required. The FSS is a structure to which the MMU is attached for launch and reentry of the orbiter. The weight of the FSS is approximately 50 lb (23 kg); hence, the payload launch weight penalty for one MMU is approximately 293 lb (133 kg). It should be noted that the weight of the flight operational MMU system includes the astronaut and the extravehicular mobility unit (EMU). The astronaut weight can vary between 100 and 215 lb (45 to 100 kg); the EMU weight is approximately 175 lb (80 kg).

#### 4.4.2 Manned Remote Work Station, MRWS (Cherry Picker)

The MRWS is being developed by the Grumman Corporation. The data presented has been taken from their final report, "Manned Remote Work Station Development Article," Volume I, Book 1, Flight Article Requirements, Report NSS-MR-RP008, dated 3-1-79.

##### Flight Article System Requirements

The following defines the overall configuration, safety, reliability, maintenance, and interface requirements.

##### *Open Cherry Picker MRWS (Figure 4.4-4)*

The MRWS shall support the EVA astroworkers and provide unobstructed reach for the astroworker to perform space tasks. The MRWS shall consist of:

- A platform with a restraint system to secure the EVA astroworker
- Stabilizer attached to the platform
- Illumination
- Stabilizer controls and displays
- RMS controls and displays
- Tool storage (small hand tools)
- Provisions for large tools
- Payload handling devices
- RMS mechanical and electrical interfaces
- Provisions for storage in payload bay

The platform shall be mounted to the orbiter RMS utilizing the stabilizer fixture that interfaces with standard snare-type end effector.

Electrical power, controls, and data shall be routed through the RMS internal cabling utilizing the payload mounted grapple fixture special-purpose end effector connector.

The open cherry picker MRWS shall fold for storage in the orbiter payload bay. Its folded volume shall not exceed  $1.5 \text{ m}^3$  and it shall be mounted adjacent to the EVA hatch at the starboard manned maneuvering unit (MMU) donning station attachment points.

##### Open Cherry Picker Subsystem Requirements

###### *Structure/Mechanical*

All major load-carrying structures of the structural subsystems shall be designed to a safe life of a minimum of 10 years in orbit with a scatter factor of 4.0. Life limitations shall be identified.




Figure 4.4-4. OCP-DTA General Arrangement

As a goal, fail-safe design concepts shall be applied to all critical structure so that failure of a single structural member shall not degrade the strength of stiffness of the structure to the extent that the crew is in immediate jeopardy.

The structure shall be designed to resist damage resulting from accidental impact during crew activities.

Safety factors used for structural design shall be consistent with those currently used for manned operations.

- Primary Structure

- Ultimate strength: A factor of 1.5 x limit load shall be applied.
- Yield strength: A factor of 1.2 x limit load shall be applied.

Structures shall be designed to withstand temperature cycling between -433°K to 366°K.

The structure shall be designed to withstand orbiter launch and landing loads specified in JSC-07700, Volume XIV.

The open cherry picker (OCP) shall be designed to be folded and unfolded by an EVA astronaut to facilitate orbiter payload bay storage.

#### *Communications*

The OCP operator shall utilize the EMU for communications with the orbiter, EVA astroworker and space construction base as applicable.

#### *Electrical Power*

The open cherry picker MRWS shall receive 28 V dc orbiter power, up to 250 W, via the RMS grapple fixture electrical connector.

The distribution system shall provide circuit protection devices for all power equipment.

The electrical power subsystem (EPS) shall have a maintained lifetime of not less than 10 years. Elements may be replaced in total or in modular form for maintenance or for growth up-rating.

#### *Environmental Control and Life Support (ECLS)*

The OCP operator shall utilize the extravehicular mobility unit (EMU) for ECLS.

#### *Thermal Control*

Passive thermal control approach should be utilized where appropriate, or if not feasible, the design should minimize system complexity and weight.

The subsystem shall not require selected orientation in orbit to maintain its thermal control function.

#### Crew Accommodations

An existing foot restraint that is mounted to a rotating platform (Fig. 4.4-5) will be utilized for the OCP.




Figure 4.4-5. Foot Restraint

A safety tether shall be provided. Also provided will be a waist restraint to be used in conjunction with foot restraint as needed.

The open platform equipment shall not inhibit crew reach (Fig. 4.4-6) to perform assembly tasks.

#### Stabilizer (Controller and Slave)

The OCP MRWS shall have one stabilizer located on the platform extending forward and shall be capable of being installed/detached in orbit. The stabilizer shall have 3 DOF as defined in Fig. 4.4-7. The stabilizer characteristics are:

Reach	1.3 m
Tip force (locked)	40 lb
Tip moment (locked)	4000 in.-lb
Accuracy	± 1 cm
Resolution	± 2 mm
Velocity	1.1 cm/sec





Figure 4.4-6. EMU Reach Capability






Figure 4.4-7. Three-Degree-Of-Freedom Stabilizer

ORIGINAL PAGE IS  
OF POOR QUALITY



- The stabilizer master control shall be a resolved rate controller(s)
- The tip shall have mechanical and electrical interfaces to accept end effectors.
- Provide controls to actuate end effector functions, eg., open/close jaws.
- The stabilizer joints shall lock in existing position at power removal.
- Back driving shall not damage the stabilizer.

#### *Cherry Picker Arm Control*

- Provide orbiter RMS/cherry picker arm control from the OCP utilizing the same type of controllers used for the orbiter RMS.
- The capability shall be available to select control of an alternate RMS/crane arm.
- The capability shall be available to the OCP operator to control individual RMS joints.
- Interface units shall be provided for open cherry picker RMS control as shown in Figure 4.4-8.

#### *Illumination*

Lights shall be mounted on the OCP to provide 50 ft-c of luminous intensity within the reach of the OCP operator. The lights shall be adjustable by the OCP operator for direction and reach.

#### *Controls and Displays (C&D)*

A C&D console shall be mounted convenient to the operator during OCP RMS maneuvers and when controlling the stabilizer. The panel shall provide accommodations for mounting the RMS and stabilizer controllers. Controls and displays panel shall be moveable so that the operator is not constrained while performing space tasks.

#### *Software*

Utilize existing orbiter software for control of the RMS.



### Remote Manipulator System (RMS)

The RMS is being developed by SPAR of Canada for the Shuttle program. These data have been taken from the Space Shuttle System Payload Accommodations, JSC 07700, Volume XIV, Revision F, dated 9-22-78.

The RMS is shown in Fig. 4.4-9. A single manipulator of 50 feet, 3 inches (15,316 mm) in length is normally located on the port side of the vehicle, as shown in Fig. 4.4-10. The RMS is stowed outside the payload dynamic envelope and is charged to orbiter weight. Detailed arm dimensions and joint angle limits are shown in Fig. 4.4-11.

A second manipulator arm can be installed on the starboard longeron if compatible with STS operational constraints. The weight of the second manipulator is weight chargeable to the payload. This weight is 905 lb, including the standard end effector and TV at the wrist (TV also mounted at the elbow is an additional 28 lb). Capability is provided to operate two manipulators in serial-only (non-simultaneous) operations. Capability is provided to hold the payload with one manipulator arm in a chosen position while operating the second manipulator arm.

The capability is provided to jettison each manipulator arm assembly. Sufficient redundancy is provided to insure that the payload can be released prior to RMS arm jettison.

#### General RMS Capabilities

a. In orbit, the manipulator is capable of deploying a maximum envelope (approximately 15 feet diameter x 60 feet long), maximum weight 65,000 lb (29,484 kg) payload. Under normal operational conditions, the RMS is capable of retrieving a 32,000-lb (14,515-kg) payload and placing it in a position for engagement with the cargo retention system in the cargo bay for return to earth. Under clearly defined contingency conditions, the RMS is capable of retrieving a maximum weight payload (65,000 lb) in a non-time constrained operation. (The requirement for retrieval of a payload weighing more than 32,000 lb could be to correct a malfunction in the payload and subsequently redeploy the payload. The orbiter entry and landing is normally constrained to payloads weighing less than 32,000 lb.

Deployment of a maximum envelope, maximum weight payload can be accomplished in approximately 25 minutes from release of payload tiedown to release of the payload at the manipulator fully deployed position.

The RMS is capable of supporting up to a maximum weight payload in the pre-planned deployed position under the attitude stabilization loads imposed by the orbiter vernier RCS (operating in min impulse mode).

Within the operational reach limits of the manipulator the orbiter vehicle will have the capability to deploy and/or retrieve single or multiple payload elements on orbit during a single flight. Within defined limitations, the RMS may also be used to place payloads on or dock payloads with, a suitably configured and stabilized body.




Figure 4.4-9. Orbiter Remote Manipulator System




Figure 4.4-10. RMS Location



Figure 4.4-11. RMS Arm Dimensions and Joint Angle Limits

b. The standard end effector provided with the RMS and its associated grapple fixture (payload provided) are shown in Figures 4.4-12, -13, and -14. The capture and rigidize sequence is shown in Fig. 4.4-15. The RMS also has the on-orbit capability of grappling a special-purpose end effector (payload provided) and providing an electrical connection across the interface for control of the special end effector. This connection may also be used to provide power and/or signals to payloads, if the payload provides the compliance and mating connector within its grapple fixture. The electrical connector is fitted on the outside of the standard end effector at the end effector/payload interface as indicated in Figure 3-14. The power for the special purpose end effector or payload is taken from the 28 V arm power bus. Wiring is provided from the orbiter flight deck on-orbit station distribution panel to the RMS shoulder interface, and from there to the face of the standard end effector. Controls and displays for command or signals to the special purpose end effector or to payloads must be provided by the payload. The wire gauging and quantities available for this interface are shown in Fig. 4.4-16. On-orbit stowage of any special purpose end effector must be provided by the payloads. The RMS standard end effector may be exchanged on the ground with a special end effector for use on orbit.

#### RMS Performance Characteristics

The velocity of the loaded RMS end effector is controlled such that the kinetic energy of the payload will not exceed that of a 32,000-lb payload moving at approximately 0.2 ft/sec. The velocity of the unloaded RMS end effector is limited to 2.0 ft/sec.

Within 5 minutes following extension of the RMS/payload and deactivation of the orbiter VRCS, the RMS will be capable of releasing a 32,000-lb maximum envelope payload within the following limits:

- Attitude within  $1^\circ$  of a specified orientation, relative to the RMS shoulder attach point. Attitude relative to orbiter is TBD.
- Position within 2.0 in. of a specified position relative to the RMS shoulder attach point.
- Angular momentum of the payload relative to the orbiter less than or equal to 10 slug-ft<sup>2</sup>/sec.
- Linear motion of less than 0.10 ft per second.






Figure 4.4-12. Standard End Effector

ORIGINAL PAGE IS  
OF POOR QUALITY




Figure 4.4-13. Standard Grapple Fixture and Target











Figure 4.4-14. RMS Standard End Effector and Grapple Fixture Envelope Schematic




OPERATION OF BALL SCREW & NUT WITHDRAWS WIRES PULLING PAYLOAD INTO FULL CONTACT & KEYED ORIENTATION. FURTHER OPERATION TENSIONS WIRES RIGIDIZING THE CONTACT.



ORIGINAL PAGE IS  
OF POOR QUALITY

Figure 4.4-15. Snare End Effector, Capture and Rigidize Sequence



4-48

A 65,000 lb payload can be released within TBD limits.

In the automatic mode, the RMS is capable of accurately positioning the end effector (loaded or unloaded) within  $\pm 2.0$  inches (50.8 mm) and  $\pm 1^\circ$  relative to the shoulder attach point. In the manual augmented mode the end effector positioning accuracy is primarily a function of operator visibility.

The manipulator arm will transmit, when fully extended and attached to a payload, loads not exceeding the following:

- a. A combined 12-lb shear force and 160 ft-lb bending moment at the end effector.
- b. A 230 ft-lb torque about the end effector axis. An example of the forces and torques that are applied by the end effector for various arm configurations are shown in Table 4.4-2.

Table 4.4-2. Force/Torque Capability at End Effector

	Torque Range (ft/lbs)		Force (lbs)		Condition
	Min	Max	Min	Max	
Shoulder Yaw	772	- 1158	15.44	- 23.2	Straight Arm
Shoulder Pitch	772	- 1158	15.44	- 23.2	Straight Arm
Elbow Pitch	528	- 792	18.41	- 27.3	Bent Arm Overall Length < 42 Ft.
Wrist Pitch	231	- 347	37.97	- 57.0	Bent Arm Overall Length < 20 Ft.
Wrist Yaw	231	- 347	54.35	- 81.6	Bent Arm Overall Length < 14 Ft.
Wrist Roll	231	- 347	-	-	

NOTE: All values are quotes for the arm under steady-state rigid body static condition; e.g., in payload bay - and single-joint drive.

The manipulator arm is capable of operating (when exposed to direct and/or reflected sunlight) for not less than:

- 30 minutes when operating in the cargo bay
- 120 minutes when operating outside the cargo bay

#### RMS Control System

Control of the RMS is effected by the operator from the RMS D&C panel in the aft flight deck. The operator has access to four prime control modes, in which he has varying degrees of software support, and a back-up mode which completely bypasses the control and display software. The control modes that can be selected by the operator are as follows:

a. Manual Augmented Mode - The operator issues commands through two 3-DOF hand controllers for commanding resolved rates for the six degrees of freedom of the arm. The rotational controller provides for resolved roll, pitch, and yaw without inducing translation at the point of resolution. The translation controller provides for resolved up/down, left/right, fore/aft translation without inducing rotation.

b. Automatic Mode - The manipulator arm movement can be controlled automatically along a prespecified trajectory. This trajectory is defined by a series of predefined positions and orientations stored in the GPC. The operator can select up to four preprogrammed automatic trajectories from the D&C panel mode select rotary switch. Up to 200 points (total) can be stored for auto trajectories, each point defined by orbiter reference position x, y, z, plus yaw, pitch, roll orientation.

A second type of automatic trajectory can be initiated by the RMS operator through the D&C select switch and the GPC keyboard. This is the operator commanded auto sequence mode and is initiated by input of the required position and orientation of the end effector or payload. A straight line trajectory is then performed from the current position and orientation to the desired position and orientation.

The above automatic sequence capabilities are available to be negotiated by payloads on an individual basis.

c. Single-Joint Drive Mode - The operator commands, through D&C panel switches, movements of individual arm joints. These commands are made through the RMS software, which controls the position of all joints, limits drive speeds, provides joint position displays, and indicates when joint angle reach limits are encountered.


d. Direct-Drive Mode - Direct drive control of the RMS is by the operator command of individual joints, using hardwired commands from the D&C panel. This is a contingency mode which bypasses the software when driving the motors (software data are normally displayed).

e. Back-Up Drive Mode - Back-up control of individual joints by operator commands through unique hardwired channels. No position data are displayed.


The combined operations of the six joints of the manipulator arm, through one of the appropriate control modes above, enables the operator to move the end effector in six degrees of freedom (3 degrees of motion in translation, 3 in rotation). The coordinate systems relating these travel directions are shown in Fig. 4.4-17. In the manual modes, the operator commands movement of the end effector using the THC and RHC in the selected coordinate system. Operations in the automatic control mode will utilize the orbiter referenced coordinate system.

#### RMS Software

The RMS software, under which most RMS operations are performed, resides in the orbiter general-purpose computer (GPC). The RMS software performs the following functions:




ORBITER LOADED. POINT OF RESOLUTION  
IS MASS OR GEOMETRIC CENTER OF PAYLOAD.




PAYLOAD. POINT OF RESOLUTION IS MASS  
OR GEOMETRIC CENTER OF THE PAYLOAD.

ORIGINAL PAGE IS  
OF POOR QUALITY



ORBITER UNLOADED. POINT OF RESOLUTION  
IS TIP OF END EFFECTOR.



END EFFECTOR. POINT OF RESOLUTION  
IS TIP OF END EFFECTOR.

Figure 4.4-17. Control Coordinate Reference Systems



- Translates operator commands into RMS arm operations and motions.
- Monitors RMS status
- Performs display computational tasks for information to the RMS operator, including caution and warning.

Control algorithms contained in the RMS software convert operator commands (normally input by the hand controllers at the D&C panel) into output rates resolved for each joint of the arm. The rate demands to the joint servos are output within limits defined according to arm and individual joint loading conditions present at the time of computation.

#### *Initialization Data*

Parameters with which the RMS software is initialized may vary from flight to flight. These parameters may be RMS hardware dependent (generally called I-loads) or flight and payload dependent (generally called Level C data). The hardware dependent parameters include: (a) end effector length, (b) hand controller biases, and (c) tachometer biases, etc. The flight and payload dependent parameters include the following (nominal values for a 32K payload are indicated:

	<u>Coarse</u>	<u>Vernier</u>
Maximum payload translation rate	0.2 fps	0.01 fps
Maximum payload rotation rate	0.0083 rad/sec	0.00415 rad/sec
Joint angle course rate limits	--	--
Joint angle vernier rate limits	--	--
Payload to end effector transformation matrix		
Automatic trajectory parameters		

The RMS initialization parameters (I-load and Level C) are identified in SD 77-SH-0002A, Level C Functional Subsystem Software Requirements (FSSR) document. Some of these quantities can be changed on orbit through GPS keyboard input. To generate the payload dependent RMS software parameters, payload characteristics should be provided approximately one year prior to flight. These characteristics, and their allowable variations, are as follows:

- Payload mass to  $\pm 10\%$
- Payload center of mass to  $\pm 6$  inches, defined in Payload Coordinate System
- Moments of inertia about payload principal axes to  $\pm 10\%$
- Payload cross-products of inertia, to  $\pm 10\%$
- Grapple fixture location(s) and installation orientation, in payload coordinates. If the payload has no preference, NASA will select grapple fixture orientation. The grapple fixture will normally be located within 5% (of payload length) of the Y-Z plane of the payload center of mass.

### *Downlist Data*

A number of RMS parameters are on the GPC downlist. These measurements are signals which are used directly or indirectly to provide data to the flight computers, the RMS operator, the ground mission controllers, or flight planners regarding the systems performance, component status, or condition of hardware and/or software elements. Each measurement is given a unique identification number to identify its signal source or location, sample rate, range, and units. The available RMS downlist parameters are listed in SD 77-SH-0002A, Level C Functional Subsystem Software Requirements (FSSR) document.

### *Orbiter Crew Station*

The orbiter aft flight deck contains the primary stations for payload deployment and retrieval operations. The RMS D&C is located at panel A-9 as shown in Fig. 4.4-18. All RMS D&C, including the hand controllers (but excluding RMS software initialization controls), are located at this port side of the on-orbit station. In addition, CCTV monitors and exterior-viewing windows are located at this RMS operator's station. The starboard side of the on-orbit station contains the displays and controls required for orbiter vehicle translation and attitude control. The mission station will contain the CRT and keyboard utilized to initialize the RMS software and checkout sequences and to provide messages for operator information and action. Two aft windows and two overhead windows are located to provide direct exterior viewing for two operators at the on-orbit station.

### *Orbiter Exterior Lighting*

The orbiter exterior lighting in the vicinity of the cargo bay is described in ICD-2-19001. This lighting is used to provide illumination to aid direct and, at times, indirect (CCTV) viewing of payload handling and proximity operations. In addition to the cargo bay bulkhead and overhead lights, a light is located on the wrist segment of the RMS arm, to provide illumination for grappling or for illumination to areas that may be shadowed by elements within the payload bay. This RMS light, along with a CCTV camera, is fixed-mounted to the rolling member of the RMS wrist joint, as shown in Fig. 4.4-19. The RMS light brightness is 3 ft-candles at 30 feet, diminishing to 0.15 ft-candle at 200 ft.

### *Closed Circuit Television (CCTV) System*

The orbiter CCTV system is described in ICD-2-19001. The orbiter can accommodate up to five CCTV camera locations within the cargo bay. The standard locations are considered to be one of the mirror image positions on the forward and aft bulkheads, plus one of four keel positions. In addition, the RMS can accommodate two camera positions on the manipulator arm; one wrist and one elbow location. The CCTV D&C panel at the aft crew station is used to control all exterior CCTV cameras, including serial operation of the two RMS cameras. CCTV cameras are generally considered as kittable with any mix, up to five cameras, installed to support mission requirements. These installations may include, on occasion, cameras mounted on payload-provided cradles





Figure 4.4-18. RMS Operator Station

ORIGINAL PAGE IS  
OF POOR QUALITY



- ① EVA HANDHOLD LOCATION, IDENTICAL FOR PORT AND STARBOARD CONFIGURED M.A.
- ② ASSUMES MAXIMUM  $48^\circ$  DIAGONAL FOV

Figure 4.4-19. RMS CCIV Wrist Camera and Light Subassembly Design Configuration

or hardware (utilizing orbiter junction and wiring capability) to support the viewing requirements for the payload deployment or berthing operations. The CCTV mounting location payload options are indicated in Fig. 4.4-20. All CCTV cameras will have zoom and iris control. In addition, the forward and aft bulkhead cameras and the optional RMS elbow camera have pan and tilt control, with pan and tilt angles displayed on the CCTV monitors. The TV cameras will be capable of accommodating a range of lenses for special payload applications; the TV lenses may be removed and replaced prior to flight. The field of view for the standard lens varies from approximately 48.0° diagonal, to approximately 8.5° diagonal, when focused at infinity.

#### 4.4.4 Beam Builder

The beam builder is under development by General Dynamics Convair Division. The information on the following pages was taken from "Space Construction Automated Fabrication Experiment Definition Study (SCAFEDS)" final report, Volume II, Study Results, CASD-ASP77-017, dated 5-26-78.

The SCAFE beam builder is an automatic machine process which fabricates beam assemblies from non-metallic materials stored within the machine. The materials are preconsolidated thermoplastic graphite/fiberglass composites which are manufactured in a convenient form for small volume storage. The thermoplastic composite materials not only provide excellent properties for space structures, but lend themselves to automatic fabrication techniques because they are heat formable and can be joined by efficient spot welding techniques.

The beam builder concept satisfies the following design criteria:

- Power utilization well within orbiter capability
- Automatic quality control
- Least amount of material
- Fewest number of beam weld joints
- No growth limitations
- Low weight

#### Beam Builder Concept

The basic processes of the beam builder are illustrated schematically in Fig. 4.4-21. The beam is constructed of three formed caps, joined to channel-shaped cross-members, and stabilized with six zig-zag plyed tension cord diagonals. Fabrication of this beam requires these processes:

- a. Storage. Flat strip material for the caps and cross-members, and the cord for the diagonals are stored by a process which provides safe, positive containment and dispenses the material with ease.




Figure 4.4-20. CCTV Camera Mounting Options




Figure 4.4-21. Cyclic Feed Fabricator Functional Schematic

- b. Heating. The flat strip material for the caps and cross-members is fed through a heating section in preparation for forming. The heating section applies heat only to bend zones in order to conserve energy. The bend zones are heated to the plastic state prior to entering the forming section.
- c. Forming. The heated caps and cross-members are formed to the desired cross sectional shape by the Convair-developed rolltrusion process.
- d. Cooling. On exit from the forming process, the beam members are cooled to a satisfactory use temperature before exposure to load.
- e. Drive. The beam is moved through the fabrication process and deployed into space by a drive mechanism on each cap member. The drive mechanism also provides the force necessary to extract the cap and cross-member material from storage and pull it through the forming process.
- f. Diagonal Cord Applicator. As the beam advances through the fabrication process, the diagonal cord members are plyed across each face of the beam. The cords are properly tensioned and positioned for joining.
- g. Cross-Member Positioner. Before the finished cross-members are cut to length, a positioner grasps the member. After cutoff, the positioners rotate and translate the cross-members into position for joining to the caps.
- h. Joining. When the cross-members are positioned and the cords are positioned and tensioned, the joining process permanently joins the beam elements together.
- i. Cutoff. Cutoff devices are required to cut cross-members to length and to cut off finished lengths of beam.

The cyclic-feed beam builder operates for a 40-second run period during which the caps and beams are advanced at 2.2 m per minute. After 1.434 m beam extension, a pause of 40 seconds is made for cross-member and diagonal cord attachment. During the pause period, the formed cross-members are grasped by the positioner, cut off, and positioned on the caps. The diagonal cords are aligned between the cap and cross-member by the cord feed mechanisms and the cord and cap are ultrasonic weld joined to the cap. The beam builder then repeats the operating cycle. The configuration of the machine is shown in Figure 4.4-22.




Figure 4.4-22. SCAFEDS Beam Builder Concept

#### Preliminary Design Description

Preliminary performance data are summarized in Table 4.4-3.

#### Cap Forming Machine Subsystem

The cap forming machine assembly contains all elements necessary to continuously process flat strip glass/graphite/thermoplastic material into the baseline cap configuration. Approximately 918 m of material is coiled in the roll retained in the storage canister. The roll turns freely on bearing-mounted rollers and unwinds uniformly as material is used. The canister is in two halves, with one half hinged to permit the material roll to be inserted. When the canister is closed and latched, an access panel in the hinged half is opened to allow the material to be manually routed over the heating section guide rollers into the forming section manual feed rollers.



Table 4.4-3. Beam Builder Preliminary Design and Performance Data

PROCESS OR SUBSYSTEM	PARAMETER	LIMITS OR TOLERANCE
Material Storage	Roll O.D.	121.4 cm Max
	Roll I.D.	60 cm Min
	Roll Length	918.2 m
	Roll Width	19.05 cm
	Roll Weight	262.2 kg
Heating	Temperature Limits:	
	1st Stage	482°K
	2nd Stage	707°K
	Forming Section	707°K
	Start-Up Time	430 seconds
Forming	Forming Section Length	
	Max. Forming Rate	Not Determined
Cooling	Actuation Time	0.2 seconds
	Actuator Stroke	0.32 cm
	Max. Cooling Time	12 seconds
Drive	Cap Stroke Tolerance	± TBD
	Cap Speed	3.585 cm/sec
	Max. Acceleration	1.3 cm/sec <sup>2</sup>
	Max. Force Capability	533N
	Max. Force Required	311N
	Run Time	40 seconds
	Pause Time	40 seconds
Cord Storage	Cord on Spool:	
	Length	1219 m
	O.D.	13.12 cm
	I.D.	7.62 cm
	Width	13.12 cm
	Weight per Spool	2.13 kg
	Spool Drag Torque	56.5 ± 5.6 N-cm
Cord Tensioner	Tensioning Force	44.5 ± 8.9 N
	Spring Stroke	21.2 cm
	Spring Load Rating	89 N
	Max. Cord Speed	11.3 cm/sec
	Pulley Diameter	7.1 cm
Cord Plyer	Travel Speed	10.7 cm/sec
	Pulley Diameter	7.1 cm

Table 4.4-3. Beam Builder Preliminary Design and Performance Data (Cont.)

PROCESS OR SUBSYSTEM	PARAMETER	LIMITS OR TOLERANCE
Clip Storage and Feed	Capacity	650 pieces
	Weight of Cross-Members	79.8 kg
	Feed Rate	0.4 cm/sec
Cross-Member Positioner	Time to Position Cross-Member	3 sec
	Separation Time	1 sec
	Return Time	4 sec
Welding Mechanism	Stroke	4 cm
	Time to Engage and Pierce	3 sec
	Time to Engage for Weld	0.2 sec
	Weld Time	2 sec
	Cooling Time	1 sec
	Retraction Time	3 sec
Cutoff Mechanism	Time to Engage and Shear	1 sec
	Time to Retract	1 sec

The heating section is partially built into the storage canister with resistance strip heaters and parabolic reflectors mounted on the access panel. The heating section extends from the access panel up to the point where the material starts to form.

The material passes from the heating section through the forming section. The rolltrusion forming section is also equipped with strip heaters which heat the partially formed material in preparation for start-up of the machine.

The material then passes from the forming section into the cooling section where it is contact cooled by aluminum platens. Cooling fluid is supplied to the inside cooling platens and expelled as waste heat by an independent cooling system in the beam builder. Waste heat is also extracted from the heater reflectors by the cooling fluid loop. The cooling platens cool one bay length of cap section during the 40-second pause period.

The drive section has four friction-drive rollers which provide the necessary pull force on the cap to draw the material from the storage roll through the heat/form/cool sections. The three cap drive sections also provide the push force to advance the beam out of the beam builder.

### *Cross-Member Subsystem*

The cross-member clip is constructed of machined aluminum sections. Two mating center support panels are joined by two end piece assemblies to form the basic clip structure.

The stack of cross-members is supported and fed to the beam assembly process by four timing belts. The clips are indexed on the belts by serrations on the mating surfaces of the belts. The belt drive and belt pulleys are mounted on the center support panels. The clip holds 650 cross-members.

The clip is loaded and assembled by laying the stack of cross-members on one of the center support/belt drive subassemblies. The second center support/belt drive subassembly is then layed on the stack and all belts inspected for proper mesh with the cross-members. The end pieces, which consist of two mated halves, are bolted to the center supports.

The feed drive is a redundant motor drive which provides simultaneous output to all four feed belts. The retainer mechanisms at the output end of the clip are described below.

Mounting pads on the inboard center support allow the clip assembly to be bolted to the beam builder structure.

The cross-member positioner/handler mechanism transports one cross-member at a time from the storage clip to the installation position on the beam. During the run period, when the beam is advancing one bay length, the positioner/handler is fully retracted with the handler below the plane of the beam side. This allows the last cross-member installed to clear the handler and also allows the cord plyers to pass over the handler/positioner.

At some time after the cord plyers have completed their stroke, each position arm is rotated and translated into position for receiving the next cross-member from the clip. The cross-member retainers on each end of the next cross-member are retracted and the clip drive stepper motors are activated. When the stack has moved about 0.4 cm, a sensor in the cross-member handler is triggered. This causes the clip drive motors to stop and cross-member retainers to engage and retain the next to last cross-member. The fingers on the handler also close and grasp the next cross-member to be installed.

The cross-member positioner arm is rotated and translated to remove the cross-member from the clip and lay it in proper position for welding to the cap members. After welding is complete, but before the beam is advanced, the handler fingers are opened and the positioner arm rotated to drop the handler below the plane of the beam side.

### *Diagonal Cord Applicator Subsystem*

The cord plyer mechanism consists of six reciprocating cord plyer subassemblies. Each plyer is driven along a guide beam by a motor-driven ball reverser lead screw. Each guide beam is equipped with position sensors to monitor the six positions of each cord plyer. Cord is supplied to each plyer from a storage spool over a series of pulleys. The inboard pulleys on the cord plyers are mounted on swivels to allow the cord to be properly aligned as the cord plyer changes position.

Forward and aft cord plyers permit the two cords on each side of the beam to be applied without interference between the moving plyers. The aft cord plyers have a longer stroke than the forward cord plyers because they are set back 13.5 cm from the forward cord plyers. This requires more lateral motion to achieve the required angle between the cord and the caps.

The forward cord plyer must always complete its stroke to the outboard position ahead of the aft cord plyer to avoid a collision with the cord of the aft plyer at the apex of the beam. Similarly, the aft cord plyer must always move from the outboard position first.

The forward and aft cord plyers each have redundant motor drives. Two of the three lead screws are motor driven while the third is driven at either end by a flexible drive shaft. Should one of the two drives fail, the other would drive all three lead screws. The cord plyers are all driven at an average velocity of 10.7 cm/sec.

The cord tensioner mechanism operates in two modes. The first mode is the supply mode where cord passes freely from the storage spool to the cord plyers. The second mode is the tensioning mode whereby the free-turning capstan is stopped and held by an electric-operated clutch brake. This causes the traveling pulley to extend under the force applied by the constant-force spring. A tension force equal to one-half the spring force is thus applied to the cord. Total spring force is measured by a force transducer attached to a guide pulley.

A cord tension force of  $44.5 \pm 8.9$  N is applied to each cord during assembly. This preloads the cords sufficiently to preclude any slackening or over tensioning due to thermal and deflection effects. The  $\pm 8.9$  N variation limits the theoretical twist and deflection in the beam to less than  $1.2^\circ$  of twist and 0.5 cm of tip deflection for a 200 m beam.

The stroke of the traveling pulley assures that a constant force is maintained on the cord throughout the assembly sequent. As the cord plyers move from the outboard position to the ready-to-weld position, the traveling pulley automatically compensates for the change in cord length.

As the beam starts to advance in the beam builder, the cord tensioners are in the free feed mode and the forward cord pleyer drive is activated. A 3-second delay is provided before start of the aft cord pleyer drive so that the forward cord plyers reach their outboard position first.

The cord plyers stop at their outboard positions and, after 23 seconds, the cord tensioner capstan brakes are applied. The beam drive thus applies the necessary force to extend the cord tensioner constant force springs to the proper stroke.

After the beam is stopped and the cross-members to be attached are in position, the ultrasonic welding heads are advanced and activated momentarily to allow a pin on each weld head to pierce the cross-member and cap just below each cord. When the piercing is completed, the aft cord pleyer drive is activated. A 2-second delay permits the aft cord pleyer cords to move clear of the forward cord plyers before the forward plyers start to move. The forward and aft cord plyers move to the ready-to-weld position while the cord tension is maintained by the cord tensioning mechanism.

At the ready-to-weld position, the cords have been strung over the piercing pins and are at their final assembled angle to the beam caps. At the conclusion of the welding operation, the cord tensioner capstan brakes are released and the next cycle is ready to begin.

#### *Beam Welding Subsystem*

The beam welding mechanism has six ultrasonic weld head assemblies which are driven in pairs by a redundant motor drive for each pair. The three weld head positions are: (1) fully retracted to allow the cross-members to be positioned by the cross-member positioners; (2) pierce position, where the piercing pin on each weld horn has penetrated the cross-member and cap; and (3) the weld position, where the weld horn is engaged and properly loaded to enable the welds to be accomplished.

Each weld horn is equipped to perform two dimple spot welds and one special cord capturing weld simultaneously. The weld horns act against internal anvils, which are extended against the inside surface of the caps by a common dual motor-driven cam mechanism. The weld station is supported and sized by the combined action of the weld anvils and the beam support rollers located on the centerline of the weld station. A spring cartridge on each anvil actuator-rod limits the engagement force. The weld anvils are retracted to allow the weld dimples to pass and to minimize friction drag on the caps.

#### *Beam Support Subsystem*

The beam is supported at two stations by precision located metal rollers. The roller support stations fall on the centerline of the beam cross-members when the beam builder is in the assembly pause mode. The rollers maintain beam straightness during assembly and react bending moments during beam extension.

### *Coolant Subsystem*

The coolant (F-21 or equivalent) is circulated through the cooling platens and heater reflectors in the heating and forming sections of the three cap forming machines. The coolant removes an estimated 448 watts total from the platens and reflectors. The high temperature coolant then flows through the radiator panel where the excess heat is radiated to space. The radiating area is sized to reject the 448 watts cooling load under maximum solar heat influx conditions. The silver backed teflon tape provides high emittance and low absorptance to minimize the thermal impact of solar heating.

The pump operates with a power demand of 58 watts. Overall system weight is estimated to be 15.3 kg.

The radiator for this system is mounted to one of the clip housings. The remaining components are installed inside the beam builder structure beneath the clips.

ORIGINAL PAGE IS  
OF POOR QUALITY

### *Beam Cutoff Subsystem*

The beam cutoff mechanism shears each cap and cord member to separate a complete beam from the beam builder. The clamping device is normally retracted to allow the cross-members to travel past the outer clamps.

In preparation for beam cutoff, a short cutoff bay (60 cm) is manufactured by the beam builder. The cords are layed along the caps within this short bay rather than crossing over in diagonal directions as they do in normal bay construction. The short bay is advanced to the point where the cutoff shears are in the center of the short bay as the next complete bay is in assembly. When the next bay is assembled, the beam builder sequence is interrupted to permit beam cutoff and beam builder or platform repositioning.

Dual motor drives operate each cutter. As the actuators are extended, the clamps engage the internal backup mechanism and force the backups into position. The shear blades are spring loaded to allow the clamps to fully engage before the shear blades penetrate the cap. The shear blades are then driven through the caps as the actuators continue to extend. This also shears the cords as they lay along the sides of the cap.

### *Beam Builder Structural Subsystem*

The beam builder structure is composed of welded aluminum elements. A preliminary analysis indicates a weight of 660 kg for the complete assembly.

The structure consists of three major segments: a forming section support, a central "spider", and an assembly section support. The forming section support is a trussed hexagonal system whose external surfaces provide support for the three machine storage/forming sections and the three cross-member storage clips. To maintain precise alignment of machine elements, local pads, machined after weld completion are provided at machine/structure interfaces.

The central spider is a three-legged box structure providing a transition load path from the internal forming section support to the external portions of the assembly section supports. It also provides an interface with the beam builder roll/turn positioning mechanism as well as supporting three cantilevered internal support beams and a support pedestal for the cross-member handler and weld anvil actuators.

The three external beams in the assembly section support provide mounting for the cord pleyer/tensioner mechanisms, the ultrasonic weld station, the cut-off mechanism, and guiderollers at the weld and exit stations. One of these three beams also supports the beam builder/assembly jig latch system. As a consequence of this eccentric support, the three beams are connected by a cross-bracing system to provide system torsional rigidity, particularly needed in view of the reduced beam section, near the spider attachment plane, to accommodate cord pleyer installation.

#### *Beam Builder Support Subsystem*

The support subsystem includes the mechanisms and controls which support the beam builder during platform fabrication.

A handling arm assembly attaches to the spider section of the beam builder structure. The handling arm is connected to a mechanism on the assembly jig which positions the beam builder.

A longitudinal beam latch mechanism aligns and couples the beam builder with the assembly jig. It provides the added support necessary to prevent relative motion between the beam builder and assembly jig during longitudinal beam fabrication. A cross-beam latch mechanism is also required to align and support the beam builder during cross-beam fabrication.



#### 4.5 GROUND SUPPORT

The ground support activity is influenced by the concept of utilizing a dedicated orbiter as a construction facility. This orbiter will be outfitted with the appropriate number of electrical energy kits, addition of oxygen and nitrogen tanks required for the EVA operations, special software and controls, and the berthing platform. Therefore, during the turnaround operations, only the replenishing of the expendables will be required. Updating of the software to be compatible with the particular missions may also be required. Unique flight support cradles and support structures will need to be installed for each of the three missions. Appropriate bridge fittings will accommodate the unique flight support equipment. Rapid turnaround between missions is desirable. However, a six-month contingency has been provided in the untended platform mode to account for any ground operations anomalies. The packaging of materials to facilitate rapid turnaround has been considered in such items as the bracing struts' canister and the development of the SCM into a single modular item.

A facility similar to the Operations and Checkout (O&C) building used by Spacelab is anticipated. While there will be no functional interfaces between cargo elements, the physical integration effort is still a time-consuming operation. This effort can be minimized by establishing a dedicated "staging" area where the individual items of the cargo can be accumulated, checked out, and packaged onto their individual flight support elements. The lack of cargo/orbiter functional interfaces eliminates the need for any orbiter functional simulator. Thus, the ground support equipment needs only to include a simple physical simulation of the orbiter cargo bay and all necessary slings, strongbacks, cranes, etc., to handle the cargo elements. All preparation of the cargo elements. All preparation of the cargo will be performed "off line" and thus not impact the standard ground turnaround time for the orbiter. The facility will include the capability to install the various cargo elements onto the standard cargo cradle for transportation to the orbiter for transfer to the payload bay in the horizontal position at the Orbiter Processing Facility (OPF).

#### 4.6 REFERENCES

ORIGINAL PAGE IS  
OF POOR QUALITY

- 4-1 NASA  
Space Shuttle System Payload Accommodations,  
JSC 07700, Volume XIV, Revision F, National Aeronautics  
and Space Administration, L. B. Johnson Space Center,  
Texas, 22 September 1978
- 4-2 Rockwell International  
Space Construction System Analysis Study  
Task 2 Final Report - Systems Analysis of Space  
Construction, SSD 79-0123, Satellite Systems Division,  
Rockwell International, June 1979





PRECEDING PAGE BLANK NOT FILMED

## 5.0 FIRST CONSTRUCTION MISSION

This section describes the detailed integration of the activities for the first construction mission, the analyses performed and results pertaining to this integrated presentation.

### 5.1 CONSTRUCTION PLAN

The general objective for the first mission plan was to perform as much as possible of the actual fabrication of beams in space and to assemble these into a basic structural framework, together with the electrical wiring connectors and attachment port/end fittings which would facilitate later installations of systems and payloads. Initially, it was not clear that all of this could be accomplished during the first mission due to potential volume limitations of the orbiter payload bay packaging. However, later analysis and design refinement gave assurance that it could all be finished except for the bracing struts provided to support the ends of cross beams during transfer to geosynchronous orbit.

Figure 5.1-1 shows the planned configuration of the platform at the end of the first mission.


#### 5.1.1 Construction Requirements

The general concepts of construction requirements in Section 2.0 were translated into detailed construction requirements for the first mission. As noted above, the scope of the first mission involves construction of the basic structure (except certain bracing struts) installation of basic wiring, connectors, and attachment ports. In addition, there is a requirement to provide sufficient instrumentation, libration damping, communications and control systems to facilitate rendezvous and berthing to the construction fixture on the second mission. These functions also require an on-board power system (powerlines, batteries, and controls). Such active spacecraft functions are provided in the construction fixture erected during the first mission.

Secondary level requirements include establishing that the basic structure is within acceptable tolerances for straightness and twist, and the recording of observable structural deviations for future reference in payload installations. Additional detail requirements are listed in Table 5.1-1.

#### 5.1.2 Construction Logic

An early step in the construction integration effort was to develop a logic diagram which outlined the major steps and flow of key events of construction, based upon analysis of the baseline design concept. Preliminary design of the platform and activity analyses then proceeded in roughly parallel time periods, considering interactions with the construction process up to the completion of the first mission. The logic diagram was revised



- ELECTRICAL LINES
- INTERFACE CONNECTORS

Figure 5.1-1. Planned Configuration of ETVP at End of First Construction Mission


Table 5.1-1. Detail Construction Requirements for First Mission

REQUIREMENTS	RATIONALE
<ul style="list-style-type: none"> <li>• All construction power shall be provided by the orbiter and limited to that of a normal payload: up to 7 kW continuously and up to 12 kW for 15 minutes every three hours.</li> <li>• The construction shall be performed with the orbiter in a free-drift mode to the maximum degree possible.</li> <li>• Construction activities shall be performed in parallel to the maximum degree feasible, within power demand limits and crew workload limits.</li> <li>• Construction activities shall be automated except where special dexterity, on-site observation or inordinate development costs make EVA desirable.</li> </ul>	<ul style="list-style-type: none"> <li>• Volume XIV requirements and cost avoidance for special power supplies.</li> <li>• Minimize costs of construction, weight penalties to platform structure and possible delays due to reorientation firings.</li> <li>• Minimize daily on-orbit costs.</li> <li>• Minimize costs due to extending the mission and provide minimal risk to crew.</li> </ul>

from time to time as required to reflect new insights developed during the analyses. Figure 5.1-2 shows the final form of the logic diagram for the first mission.

Note that the logic diagram is not a complete end-to-end activity sequence. It does represent the initial buildup of construction fixtures and the unique processes of fabricating the three longitudinal beams. However, at step 9.1 there is a break in the pictured sequence. This point on the chart begins a typical cycle of fabrication and installation of long and short cross beams, together with their associated transverse beams and the cross-brace cords between them. Cycles of repetition are indicated. At the end of the diagram there is a small number of shutdown activities. (The format of Figure 5.1-2 is thus more representative of typical concerns than a complete summary of all the construction activity). Further explanation and illustrations of the construction process are presented in Section 5.2.

In the format of the logic diagram, activities which potentially could be performed roughly in parallel are shown in a column, one above the other: The first time a particular type or unique activity occurs it is designated with a sequence number. Where activities are shown in parallel the numbering system uses a decimal system beginning at (.1) to designate the group of simultaneously occurring functions. Other, single, activities are shown with only the zero after the decimal in the sequence number. Repetitions are not given a sequence number. This system of numbering is admittedly somewhat rough and subjective. For example, transportation of cross and transverse beams is generally the same, being performed by the RMS. However, the reach




① BEGINNING OF TYPICAL (MID-SECTION) TWO-BAY CYCLE WITH ONE LONG CROSSBEAM AND ONE SHORT CROSSBEAM. DIFFERENT ACTIVITIES REQUIRED AT EACH END OF PLATFORM—NOT SHOWN HERE.

NOTE

( ) - POTENTIAL APPLICATIONS OF FUNCTION TO SIMILAR  
PIECE-PARTS ARE INDICATED

8 JAN. 1980

Figure 5.1-2. Engineering and Technology Verification  
Platform Construction Logic—First Mission



8 JAN 1980

Figure 5.1-2. Engineering and Technology Verification  
Platform Construction Logic—First Mission (Cont.)

and manipulation functions are significantly different due to their geometrical orientation distances from the site of pickup and obstructions which must be avoided. As a result, somewhat different durations are required and a separate activity description sheet was prepared for each type.

On the other hand, the installation of intersection fittings to cross beams or transverse beams is considered as a repetition of activity, even though there are some differences in sequence due to the length of beams and distance of the beam builder to the installation point. Also, the construction of cross beams was considered a repetition, but there are both long and short cross beams, with necessarily different requirements for power and duration of fabrication activity.

Another point of interest to the analyst is the separation of certain functions, which in some cases are obviously performed in parallel during the same time period. At the time of beginning the analysis it was not clear which functions could be combined. As the effort proceeded, it was felt useful to maintain a separate identity for many of these functions to avoid inordinate efforts in renumbering the sequences and redefining activities. Where of obvious advantage, two or more functions were combined for analysis into one Construction Activity Data Sheet (these sheets are described in the following Section 5.3).

## 5.2 CONSTRUCTION PROCESS

The overall process of space construction during the first mission (outlined in the foregoing Section 5.1.2) is further explained and illustrated in this section. In addition, key issues and trades performed during the systems analysis are highlighted.

For purposes of this discussion, the construction process begins after arrival at orbital altitude, opening of payload bay doors and preparation of the orbiter systems for orbital operations. This includes checkout and deployment of the Remote Manipulator System (RMS) to a "ready" position. Figure 5.2-1 illustrates this initial condition, with all cargo still stowed in the payload bay.

The initial effort is to grasp the stowed construction fixture with the RMS standard end effector, rotate and translate it to a position near the forward end of the payload bay (Figure 5.2-2), where it is docked to a special berthing<sup>1</sup> fixture on the orbiter and remotely deployed.

The RMS handling method was selected to avoid the complexity and constraints on motion which would be required to rotate the construction fixture into position by a special mechanism. Also, subsequent flights require a similar berthing activity to attach the orbiter to the construction fixture. Remote deployment of the construction fixture was selected to facilitate rapid preparations for

<sup>1</sup>Berthing is defined as maneuvering two modules or spacecraft into contact using a manipulator (per Space Operations Center System Analysis Study, JSC-16244)

- READY THE ORBITER & RMS FOR CONSTRUCTION




Figure 5.2-1. Initial Conditions for Construction—First Mission

• DEPLOY MAIN CONSTRUCTION FIXTURE




Figure 5.2-2. RMS Transporting the Construction Fixture to Operational Location



C-2

construction, and was judged appropriate for assuming accurate alignment of the key portions of the building equipment. Also, this approach minimizes problems of electrical connections in space which are not necessarily related to the technology concerns of constructing the space fabricated platform. However, the design of the construction fixture will exercise many areas of technology related to space-deployable structures.

The next step, shown in Figure 5.2-3, is to extract the beam builder and its attached devices, transport it to the deployed construction fixture and install it on the rotary head in position for fabricating the first longitudinal beam. The attached devices include a device for installing the so-called attachment ports (for installing payloads and other components to ends of the longitudinal beam), a holder/dispenser with six attachment ports, a support tripod which interfaces with the construction fixture, lights and a TV camera.

Methods for extracting the beam builder machine (and possibly the construction fixture) are similar to initiating deployment of other large payloads by RMS. A payload installation and deployment aid (PIDA) may be required to assure safe clearances and proper orientation for RMS access to a desirable grappling point which will facilitate attachment of the beam builder to the construction fixture. This is an important issue of concern to all in-space assembly and construction operations. Ideally, the grappling point should aid the entire process of reach and vision for grappling, extraction, transport, and attachment at the assembly point and subsequent return to stowage, if required. The device for attaching the beam builder to the construction fixture is a self-aligning 3-petal device similar to the NASA PIDA interface device. However, it also includes electrical connectors for power control and sensor signals between the beam builder assembly and the construction fixture/crew cabin.

After checking out the system, fabrication begins on the first longitudinal beam as shown in Figure 5.2-4. The beam builder forms a short section, and stops. An attachment port is then installed, and fabrication continues until sufficient length is achieved. The beam is then cut, translated longitudinally a short distance by the powered rollers of the construction fixture and held while another attachment port is installed.

In parallel with the above operations, a second construction station is set up on the aft portion of the payload bay, as also shown in Figure 5.2-4. This activity could be performed later (as shown on the Logic Diagram - Figure 5.1-2), but the inactive period for the RMS during beam fabrication provides an early opportunity to accomplish a parallel operation and thus reduce overall construction time.

The beam builder complex is then rotated 120°, to a new position where it again fabricates a longitudinal beam. During this period the previously built longitudinal beam is withdrawn through the construction fixture while a harness of electrical cables is unreeled and attached to it along one face. These concepts are illustrated in Figure 5.2-5. After fabrication of the second longitudinal beam and assembly of its attachment ports, the beam builder is again rotated 120° counterclockwise and the third (apex) longitudinal beam is fabricated. During this period the first longitudinal beam (with installed electrical lines) is returned to its original fabricated position.

• INSTALL BEAM BUILDER




Figure 5.2-3. RMS Transporting Beam Builder to Deployed Construction Fixture

ORIGINAL PAGE IS  
OF POOR QUALITY

- FABRICATE FIRST LONGITUDINAL BEAM
- SETUP WORK STATION 2




Figure 5.2-4. Fabricating the First Longitudinal Beam  
and Setting Up Construction Station No. 2

- FABRICATE 2ND LONGITUDINAL BEAM
- INSTALL WIRE HARNESS ON 1ST BEAM




Figure 5.2-5. Fabrication of 2nd Longitudinal Beam During  
Wire Laying on First Longitudinal Beam

Upon completion of all three longitudinal beams, the beam builder is transported from the construction fixture to the 2nd construction station, as shown in Figure 5.2-6. The support tripod for the beam builder (which is left attached to the construction fixture during the move) is then removed from the construction fixture and stowed in the payload bay. Additional reconfigurations of the construction fixture and the attach port installation system are accomplished to prepare for fabrication and assembly of crossbeams and transverse beams. One crew member suits up and egresses through the Orbiter Air Lock at this time in order to visually inspect Construction Station No. 2 and then occupy the EVA work station on the Construction Fixture (Station No. 1). He remains in the vicinity of Construction Station No. 2 during initial fabrication of the first transverse beam, which is illustrated in Figure 5.2-7. He also observes and may help guide (by words and signals) the RMS as it grapples and connects into a special end effector which enables it to handle the beams fabricated at the second work station.

Upon completion of the first transverse beam, the RMS transports it to the forward side of the construction fixture (as shown in Figure 5.2-8) where it is transferred to a special beam positioner under control of the astronaut at the EVA work station. In the meantime, a second transverse beam is being fabricated, and the RMS must return to grasp it and transport it to the aft portion of the construction fixture. The EVA astronaut joins the first transverse beam to the longitudinal beams by electrical heating of intersection fittings (Figure 5.2-9) and makes initial hookups of the cross brace cords at the joints. He then reorients himself to deal with the 2nd transverse beam, and repeats the process.

The first (long) crossbeam fabrication is started after the 2nd transverse beam is removed from the Construction Station No. 2. This crossbeam has attachment ports at each end, docking ports for teleoperator servicing and electrical wiring as well as the intersection fittings which are on the transverse beams, as shown in Figure 5.2-10. This crossbeam is transported and joined to the longitudinals in the same manner as are the transverse beams, but also requires the EVA astronaut to connect electrical wires to the first longitudinal beam, as indicated in Figure 5.2-11. The complete structural assembly is then translated through the construction fixture to a position for assembly of a second set of three beams to form a new frame set (Figure 5.2-12). In the meantime, fabrication is initiated on the next transverse beam, which is grasped by the RMS and positioned as close as is feasible to be ready for the joining to the longitudinals. At the end of the translation an observation and record is made of the structural alignment by use of an electro-optical measuring system described later.

The complete cycle of fabrication and assembly of crossbeams and transverse beams is again repeated, with a few exceptions. The exceptions include omission of electrical lines on the short crossbeams (and thus deleting the interconnection to longitudinals) and the addition of more connections and subsequent tensioning of cross-brace cords as each beam is joined. Figure 5.2-13 illustrates the sequence of EVA crew activities during cord installation and tensioning.

• MOVE BEAM BUILDER TO STATION 2




Figure 5.2-6. Moving Beam Builder to Construction Station No. 2

- FABRICATE FIRST TRANSVERSE BEAM
- INITIATE EVA




Figure 5.2-7. Fabrication of First Transverse Beam

• INSTALL TRANSVERSE BEAM NO. 1





Figure 5.2-8. Transport and Installation of First  
Transverse Beam During Fabrication of Second





PROCEDURE

- ASTRONAUT TAKES POWER SUPPLY PIGTAIL FROM LOCATION ON BEAM POSITIONER AND MAKES CONNECTION TO ELECTRODE ON THE INTERSECTION FITTING.
- THE CHERRY PICKER IS TRANSLATED TO THE ADJACENT LONGITUDINAL BEAM WHERE THE PROCEDURE IS REPEATED.
- BOTH INTERSECTION FITTINGS REMAIN CONNECTED FOR THE REQUIRED "COOKING" PERIOD.
- WHEN THE CROSS BEAM IS WELDED TO THE LONGITUDINAL BEAM, THE POWER SUPPLY PIGTAILS ARE REMOVED

Figure 5.2-9. Procedure for Joining Crossbeams and Transverse Beams to Longitudinal Beams




Figure 5.2-10. Fabrication of Crossbeam and Installing  
Bracing Cords

• PERFORM EVA ELECTRICAL HOOKUP




Figure 5.2-11. EVA Connection of Electrical Lines  
- Crossbeam to Longitudinal

- TRANSLATE STRUCTURE
- FABRICATE TRANSVERSE BEAM




Figure 5.2-12. Translation of Platform Structural Assembly




Figure 5.2-13. Bracing Cord Installation

ORIGINAL PAGE IS  
OF POOR QUALITY

The process of construction continues with alternate frames containing long crossbeams and short crossbeams until completed. Then, the primary construction fixture is configured for intended operation, the second construction station is dismantled and return cargo is stowed. Figure 5.2-14 illustrates the condition prior to separation.

The return cargo includes the central portion of the primary construction fixture, the beam builder machine, attachment port holder and installation device, intersection fitting installation device and wire laying reel. During the preparation of the activity analysis it was planned to leave the modified open cherry picker (astronaut support platform) in orbit, attached to the construction fixture. However, later analysis connected with the second mission suggests a high desirability for returning this item to earth for adding a stabilizer arm, additional lights and tool support devices to make it suitable for handling struts, deployable support structures and equipment modules. It was decided to make this change in the process, but in order to conserve study resources, the Construction Activity Data Sheet was not revised.

After deployment of the libration damper RCS booms on the Construction Fixture, the system is checked out and the orbiter is separated. This completes the construction activity for the first mission.

### 5.3 ACTIVITY ANALYSES

The primary working analysis documents for the construction integration effort were designated as Construction Activity Data Sheets. As shown in Figure 5.3-1, these data sheets (with attachments) performed a key role in the construction system analyses. They were used for two basic purposes: (1) A record of design concept and analyses performed and (2) A requirements development document for those designs and procedures not yet clearly formulated. One Construction Activity Data Sheet was prepared for each of the designated blocks in the construction logic diagram (Figure 5.1-2). The total set of these documents is included in Appendix B.

Note that the totality of this documentation represents a majority, but not all, of key requirements for time, power/energy, crew and equipment required to accomplish the construction. It was found helpful during this period to use the metaphor of building a brick wall: The Construction Activity Data Sheets represent the "bricks", whereas certain adjustments and overall integration concerns are thought of as "mortar" which fills in the gaps between "bricks", holds them together, and forms a cohesive whole to the first mission integrated analysis description, which is presented later.

For example, each Construction Activity Data Sheet indicates which key equipment is used and for how long to accomplish the specific activity. However, it does not necessarily account for standby power demands between such activities, nor does it show duplications of lighting power where complimentary activities are performed in parallel at the same station, using the same lights. Furthermore, many functions are repeated during the course of construction, with only minor variations. A separate activity description was not created for such repetitions.

• READY CONST FIXTURE FOR UNTENDED OPS




Figure 5.2-14. Preparation for Untended Operations




Figure 5.3-1. End-to-End Construction Activity Analysis





However, these documents provide a useful compilation of design and procedure details concerning how the construction processes was conceived and they formed a basis for later integration analyses.

One further qualification is appropriate: The Construction Activity Data Sheets were originally prepared for the platform configuration which was current at the time of preparation. As a result of the construction analysis a major change in design was made approximately mid way during the study period (near the close of the first mission analysis) in which the platform overall length was reduced from 136 meters to 108 meters. Concurrently, the long cross beams were reduced from 20 meters to 17.4 meters. It was recognized that this change implied that iterations should be accomplished on those activity data sheets which related to certain long beam fabrications and platform translation activities. However, limited resources did not permit a complete iteration for all the data sheets to reflect the new lengths. In general, the integrated timelines and integrated mission power profiles for all missions were based on the older (longer) configuration. Thus, the integrated analyses are conservative in estimating somewhat longer work period durations than needed for the final design. Where pertinent, those Construction Activity Data Sheets in Appendix B which contain time and energy estimated based on the final downsized configuration are indicated by an asterisk.

In view of the pioneering aspects of this Space Construction System Analysis study, some comments are appropriate concerning lessons learned in analysis and documentation techniques. One such lesson is that the estimating of timelines, power and energy is facilitated by listing all three in one table of data. However, in doing so, care must be taken to note activities which contribute to power and energy demand but do not add to the time. Another observation is that the activity analysis sheets need only list key construction equipment items, tasks and formulas or rationale for estimating time, power and energy. The summarizing of total power and time for the mission is a task better suited to the integration analyses, in which all the concurrent and sequential activities are considered together on a master chart.


#### 5.3.1 Structural Analysis Verification of "X"-Bracing Installation Approach

This article describes the structural analysis performed to verify the feasibility of the X-bracing installation and pretensioning construction approach described in the Construction Activity Data (11.2 - 11.3, Appendix B). The essential technique of the X-bracing operations is that in each face of the tri-beam initial pretension of the first cord is to a small load such as 66 to 112 N (15 to 25 Lbs) and that of the second cord to a load of 2360 N (530 lbs). The premise is that the first cord will then have a tension of 2360 N (530 lbs) + 150 N (35 lbs). The structural analysis conducted validated this premise (which, incidentally, is similar to that of the astromast).

Table 5.3-1 illustrates the results of NASTRAN analyses performed on a single bay model of the tri-beam. The lowest tension force in element 12-26 is 2249 N or 111 N less than the nominal value. Further, the foregoing did not include thermal change effects. A 55° C temperature change in the cord will effect a tension load change of 50 N (11.5 lbs).

Table 5.3-1. Tri-Beam Cable Pretension Loads

Cables in Place	Action	Cable Tension (N)					
		12-26	8-30	12-19	1-30	8-19	1-26
12-26	Pretension cable 12-26 to 111 N	111					
12-26, 8-30	Pretension 8-30 to 2360 N	2320	2360				
12-26, 8-30, 12-19	Pretension 12-19 to 111 N	2308	2374	111			
12-26, 8-30, 12-19, 1-30	Pretension 1-30 to 2360 N	2295	2308	2310	2360		
12-26, 8-30, 1-30, 12-19	Pretension 8-19 to 111 N	2311	2290	2292	2371	111	
8-19 All in place	Pretension 1-26 to 2360 N	2249	2277	2279	2309	2299	2360



It is evident from Table 5.3-1 that the tailoring of the second cord tension values can be determined during ground development tests to minimize the 111 N load reduction in cable 12-26 to approximately 40 N. Maintenance of the tension loads to +150 N in the presence of the thermal variations appears achievable even with  $\pm 200^{\circ}$  F relative temperature changes in the X-bracing cords.

#### 5.4 INTEGRATION ANALYSIS

The integration analysis for the first mission was undertaken to develop a complete end-to-end synthesis of the applicable on-orbit construction process. This was the first detailed look at combining all the activities into a complete and logical sequence of work from which could be derived requirements for total time, average power, peak power, total energy, and number of crew required. Another output desired was the need for construction support equipment, including lighting and TV requirements for accomplishing the mission.

The overall process of analysis is indicated in Figure 5.4-1. Actual construction work requirements and crew activity scheduling requirements were developed in parallel and then combined into an integrated activity timeline. This output was represented graphically for visual check of parallel activities, power peaking problems, and crew utilization. Based on this integrated activity timeline, average power and exposure to peak power conditions were calculated, total energy requirements were calculated, the the results summarized in tabular format. These data were used to develop graphical presentations of the power profiles and total energy usage.




Figure 5.4-1. Integration Analysis Process

Construction support equipment needs, including lighting and TV, were developed from the *Construction Activity Data Sheets*, together with the considerations of the integrated timeline analysis, power, and energy. These outputs are summarized in following sections of this report (Sections 5.4.1 through 5.5). A similar process was used for the integration analyses of the second and third missions, which are discussed in Sections 6.0 and 7.0, respectively.

#### 5.4.1 Integrated Activity Timelines

The detailed synthesis of the first mission construction activity began with representing the previously described major activities as bars on an integrated sequence chart, using a non-scaled, working diagram. The major purposes of this initial effort were to (1) define critical sequences of activities, (2) determine where additional, special activities might be needed for continuity and completeness, and (3) examine opportunities for parallel accomplishment of activities. Each bar was labeled with its appropriate duration in minutes (to the next largest integer minute). A preliminary review was performed to consider power, crew scheduling and equipment usage.

With the information gained from the preliminary review, a scaled timeline of the integrated activity was prepared, as shown in Figure 5.4-2. Each numbered construction activity and several non-numbered, but major "fill-in" construction activities are listed in the column on the left. For each listed activity, a bar of appropriate length is shown to the right along the time scale in the selected time frame. EVA crew rest periods and shift change periods are also shown along the bottom of the chart. The crew work shifts and rest were determined by a parallel, but separate analysis (described later) taking into account the typical work station requirements (parallel IVA and EVA work), EVA suit donning and doffing times and other standard work-rest cycle requirements derived from NASA planning documents (References 5-1, 5-2 and 5-6). See Section 5.4-2 for details of these crew activity analyses.

The integrated timeline was used as a basis for developing power profile charts, energy consumption analyses and other time-related analyses which are discussed in following sections.

The process of synthesizing the integrated activity timeline brought out the need to account for several simultaneous and interim activities and status conditions not specified during preparation of the Construction Activity Data Sheets. For example, the beam fabrication machine requires about seven minutes (430 seconds) to warm up prior to actual beam fabrication, but otherwise may be turned off completely between fabrication periods. Early in the integration analysis a general checkout activity is also presumed to be required after each relocation and setup of the beam builder machine at a new location. In lieu of detailed information on this type of activity, power requirements were assumed as equal to the average required for beam fabrication (2.24 kw). Later, the seven minutes warm up power was estimated as that required only for the heaters (1.53 kw). These warm up times were accounted for in calculating power, energy and time, but do not show as blocks of activity on Figure 5.4-2.

Similarly, the Remote Manipulator System (RMS) was assumed to require standby heating (at 1.050 kw) on a 50% duty cycle basis most of the time during construction activity. In addition, it was assumed the RMS arm would be "parked" at such times in advantageous position for use of the wrist light and wrist TV camera (together with its heater, also operating on a 50% duty cycle). The arm thus function as an auxiliary "camera stand" to provide alternate viewing angles of construction operations. Such standby status conditions are not specified in Figure 5.4-2, primarily to avoid further visual clutter.

However, the analyst needs such information on a working document as a reminder of power demands.

Another consideration of major power demand significance is that of general lighting, such as by use of orbiter payload bay lights, construction fixture lights and other specific lamps. A working document should list each lamp and show a bar of "activity" when it is turned on. TV cameras, tilt and pan mechanisms, control/display items, etc. also are of some concern, but may not draw significant power in comparison to uncertainties of the RMS or of beam fabrication.

The detailed analytical effort involved in calculating power profiles and energy from a chart such as shown in Figure 5.4-2 is quite time consuming and tedious. A portion of the activity is essentially repetitious but is slightly different for each cycle, primarily because of crew rest and crew exchange period delays. For purposes of this preliminary type of analysis it was felt appropriate to create a somewhat artificial timeline segment chart for a representative cycle. The resulting chart is shown in Figure 5.4-3. In preparing this chart the activities were first sequenced as if a non-tiring robot was accomplishing the work. Then the probable requisite crew rest periods were added to compile a representative total time. Peak and average power estimates based on such a chart are slightly higher than expected in practice, but total energy should be very closely approximated. The chart cycle includes one set of activities for fabricating a frame with a short crossbeam and one for a frame with a long crossbeam, with associated wiring installations and connections. Approximately 5 such cycles are required after assembly of the first frame which has a long crossbeam, and this was the basis for the energy estimation. In fact, the last cycle is again slightly different, because of tying off the cross-brace cords, the small extension stubs of the longitudinals and the lack of need for a final translation and subsequent structural alignment check.

In the case of synthesizing timelines for a phase C-D study, it would be advantageous to set up each cycle with crew rest periods at common times in each sequence, so that each cycle is exactly repetitious to the degree possible. This would ease the difficulty reduce cost, mission planning and crew training. However, the potential need for flexibility in on-site activity scheduling should be considered and provisions made for computer-generated automatic checklists which would account for necessary logic of construction processes and help minimize effects of unforeseen delays by "work around" methods.

MISSION TIME G.E.T.

0:00

1:00

2:00

3:00

4:00

- 1.0 ERECT & DEPLOY CONSTRUCTION FIXTURE
- 2.0 INSTALL BEAM BUILDER ON CONSTRUCTION FIXTURE  
CHECKOUT BEAM BUILDER
- 3.1 FABRICATE LONGITUDINAL BEAM
- 3.2 INSTALL ATTACH PORTS ON LONGITUDINAL BEAM
- 7.0 SETUP CONSTRUCTION STATION No. 2
- 4.0 REPOSITION BEAM BUILDER 120°
- 5.1 WITHDRAW LONGITUDINAL BEAM No. 1
- 5.2 INSTALL ELECTRIC LINES ON LONGITUDINAL BEAM No. 1
- 6.0 RETURN LONGITUDINAL BEAM No. 1 TO FABRICATION POSITION
- 8.1 RELOCATE BEAM BUILDER TO CONSTRUCTION STATION No. 2  
CHECKOUT BEAM BUILDER AT CONSTRUCTION STATION No. 2  
RMS END EFFECTOR CHANGE  
EVA ASTRONAUT EXPRESS & INSPECTION TOUR
- 9.1 FABRICATE TRANSVERSE BEAM
- 9.2 JOIN INTERSECTION FITTINGS TO TRANSVERSE BEAM
- 10.0 TRANSPORT TRANSVERSE BEAM
- 8.2 RECONFIGURE CONSTRUCTION FIXTURE & OCCUPY EVA STATION
- 11.1 JOIN TRANSVERSE BEAM TO LONGITUDINAL BEAMS
- 11.2A INITIAL CONNECTION OF X-BRACE CORDS
- 11.2B JOIN X-BRACE CORDS TO LEADING & TRAILING EARS
- 11.3 TENSION X-BRACE CORDS
- 12.1 TRANSPORT TRANSVERSE BEAM
- 12.2 FABRICATE CROSS BEAM (LONG/SHORT)
- 12.3 INSTALL ATTACH PORTS ON CROSS BEAM
- 12.4 INSTALL ELECTRIC LINES ON CROSS BEAM
- 12.5 INSTALL TELEOPERATOR DOCKING PORTS
- 13.0 TRANSPORT CROSS BEAM
- 14.0 CONNECT ELECTRIC LINES FROM CROSS BEAM TO LONGITUDINAL BEAM
- 15.0 TRANSLATE STRUCTURE ONE BAY LENGTH
- 16.0 CHECK STRUCTURAL ALIGNMENT
- 17.1 CONFIGURE CONSTRUCTION FIXTURE FOR UNTENDED OPERATIONS
- 17.2 STOW RETURN CARGO IN PAYLOAD BAY

EVA ASTRONAUT No. 1 TRANSPORT / REST / LUNCH

EVA ASTRONAUT No. 2 TRANSPORT / REST / LUNCH

EVA ASTRONAUT No. 3 TRANSPORT / REST / LUNCH

PRECEDING PAGE BLANK NOT FILMED

ORIGINAL PAGE IS  
OF POOR QUALITY

1 FOLDOUT FRAME

5:00 6:00 7:00 8:00 9:00 10:00 11:00

87

26

10

40

125

20

0

0

125

0

53


2

38

138

2

FOLDOUT FRAME





20:00

21:00

22:00

23:00

24:00

25:00

26:00

(On Cross Beam)

(On Cross Beam)

(On Cross Beam)

16

16

16

16

16

16

16

16

16

16

16

16

16

16

16

16

30

30

30

2 10

2 20

2 10

0 0

0 0

0 0

34

34

34

4

6

0

20

10

10

10

10


10

10

10

10

22:00 24:00 27:00 28:00 29:00 30:00 31:00 32:00



5 FOLDOUT FRAME

30:00

31:00


32:00

33:00

34:00

35:00

36:00



6 FOLDOUT FRAME

424

## 7 FOLDOUT FRAME




Figure 5.4-2. Integration Activity Timeline

8 BOLDOUT FRAME

48:00




57:00

48:00

69:00

70:00

71:00



DESIGN MARGIN

21 Hrs 13 Min

Integration Activity Timeline - First Mission

9 FOLDOUT FRAME

SCALE ✓	OR 1/2" = 1' FZ DATE 1/14/80 WOBEL	Rockwell International Space Systems Group 12114 Laurel Road Downey, CA 90241	
INTEGRATED ACTIVITY TIMELINE 1ST MISSION			42662-75

5-31, 5-32

PRECEDING PAGE BLANK NOT FILMED

MISSION TIME - G.E.T.



ACTIVITY

- 9.1 FABRICATE TRANSVERSE BEAM\_\_\_\_\_
- 9.2 JOIN INTERSECTION FITTINGS TO TRANSVERSE BEAM\_\_\_\_\_
- 10.0 TRANSPORT TRANSVERSE BEAM\_\_\_\_\_
- 11.1 JOIN TRANSVERSE BEAM TO LONGITUDINAL BEAMS\_\_\_\_\_
- 12.2B JOIN X-BRACE CORDS TO LEADING & TRAILING EARS\_\_\_\_\_
- 11.3 TENSION X-BRACE CORDS\_\_\_\_\_
- 12.1 TRANSPORT TRANSVERSE BEAM\_\_\_\_\_
- 12.2 FABRICATE CROSS BEAM (SHORT/LONG)\_\_\_\_\_
- 12.3 INSTALL ATTACH PORTS ON CROSS BEAM\_\_\_\_\_
- 12.4 INSTALL ELECTRIC LINES ON CROSS BEAM\_\_\_\_\_
- 12.5 INSTALL TELEOPERATOR DOCKING PORTS\_\_\_\_\_
- 13.0 TRANSPORT CROSS BEAM\_\_\_\_\_
- 14.0 CONNECT ELECTRIC LINES FROM CROSS BEAM TO LONGIT. BEAM\_\_\_\_\_
- 15.0 TRANSLATE STRUCTURE ONE BAY LENGTH\_\_\_\_\_
- 16.0 CHECK STRUCTURAL ALIGNMENT\_\_\_\_\_

ALLOWANCE FOR ASTRONAUT EGRESS, REST, LUNCH & INGRESS\_\_\_\_\_

HOLDOUT FRAME

G.E.T. 0:00 1:00 2:00 3:00



INGRESS

2 FOLDOUT FRAME







Figure 5.4-3. Representative Cycle of Rep



5.4-3. Representative Cycle of Repetitive Construction Activity—First Mission

4

FOLDOUT FRAME



PRECEDING PAGE BLANK NOT FILMED


#### 5.4.2 Crew Activity Scheduling Analysis

The primary driver in crew size and work schedule analysis was to accomplish the construction in minimum time, within the usual constraints of crew safety, stowage volume, weight and power limits. As a first approximation, it was assumed that minimum construction time would result in the lowest cost per flight, particularly if a need for additional kits of supplies is thus avoided.

Review of the crew workload requirements in the Construction Activity Data Sheets showed that the majority of the construction could be accomplished with a crew of two persons operating simultaneously. One crew member would be in the orbiter at the aft flight deck, and the other would be performing extravehicular activity EVA. Exceptions occur during the initial deployment of the Construction Fixture (Station No. 1) and Construction Station No. 2, and during the preparations for departure near the end of the construction period. In these cases the crew work is done from the cabin. Only one person appears to be necessary, but additional crew are available to help, and would likely be assigned active roles.

The baseline crew activity schedule developed is shown in Figure 5.4-4. It requires a crew of six, operating in teams of two persons each, three, eleven-hour work shifts per day. Except for the start-up period, one member of each team is an EVA worker and the other is the IVA operator of the RMS and other remotely controlled construction equipment. A key consideration here is that the IVA operator is also cross-trained in EVA operations and is prepared to egress on short notice to effect a rescue of the EVA worker. In order to accomplish the eight hour EVA workshift it was assumed that there would be developed an acceptable two-gas pressure suit and appropriate life support system operating at a high pressure (nominally 8 pounds per square inch). This equipment would avoid three hours of pre-breathing of 100% oxygen prior to egress. With such a capability, the EVA astronaut can theoretically accomplish eight hours of EVA (including rest periods) in an eleven hour work day, using present donning and doffing times of 1.5 hours at each end of the 8 hour work period. Reducing the donning/doffing times could reduce the work day length.

Another significant problem of crew scheduling is also solved by the high-pressure suit system. Specifically, it avoids the necessity for an IVA operator to be on 100% oxygen for 8 to 9 hours per day at full cabin pressure of 14.7 psi. This would be necessary using a single person as inside backup crew member in parallel with a 5- to 6- hour EVA shift with the EVA astronaut using the 4 psi suit currently under development for the space shuttle EVA operations. According to medical research results obtained by NASA (Reference 5-1), only 6 hours per day of continuous exposure to 100% oxygen to cabin atmospheric pressure (14.7 psi) is acceptable on a daily basis. Thus, use of the 4 psi suit would require an additional IVA backup crew member or a separate, third person per team acting as EVA crew member "buddy" on standby. Both options are undesirable. As currently designed, the construction system does not effectively utilize an additional EVA crew person for construction work. Furthermore, the orbiter cabin would become excessively crowded with the 9 crew members required to operate three shifts per day. Maintaining



a crew limit of six persons, using the current 6 hour limit suit, and three hours of pre-breathing oxygen would significantly extend the required time on orbit.

Both the available EVA time per crew shift and the rest periods associated have an effect on specific construction timeline layouts. Complete analyses of alternate timelines were not developed for this study. However, an alternate schedule based on a crew of four and two shifts per day was prepared as shown in Figure 5.4-5. At the expense of longer mission time, this schedule offers advantages of less crowded crew quarters, and more utilization of the available crew. An obvious concern of the baseline schedule was that one member of the crew is utilized for only one 8 hour EVA shift during the first mission, probably after several months of expensive training.

A remarkable consequence of the baseline crew utilization schedule is that the entire construction is nominally completed within approximately two days elapsed time (three days with allowance factor). The alternate schedule (Figure 5.4-5) would require about 2.7 days nominal time (4.06 days with allowance factor) depending on specific effects of crew rest periods.

In developing the crew activity schedules, NASA recommended allowances were utilized based on existing documentation (Reference 1 and Reference 2). Figure 5.4-6 shows the typical individual daily work-rest cycle adapted for a nominal 11 hour work day. The crew activity schedules provide adequate time for orbiter housekeeping functions during each shift. The scheduled duties considered for analysis are shown in Table 5.4-1, which was developed from data in Reference 2. Because of the necessity to setup each team of two crew members on staggered diurnal cycles, there is considerable free time for other crew members at the beginning and end of the construction period.

Crew rest periods during EVA are scheduled for approximately every fifty minutes and last for 10 minutes. Minor adjustments are shown in the integrated timeline to match appropriate break points in the activity. A snack period of twenty minutes is also scheduled for the middle of the eight hour period. It is presumed this will be used for a high-calorie nutrition bar inside the suit. At the beginning and end of each crew shift there is a 10 minute transport period for the astronaut to return to the airlock or move from the airlock to the work station as appropriate.

#### 5.4.3 Lighting and TV Requirements Analysis

The general impacts of naturally available lighting and requirements for artificial lighting were investigated in significant depth during Part 1 of this construction system analysis contract study. As a result, the concepts of construction fixtures, work station designs and overall methods have been evolved toward minimum demands for power to provide artificial illumination. The systems analysis approach used in this study has been to specify a minimal set of lamps needed to perform each particular construction activity, then examine the overall integrated activity to determine additional needs or possible reductions in requirements.

MISSION TIME - G.E.T.

0:00

5:00

10:00

15:00

20:00

25:00

30:00

ASTRONAUT No. 1

M	8:00 SLEEP	M	8:00 EVA	
---	------------	---	----------	--

ASTRONAUT No. 2

	M	4:43 IVA	M	8:00 SLEEP	M		
--	---	----------	---	------------	---	--	--

ASTRONAUT No. 3

M	8:00 SLEEP	M	8:00 IVA	
---	------------	---	----------	--

ASTRONAUT No. 4

M	4:43 IVA
---	----------

M	8:00 SLEEP	M		
---	------------	---	--	--

PRECEDING PAGE BLANK NOT FILMED

| FOLDED OUT FRAME

20:00 25:00 30:00 35:00 40:00 45:00 50:00 55:00 60:00

M		8:00 EVA			M		8:00 SLEEP		M		8:00 EVA			M
---	--	----------	--	--	---	--	------------	--	---	--	----------	--	--	---

8:00 SLEEP		M		8:00 EVA			M		8:00 SLEEP		M		8:00 EVA		
------------	--	---	--	----------	--	--	---	--	------------	--	---	--	----------	--	--

M		8:00 IVA			M		8:00 SLEEP		M		8:00 IVA			M		8:00 SLEEP
---	--	----------	--	--	---	--	------------	--	---	--	----------	--	--	---	--	------------

8:00 SLEEP		M		8:00 IVA			M		8:00 SLEEP		M		8:00 IVA		
------------	--	---	--	----------	--	--	---	--	------------	--	---	--	----------	--	--

Figure 5.4-5. Alternate (4-Man) Crew

2 FOLDOUT FRAME




Figure 5.4-5. Alternate (4-Man) Crew Activity Schedule—First Mission

3 FOLDOUT FRAME






Figure 5.4-6. Typical Time Allocation  
for Shuttle EVA Work Day

Table 5.4-1. Orbiter Housekeeping Time Requirements

	Frequency	Duration (Min.)	Daily Time Reqt. (Min.)
Waste Compartment Cleaning	1	15	15
Water Dump	3	5	15
CO <sub>2</sub> Absorber Replacement	4	5	20
Fuel Cell Purge	3	5	15
Status Report	1	15	15
GN&C Update (free drift)	3	15	45
Trash Stowage	1	15	15
Total Daily Time Requirements			140 (2 Hrs. 20 Min.)

During the development of the integrated timeline analysis the analyst attempted to keep a mental picture of which lamps and TV cameras were called for by the specific combinations of activities and to evaluate whether each lamp or camera was useful or redundant. The total power demand for lighting and TV was then calculated. The calculations are conservative, in that no account was taken of daylight versus dark side operations. It was felt this condition would represent the most practical operational condition, avoiding complexities of sensors and crew workload concerns for transitions from light side to dark side of orbit or vice versa. In fact, some alleviation of power peaks could be accomplished (if necessary) by turning off those un-needed work station lamps which are compatible with such frequent cycling. However, frequent on-off cycling of lights in the orbiter payload bay is undesirable. The integration analysis assumes that different numbers of payload bay lamps are used during the construction period in a consciously selective manner, according to expected need. For example, the lamp on the forward bulkhead is initially called for to aid observation of the handling of the construction fixture and its installation onto the docking port. Additional lamps are turned on as equipment is removed from the bay, both to provide direct illumination of the key surfaces of the components and to provide location information by means of background contrast, utilizing available open spaces between cargo items (to be determined later). Eventually, the number in use is reduced to two in the aft portion of the bay, where the crossbeams and transverse beams are fabricated. During stowage of equipment for the return trip all 6 of the payload bay lamps in the side walls will probably be used again.

Several types of small marker lamps, "running lights" and crew-held portable lamps were not specifically included in the analyses of power. It was assumed that their power demands would be small compared to the uncertainties of total power requirements. Therefore, specific mention or inclusion would not contribute greatly to overall solution of the problem.


It was considered that the construction fixture needs several types of lamps at the 100 to 200 watt level to illuminate beam positioning and joining operations. These would be selectively used according to need. Usually, not more than 200 watts would be required.

For the astronaut EVA work station (modified cherry picker and maneuvering arm), it was assumed that three 60-watt lamps would be available as needed to illuminate key work areas. This is in conformance with MRWS Open Cherry Picker design concepts proposed during Grumman studies. Two 100 watt lamps were assumed for illumination of the output area of the beam builder machine where attachment ports are also installed.

Television cameras of the same general type and power demand as planned for the RMS were identified for use with the beam builder/attachment port installation area, and various places on the construction fixtures permitting observation of EVA and aiding transportation of beams on observation of equipment. Most of these would incorporate a tilt and pan capability, but the capability is not always needed.


Figure 5.4-7 summarizes the major types and locations of lights and TV camera installations for the first mission.

# **WELDOUT FRAME**



ORIGINAL PAGE IS  
OF POOR QUALITY

PRECEDING PAGE BLANK NOT FILMED



2 FOLDOUT FRAME

ITEM NO.	DESCRIPTION—CHARACTERISTICS/USAGE
(1)	ONE INCANDESCENT FLOODLAMP AND TV CAMERA FIXED TOGETHER ON TILT/PAN MOUNT. LOCATION—YOKER CONSTRUCTION STATION NO. 1. PURPOSE—ASSIST PORT & PRE-POSITIONING OF FORWARD TRANSVERSE AND CROSSBEAMS, GENERAL ASSEMBLY AND STOWAGE OF ASTRONAUT OBSERVATION (SAFETY AND PUBLIC RELATION)
(2)	TWO INCANDESCENT LAMPS, ONE FIXED ON EACH SIDE OF CAMERA. SET IS MOUNTED ON TILT/PAN MECHANISM. LOCATION—NEAR FABRICATION END OF BEAM BUILDER MACHINE. PURPOSE—OBSERVE BEAM STRAIGHTNESS, QUALITY, INSTALLATION OF ATTACHMENT PORTS. ASSIST HANDLING OF CROSSBEAMS AND TRANSVERSE IN CONSTRUCTION STATION NO. 2 (RELOCATED WITH BUILDER MACHINE). BEAM FOCUSING IS DESIRABLE. OBSERVE MAXIMUM POSSIBLE LENGTH OF FABRICATED
(3)	ONE LAMP AND TV UNIT SIMILAR TO (1).
(4)	ONE ORBITER PAYLOAD BAY LAMP, METAL HALIDE TYPE (STANDARD ITEM). LOCATION—FORWARD BULKHEAD OF ORBITER PAYLOAD BAY, BETWEEN WINDOWS. PURPOSE (FOR CONSTRUCTION)—ASSIST HANDLING OF CONSTRUCTION STATION NO. 1 FROM PAYLOAD BAY STOWAGE TO DOCKING PORT. ASSIST EVA INGRESS, EGRESS.
(5)	ONE ORBITER DOCKING LAMP (STANDARD). LOCATION—BETWEEN DOCKING WINDOWS ON UPPER SURFACE OF ORBITER. FIXED, POINTING UPWARD. PURPOSE (FOR CONSTRUCTION)—ASSIST HANDLING OF CONSTRUCTION STATION NO. 1 FROM STOWAGE TO DOCKING. ASSIST ORBITER SEPARATION AT END OF CONSTRUCTION.
(6)	ONE LAMP AND TV UNIT SIMILAR TO (1). PURPOSE—SIMILAR TO (1), BUT ALSO INCLUDES OBSERVING OF ORBITER AND ACTIVITY AT CONSTRUCTION STATION NO. 2, STOWAGE FOR RETURN.
(7)	ONE LAMP AND TV UNIT SIMILAR TO (1). PURPOSE—SIMILAR TO (1), WITH SPECIAL EMPHASIS ON SETTING STOWAGE OF CONSTRUCTION STATION NO. 2; COVERING BOARD SIDE BLIND SPOTS.
NOTES	
(a)	ITEMS (1), (3), (6), AND (8) MAY ALSO ASSIST OBSERVATION
(b)	LAMPS ON ORBITER AND CONSTRUCTION FIXTURE NO. 1
(c)	MMU OR/AND EVA SUIT WILL HAVE WORKLIGHTS AND NAVIGATION
(d)	RUNNING LIGHTS AND BEACON FOR RENDEZVOUS NOT SHOWN

Figure 5.4-7. Lighting

# LIGHTS AND TV CAMERAS FOR CONSTRUCTION—FIRST MISSION

ITEM NO.	DESCRIPTION—CHARACTERISTICS/USAGE	PEAK POWER	ITEM NO.	DESCRIPTION—CHARACTERISTICS/USAGE
(1)	ONE INCANDESCENT FLOODLAMP AND TV CAMERA FIXED TOGETHER ON TILT/PAN MOUNT. LOCATION—YOKE OF CONSTRUCTION STATION NO. 1. PURPOSE—ASSIST TRANSPORT & PRE-POSITIONING OF FORWARD TRANSVERSE BEAMS AND CROSSBEAMS, GENERAL ASSEMBLY AND STOWAGE, EVA ASTRONAUT OBSERVATION (SAFETY AND PUBLIC RECORD).	0.247	(8)	ONE TV CAMERA WITH TILT/PAN MOUNT. LOCATION—RMS ELBOW (STANDARD ITEM). PURPOSE—ASSIST IN HANDLING SETUP, CONSTRUCTION, STOWAGE.
(2)	TWO INCANDESCENT LAMPS, ONE FIXED ON EACH SIDE OF TV CAMERA. SET IS MOUNTED ON TILT/PAN MECHANISM. LOCATION—NEAR FABRICATION END OF BEAM BUILDER MACHINE. PURPOSE—OBSERVE BEAM STRAIGHTNESS AND QUALITY, INSTALLATION OF ATTACHMENT PORTS. ALSO, ASSIST HANDLING OF CROSSBEAMS AND TRANSVERSE BEAMS IN CONSTRUCTION STATION NO. 2 (RELOCATED WITH BEAM BUILDER MACHINE). BEAM FOCUSING IS DESIRABLE TO OBSERVE MAXIMUM POSSIBLE LENGTH OF FABRICATED BEAM.	0.247	(9)	ONE LAMP AND TV CAMERA FIXED ON TILT/PAN MOUNT. LOCATION—RMS ELBOW (STANDARD ITEM BUT NEW MOUNT). PURPOSE—ASSIST IN HANDLING BEAMS, TRANSPORTING THEM TO PERFORM SETUP, CONSTRUCTION, STOWAGE.
(3)	ONE LAMP AND TV UNIT SIMILAR TO (1).	0.247	(10)	SIX METAL HALIDE LAMPS (STANDARD ITEMS). LOCATION—SIDE OF ORBITER PAYLOAD BAY; ONE OF SIX ILLUSTRATION—BACKGROUND FOR EXTRACTING EQUIPMENT, SET NO. 2 AND EVA INSPECTION DIFFUSERS OR BLINDS MAY BE USED TO PROTECT CAMERAS FROM DIRECT VIEW.
(4)	ONE ORBITER PAYLOAD BAY LAMP, METAL HALIDE TYPE (STANDARD ITEM). LOCATION—FORWARD BULKHEAD OF ORBITER PAYLOAD BAY, BETWEEN WINDOWS. PURPOSE—(FOR CONSTRUCTION)—ASSIST HANDLING OF CONSTRUCTION STATION NO. 1 FROM PAYLOAD BAY STOWAGE TO DOCKING PORT. ASSIST EVA INGRESS, EGRESS.	0.200	(11)	ONE TV CAMERA UNIT (STANDARD) WITH TILT & PAN MOUNT. LOCATION—FORWARD BULKHEAD OF ORBITER PAYLOAD BAY. PURPOSE—ASSIST IN SETUP OF CONSTRUCTION STATION NO. 1 FROM STOWAGE TO DOCKING. ASSIST ORBITER SEPARATION AT END OF CONSTRUCTION.
(5)	ONE ORBITER DOCKING LAMP (STANDARD). LOCATION—BETWEEN DOCKING WINDOWS ON UPPER SURFACE OF CABIN. FIXED, POINTING UPWARD. PURPOSE (FOR CONSTRUCTION)—ASSIST HANDLING OF CONSTRUCTION STATION NO. 1 FROM STOWAGE TO DOCKING. ASSIST ORBITER SEPARATION AT END OF CONSTRUCTION.	0.200	(12)	ONE TV CAMERA UNIT, SIMILAR TO (11), LOCATED AT FORWARD BULKHEAD OF ORBITER PAYLOAD BAY. PURPOSE—ASSIST SETUP OF CONSTRUCTION STATION NO. 1 FROM STOWAGE TO DOCKING. ASSIST ORBITER SEPARATION AT END OF CONSTRUCTION.
(6)	ONE LAMP AND TV UNIT SIMILAR TO (1). PURPOSE—SIMILAR TO (1), BUT ALSO INCLUDES OBSERVING SETUP AND ACTIVITY AT CONSTRUCTION STATION NO. 2, CARGO STOWAGE FOR RETURN.	0.247	(13)	ONE LAMP & TV UNIT SIMILAR TO (6), LOCATED AT LOWER CROSS BRIDGE OF BEAM BUILDER MACHINE. PURPOSE—ASSIST IN RELOCATION OF CENTRAL PORT.
(7)	ONE LAMP AND TV UNIT SIMILAR TO (1). PURPOSE—SIMILAR TO (1), WITH SPECIAL EMPHASIS ON SETUP AND STOWAGE OF CONSTRUCTION STATION NO. 2; COVERS STARBOARD SIDE BLIND SPOTS.	0.247	(14)	ONE LAMP & TV UNIT SIMILAR TO (6), ILLUMINATING STARBOARD SIDE BLIND SPOTS. PURPOSE—ASSIST IN HANDLING AND PRE-POSITIONING OF BEAMS.

## NOTES

- ITEMS (1), (3), (6), AND (8) MAY ALSO ASSIST OBSERVATION OF TRANSLATION OF STRUCTURAL ASSY AND DEPLOYMENT.
- LAMPS ON ORBITER AND CONSTRUCTION FIXTURE NO. 1 ARE ALSO USEFUL FOR SECOND AND THIRD MISSIONS.
- MMU OR/AND EVA SUIT WILL HAVE WORKLIGHTS AND NAVIGATION LIGHTS. MODIFIED CHERRY PICKER (NOT VISIBLE) MAY BE USED FOR STOWAGE.
- RUNNING LIGHTS AND BEACON FOR RENDEZVOUS NOT SHOWN.

LIGHTS AND TV CAMERAS FOR CONSTRUCTION—FIRST MISSION

CHARACTERISTICS/USAGE	PEAK POWER	ITEM NO.	DESCRIPTION—CHARACTERISTICS/USAGE	PEAK POWER
CAMERA FIXED TO Y- TION—YOKE OF —ASSIST TRANS- —TRANSVERSE BEAMS AND STOWAGE, EVA PUBLIC RECORD).	0.247	(8)	ONE TV CAMERA WITH TILT AND PAN MOUNT. LOCATION— RMS ELBOW (STANDARD ITEM). PURPOSE (FOR CONSTRUCTION)— ASSIST IN HANDLING BEAMS, OTHER MODULES IN SETUP, CONSTRUCTION, STOWAGE.	0.047
ON EACH SIDE OF TV AN MECHANISM. BEAM BUILDER STRAIGHTNESS AND PORTS. ALSO, —TRANSVERSE BEAMS LOCATED WITH BEAM IS DESIRABLE TO F FABRICATED BEAM.	0.247	(9)	ONE LAMP AND TV CAMERA FIXED TOGETHER ON TILT AND PAN MOUNT. LOCATION—RMS WRIST (STANDARD LOCATION, BUT NEW MOUNT). PURPOSE—ASSIST IN GRAPPLING MOD- ULES, TRANSPORTING THEM AND POSITIONING OR BERTHING THEM TO PERFORM SETUP, CONSTRUCTION, AND STOWAGE.	0.220
1). AL HALIDE TYPE RD BULKHEAD OF OWS. PURPOSE— NG OF CONSTRUCTION OWAGE TO DOCKING	0.247	(10)	SIX METAL HALIDE LAMPS OF 0.200 KW EACH (STANDARD ITEMS). LOCATION—SIDE WALLS OF ORBITER PAYLOAD BAY; ONE OF SIX ILLUSTRATED. PURPOSE (FOR CONSTRUCTION)— BACKGROUND FOR EXTRACTING AND STOWING OF CON- STRUCTION EQUIPMENT, SETUP OF CONSTRUCTION STATION NO. 2 AND EVA INSPECTION. (NOTE: SOME SPECIAL DIFFUSERS OR BLINDS MAY BE NEEDED TO PROTECT TV CAMERAS FROM DIRECT VIEW OF LAMPS.	1.200
2). LOCATION— SURFACE OF CABIN. (FOR CONSTRUCTION)— ATION NO. 1 FROM ER SEPARATION AT	0.200	(11)	ONE TV CAMERA UNIT (STANDARD ORBITER ITEM) WITH TILT & PAN MOUNT. LOCATION—AFT BULKHEAD OF ORBITER PAYLOAD BAY. PURPOSE (FOR CONSTRUCTION)— ASSIST IN SETUP OF CONSTRUCTION STATION NO. 2, EXTRACTION AND STOWAGE OF CONSTRUCTION EQUIPMENT, TRANSPORT OF BEAMS.	0.047
3). PURPOSE— OBSERVING SETUP ON NO. 2, CARGO	0.247	(12)	ONE TV CAMERA UNIT, SIMILAR TO (11) BUT LOCATED ON FORWARD BULKHEAD OF ORBITER PAYLOAD BAY. PURPOSE— ASSIST SETUP OF CONSTRUCTION STATION NO. 1, TRANS- PORT OF FORWARD TRANSVERSE BEAMS AND EVA SAFETY WATCH. MAJOR AID IN PREVENTING RMS ARM COLLISION WITH STRUCTURE.	0.247
4). PURPOSE— SIS ON SETUP AND 1. 2; COVERS STAR-	0.247	(13)	ONE LAMP & TV UNIT SIMILAR TO (1) BUT LOCATED ON LOWER CROSS BRIDGE OF BUILDING FIXTURE YOKE. PURPOSE—ASSIST IN RELOCATION OF BEAM BUILDER, REMOVAL OF CENTRAL PORTION OF CONSTR. FIXTURE NO. 1	0.247
	0.247	(14)	ONE LAMP & TV UNIT SIMILAR TO (1). PURPOSE— SIMILAR TO (6), ILLUMINATES AFT TRANSVERSE BEAM HANDLING AND PRE-POSITIONING BY RMS.	0.247

ASSIST OBSERVATION OF TRANSLATION OF STRUCTURAL ASSY AND DEPLOYMENT OF LIBRATION DAMPER.  
TURE NO. 1 ARE ALSO USEFUL FOR SECOND AND THIRD MISSIONS.  
ITS AND NAVIGATION LIGHTS. MODIFIED CHERRY PICKER (NOT VISIBLE) HAS THREE 60-W LAMPS.  
US NOT SHOWN.

FOLDOUT FRAME

#### 5.4.4 Power Demand Analysis

PRECEDING PAGE BLANK NOT FILMED

The construction activity logic, construction support equipment, and detailed timeline development were designed to avoid gross and obvious power demand peaking. For example, only one beam builder machine is supplied, and consideration was given to minimizing use of lights. In addition, the basic concept of the primary construction fixture minimized the work space volume and thus kept lighting and transport demands low. Nevertheless, there was continuing concern that power demands might exceed the nominal payload power capacity of the Shuttle orbiter. This power capacity is basically limited by heat rejection capability of the orbiter radiators to a maximum of 7 kW continuously, or up to 12 kW for 15 minutes every three hours. The baseline orbiter energy capacity was assumed to be 50 kWh without added cryogenic tanks. Additional fuel for energy can be supplied by cryogenic tanks sets, as indicated in Figure 5.4-8. For example, one extra tank set provides 840 kWh for payload energy.




Figure 5.4-8. Payload Energy/Power Availability


It is appropriate to examine closely the basic assumptions and estimation processes used in the power and energy analyses in order to consider their future applicability to other proposed projects. Table 5.4-2 lists several key assumptions and estimating procedures used.

Table 5.4-2. Key Assumptions and Estimating Procedures for  
Power Demand/Energy Analysis—First Mission

1. The beam builder machine is turned on for at least seven minutes (430 sec nominal) prior to usage for a warmup and/or checkout period, and is turned off after each beam is constructed. During the early buildup portion, power demand was conservatively estimated at 2.240 kW. Later inquiry established the demand at 1.53 kW as a conservative estimate. These magnitudes incorporate a margin for additional cap thickness of the beam used in the Rockwell design as compared to the basic beam design analyzed by General Dynamics.
2. Lighting was provided continuously for all functions as if they were to be conducted on the dark side of orbit. Lighting levels are considered frugal, but adequate, to accomplish key assembly activities.
3. All heaters for RMS motors, TV cameras, and other mechanisms were estimated to be operating 50 percent of the time, during which the mechanism was used on a ready-standby status.
4. The RMS heaters, wrist TV camera, camera heater, and light were left on at all times between RMS usage, except during fabrication of the longitudinal beams.
5. The entire analysis is success-oriented. No power allocation is specified for contingency operations. However, a design margin of 50 percent is applied to the calculated energy to account for unintentional omissions.

The power profile and energy analyses were performed in two parts, as illustrated in Figure 5.4-9. The first portion (at the left of the figure) involved the initial setup of the construction fixture, the fabrication of longitudinal beams, the fabrication of the first frame set of two transverse beams and one long crossbeam, and their assembly to the longitudinal beams. All sequences and crew rest periods were assumed as shown in Figure 5.4-2, up to the time for the first translation of the assembly. Another portion of the analysis was based on a representative, modular division of effort which is repeated five times. The power profile for this portion is at the right of Figure 5.4-9. This cycle of work involves fabrication and assembly of two consecutive sets of frames, one with a long crossbeam and one with a short crossbeam, together with the cross-brace cords installations between them and in the previous adjacent bay (Figure 5.4-2). This modular segment of repetitive work is somewhat artificial in that it does not show probable occurrences of crew rest periods or crew exchange periods. If such were included, the timelines could not be exactly repetitive since crew rest periods do not occur at precisely the same point in the sequence on every cycle. However, the inclusion of time for crew rest/exchange periods will generally tend to reduce average power levels and exposure to power peaks. The effects on average power and total energy are partially accounted for in the "representative" cycles by adding time for rest/exchange periods into






BOLDOUT FRAME

ORIGINAL PAGE IS  
OF POOR QUALITY.

3:00 4:00 5:00 6:00 7:00 8:00 9:00 10:00

RAY POWER LIMIT




3:00 4:00 5:00 6:00 7:00 8:00 9:00 10:00

ORIGINAL PAGE IS  
OF POOR QUALITY


INITIAL PERIOD  
(SETUP, FABRICATION OF LONGITUDINAL BEAMS  
AND INITIAL FRAME SET INSTALLATION  
PRIOR TO FIRST TRANSLATION OF PLATFORM)

2 FOLDOUT FRAME



3 FOLDOUT FRAME


ORIGINAL PAGE IS  
OF POOR QUALITY



ORIGINAL PAGE IS  
POOR QUALITY

4 FOLDOUT FRAME

0:00 1:00 2:00



ORIGINAL PAGE IS  
OF POOR QUALITY

5 FOLDOUT FRAME

Figure 5.4-9. Power Profile for First Mission

PRECEDING PAGE BLANK NOT FILMED

the calculation of overall averages. To calculate the total energy requirements for construction, these "representative cycles" were assumed to have been repeated five times, and the total added to the "initial period" analysis. A small reduction was applied to account for nonrepetitive items in the last cycle. Finally, a small segment of power and energy was defined for the activities of stowing return cargo, preparing the construction fixture, and checking it out for untended operation. The combination of these activity segments to develop a nominal (no-margin) estimate and a baseline estimate with design margin is outlined in Table 5.4-3.

Table 5.4-3. Total Energy and Average Power—First Mission

Activity Segment	Duration (hr)	Energy Required (kWh)	Average Power (kW)
•Initial activity—begin IVA, to first translation	12.93	39.11	3.02
•Repetitive activity—long and short crossbeam frames and translations, 5 cycles at 20.19 kWh and 335 minutes each; $5 \times 20.19 = 100.95$ kWh			
Adjustment for last cycle: <u>-1.21 kWh</u>	27.9*	99.74*	3.57*
•Shutdown activity	<u>1.67</u>	<u>5.59</u>	<u>3.35</u>
Nominal total energy	42.5*	144.44	3.40*
Design margin (50% of nominal)	<u>+21.25</u>	<u>+72.22</u>	<u>+3.40</u>
Baseline magnitudes for construction period	63.75 (2.66 days)	216.66	3.40
*Based on repetitive time and energy estimates.			

The design margin for the integrated construction timeline analysis, as shown in Table 5.4-3, was arbitrarily established as 50 percent longer than the nominal time estimate. The associated power and energy margin was simply developed by assuming the nominal average power level would continue for the 50% design margin of time. This concept is consistent with the approach of rescheduling activities to avoid simultaneous use of equipment having a high power demand. Also, any unexpected problems of assembly or delays in crew scheduling would tend to extend the time without increasing peak power demands. The resulting derived baseline power and energy requirements are considered to include unintentional omissions, work interruptions due to unacceptable sun-viewing conditions, and possible delays for crew planning time. Contingencies involving mechanical or electrical repairs, spare parts exchanges, or crew entanglements, etc., are not considered in these analyses.

Foregoing considerations have primarily accounted for overall average power demands and total energy requirements. However, they did not specifically deal with exposures to peak power demand which exceed the nominal orbiter limits of 7 kW. Figure 5.4-9 shows several periods where it is possible that peak power demands might exceed 7 kW, sometimes for over 15 minutes. Since such high demands can have an undesirable effect on fuel cell life, it is expected that they would be eliminated by extending the total construction time (within the above described margin) to avoid simultaneous operations of high-powered equipment.

Typically, the peak power demands occur when beams are being transported and fabricated simultaneously. Addition of other activities at the same time, such as installing and tensioning cross-brace cords, pushes the potential peak power over the 7-kW limit. However, this exposure is only a statistical probability, since average power demands rarely exceed 6 kW. When crew rest periods are scheduled near critical power demand periods, some "natural" work period stretchout and peak leveling will be experienced.

Among the major contributors to the possibility of excessive power peaks are the electric heaters on the RMS and the orbiter lamps. In the analysis, it was assumed that most of the specially designed construction support equipment will not require electric heaters. This approach is justified on the basis of an expected low number of duty cycles and expected advancements in technology. However, should more heaters be required for some of the automatic assembly machinery, greater attention could be given to energy management to meet thermal requirements by selective on/off cycling of heaters and by more judicious design of low-power lighting systems. Based on the current results, extreme measures to reduce lighting power do not appear justified for the construction of the type of platform used as a model for this study.

#### 5.4.5 Construction Support Equipment (CSE) Requirements

At the outset of this discussion, it is important to clarify terminology. By the term *construction support equipment* is meant those particular devices which directly and actively contribute to the processes of on-orbit construction, but are not finally incorporated into the spacecraft which remains at low earth orbit and is sent to geosynchronous orbit. In some cases, items like the modified orbiter remote manipulator system are included, even though these may be later considered as general-purpose, standard "orbiter equipment" in programmatic terms. Items involved exclusively in transportation (e.g., cradles, pallets) are not included. In fact, a hard and precise definition is not easy to formulate. For example, the main yoke of the primary construction fixture is assumed to remain on the constructed spacecraft during its life at low earth orbit, but would not be sent to geosynchronous orbit.

Figures 5.4-10 through 5.4-13 illustrate the identified CSE and describe the key characteristics and usages for the first mission.

A major point to be brought out here is that these space construction equipment items significantly determine the crew productivity, just as does production machinery in a factory. They also significantly affect the time on orbit, the power demands, and the cost of construction. These equipment





Figure 5.4-10. Remote Manipulator System Modifications




I.D.	DESCRIPTION
1	BUILDING FIXTURE SUPPORT YOKE. THE TWO ARMS OF THIS STRUCTURE FORM THE BASIC SUPPORT ELEMENTS OF THE BUILDING FIXTURE. THE ARMS ALSO PROVIDE THE SUPPORT FOR ALL THE MECHANICAL FUNCTIONS REQUIRED TO FABRICATE THE LONGITUDINAL BEAMS FOR THE ENGINEERING TECHNOLOGY VERIFICATION PLATFORM.
2	BUILDING FIXTURE BRIDGE & BERTHING PORT. THIS BRIDGE JOINS & SUPPORTS THE ARMS OF THE BUILDING FIXTURE & ALSO CONTAINS HALF OF A 4-PETAL BERTHING ADAPTER SYSTEM. CONTAINED WITHIN THIS PART ARE ALL THE REQUIRED ELECTRICAL INTERFACE CONNECTIONS TO PROVIDE BOTH POWER & DATA READOUT BETWEEN THE ORBITER AND THE ENGINEERING TECHNOLOGY VERIFICATION PLATFORM (ETVP).
3	BUILDING FIXTURE RIGIDIZING LINKS. THE 2 LINKS SHOWN PROVIDE CONTROL OF THE FIXTURE SUPPORT ARMS DURING DEPLOYMENT BY UTILIZING THE BUILT-IN POWER DRIVE SYSTEM. ALSO, THEY PROVIDE RIGIDIZING OF THE FIXTURE WHEN THE CORRECT ARM POSITION IS ATTAINED.
4 & 5	BRIDGE BEAM EXTENSION & BRIDGE BEAM FOLDING SUPPORT STRUCTURE. THE BRIDGE BEAM EXTENSION IS A STRUCTURAL ENCLOSURE THAT SUPPORTS THE BEAM BUILDER, THE CROSS-CORD STORAGE REEL CLUSTER, AND THE DATA/POWER CABLE STORAGE REEL. WITHIN THE BODY OF THIS STRUCTURE ARE HOUSED ALL THE POWER AND DRIVE ACTUATORS THAT OPERATE THE COMPONENTS ATTACHED TO THIS HOUSING. THIS STRUCTURAL ASSY IS IN TURN SUPPORTED BY 4 HINGED & FOLDING SUPPORT ARMS WHICH ARE ATTACHED TO THE BUILDING FIXTURE BY AN ELECTROMECHANICAL LATCH SYSTEM WHICH CAN BE RELEASED BY REMOTE CONTROL FROM THE CREW CABIN. WHEN THE LATCHES ARE RELEASED THE 4 ARMS AUTOMATICALLY FOLD & ROTATE SO THAT THE WHOLE STRUCTURE CAN BE REMOVED FROM THE BUILDING FIXTURE AND STORED IN THE ORBITER.
6 & 7	EXTENDABLE SUPPORT BOOMS & ROLLER SUPPORT ARMS. THIS EXTENDABLE BOOM PROVIDES SUPPORT FOR THE LONGITUDINAL BEAM SUPPORT ARMS. AN ACTUATION DEVICE LOCATED AT THE BASE OF THE SYSTEM EXTENDS THE BOOM, TRANSPORTING WITH IT THE LONGITUDINAL BEAM SUPPORT ARMS. POWER IS PROVIDED TO THE ROLLER ARMS BY INTERNAL LEADS ORIGINATING AT THE ORBITER/FIXTURE INTERFACE. THE FUNCTION OF THESE ARMS (3 SETS OF 6 ARMS EA, & 1 SET OF 3 ARMS) IS TO PROVIDE BEAM SUPPORT DURING FABRICATION AND ALSO DURING PLATFORM TRANSLATION THROUGH THE BUILDING FIXTURE.
8	BEAM BUILDER. THIS MACHINE IS UTILIZED TO AUTOMATICALLY FABRICATE SPACE STRUCTURAL ELEMENTS FROM COMPOSITE MATERIALS. THE STRUCTURE CONSISTS OF 3 MAJOR SEGMENTS—A FORMING SECTION, A CENTRAL SUPPORT SPIDER, & A FINAL BEAM SUPPORT SECTION. ADDITIONAL SUBSYSTEMS WITHIN THE MACHINE ARE MATERIAL REELS, CORD PLYERS, WE, AND A BEAM CUTOFF SYSTEM.
9 & 10	THE BEAM BUILDER SUPPORT TRIPOD & ATTACH PORT MAGAZINE. AND ATTACH PORT POSITIONER & WELDER. THE BEAM BUILDER SUPPORT TRIPOD IS A SPECIAL TOOL WHICH PROVIDES THE INTERFACE BRIDGE BETWEEN THE BRIDGE BEAM EXTENSION (ITEM 4) & THE BEAM BUILDER. IN CONJUNCTION WITH THIS TRIPOD IS A MAGAZINE CONSISTING OF 6 BEAM END ATTACH PORTS. ALSO ON THE BEAM BUILDER IS A PORT POSITIONER WHICH CORRECTLY POSITIONS THE PORTS ONTO THE LONGITUDINAL BEAM ENDS. THIS OPERATION IS THEN FOLLOWED BY THE APPLICATION OF ELECTRIC CURRENT THROUGH THE PORT POSITIONER HEAD ASSEMBLY TO WELD THE PORTS TO THE BEAMS BY ELECTRIC RESISTANCE HEATING OF A BONDING MATERIAL.



• (ATTACH PORT POSITIONER-WELDER) OPPOSITE VIEW NOT VISIBLE IN THIS VIEW; SEE FIGURE 5.4-12.

Figure 5.4-11. Construction Station No. 1 & Beam Builder Machine

I.D.	DESCRIPTION
11	<p>BEAM POSITIONER. THIS UNIT PROVIDES THE CONTROL THAT IS NECESSARY TO POSITION AND HOLD EITHER THE LONG OR SHORT CROSSBEAMS AND THE TRANSVERSE BEAMS DURING THAT ASSEMBLY PERIOD WHEN THE BEAMS ARE BEING ATTACHED TO THE PLATFORM LONGITUDINAL BEAMS. THIS UNIT HAS BUILT-IN CAPABILITY OF MOVEMENT IN THREE AXES. THE PLANE OF THE BEAM GRIP CLAMPS CAN BE RAISED OR LOWERED. THE GRIP CLAMPS, IN TURN, CAN BE EXTENDED OR RETRACTED OR MOVED LATEROALLY TO ENSURE THAT THE POSITIONER CAN PICK UP THE BEAMS FOR ATTACHMENT. FOLLOWING THE JOINING OF THE CROSSBEAMS OR TRANSVERSE BEAMS TO THE LONGITUDINAL BEAMS, THE POSITIONER IS CONTROLLED TO EXERT A PRE-DETERMINED TENSILE LOAD ON THE JOINT TO VERIFY STRENGTH OF THE ASSEMBLY.</p>
12	<p>DIAGONAL CROSSBRACE CORD STORAGE REELS. THE 6 REELS INVOLVED IN THIS ASSEMBLY SEQUENCE PROVIDE THE SUPPLY SOURCE FOR ALL THE DIAGONAL CROSSBRACE CORDS ON THE PLATFORM STRUCTURE. WHEN DEPLOYED INTO THEIR DISPENSING POSITION, AN ASTRONAUT IN THE CORRECT LOCATION WILL HOOK THE CORD ENDS TO ATTACH POINTS ON THE INTERSECTION FITTINGS AT THE BEAM INTERFACES. AS THE PLATFORM ADVANCES THROUGH THE BUILDING FIXTURE THE CORDS WILL BE PULLED FROM THE REELS. WHEN THE NEXT CROSS FRAME IS REACHED, THE ASTRONAUT WILL ATTACH THE CORD ENDS TO THE INTERSECTION FITTING AT THIS STATION. THIS PROCEDURE CONTINUES UNTIL CROSSBRACE CORDS HAVE BEEN INSTALLED IN ALL PLANES BETWEEN CROSSBEAMS OF THE COMPLETE PLATFORM.</p>
13	<p>DATA/POWER CABLE STORAGE REEL. THIS STORAGE REEL CONTAINS ALL THE CABLES, CONNECTORS, AND VELCRO ATTACH STRIPS REQUIRED TO PROVIDE THE COMPLETE CABLE RUNS AND BREAKOUT LEADS TO THE CROSSBEAMS. ELECTRICAL CABLES EXTEND THE FULL LENGTH OF THE PLATFORM, ORIGINATING AT THE SYSTEM CONTROL MODULE AND TERMINATING AT THE PROPULSION MODULES. CABLE DISPENSING AND ATTACHMENT TO THE STRUCTURE ARE PERFORMED AUTOMATICALLY BY SYSTEMS BUILT INTO THE UNIT AS THE LONGITUDINAL BEAMS PASS THROUGH THE BUILDING FIXTURE.</p>
14	<p>MMU PORT. THE FUNCTION OF THIS EQUIPMENT IS TO PROVIDE A DOCKING PORT FOR THE ASTRONAUT AND HIS MMU. THE ASTRONAUT WILL MOVE TO THIS PORT WITH HIS MMU AND PROCEED TO DOCK TO THE PORT'S LATCHING MECHANISM. AFTER SECURING HIS MMU, HE WILL THEN SEPARATE FROM IT, AND TRANSFER TO THE EVA WORK STATION (ITEM 15) TO PROCEED TO HIS ASSIGNED WORK TASK.</p>
	<p>EVA WORK STATION—THIS WORK STATION CONSISTS OF A MODIFIED OPEN CHERRY PICKER (ITEM 15) WHICH IS ATTACHED TO AND CONTROLS THE MOTION OF A POSITIONING ARM (ITEM 16)</p>
15	<p>MODIFIED CHERRY PICKER. THE GRUMMAN CONCEPT FOR AN OPEN CHERRY PICKER IS MODIFIED BY REMOVING THE STABILIZER ARM, LIGHT STANCHIONS, TOOL RIN, AND PAYLOAD SUPPORTS. LIGHTS ARE RELOCATED ON THE CONTROL/DISPLAY PANEL. THE COMPACT DESIGN ALLOWS ACCESS TO CONFINED SPACES. CONTROL OF THE BEAM POSITIONER IS INCLUDED ON THE CONTROL/DISPLAY PANEL.</p>
16	<p>POSITIONING ARM. THIS POSITIONING ARM IS THE SUPPORT BOOM FOR THE MODIFIED CHERRY PICKER. THE POSITIONING ARM HAS THE CAPABILITY OF ROTATION ABOUT ITS SUPPORT INTERFACE, AND THE ABILITY TO TELESCOPE, SO THAT THE ASTRONAUT ON THE EVA WORK STATION CAN BE POSITIONED IN ALL AREAS REQUIRED FOR HIS ASSEMBLY WORK.</p>



ORIGINAL PAGE IS  
OF POOR QUALITY

Figure 5.4-11. Construction Station No. 1 & Beam Builder Machine (Cont'd)




Figure 5.4-12. Construction Station No. 2




Figure 5.4-13. Additional Construction Support Equipment

items are strongly involved in the new technology requirements for space construction. Some important considerations of major CSE items related to the first mission are highlighted in the following discussion.

*(a) Remote Manipulator System (RMS) Modifications*

Figure 5.4-10 illustrates potential changes to the RMS. The standard orbiter RMS must be modified to perform the construction as defined in this study. An upper-arm roll joint, or its equivalent capability, and associated software are required to provide the upward reach needed to install crossbeams, transverse beams, RCS modules, and payloads. This is primarily required by the location of the height of the apex beam of the ETVP above the RMS shoulder joint, but is also driven by the overall close-in location and limited clearances of the construction fixture work stations. This new mobility capability is considered by Rockwell to be of fundamental importance for space construction and highly useful for transfer of payloads to potential on-orbit stations. The design penalties and procedures to "get around" the lack of this capability seem to be unwarranted and usually complex. For example, there could be a telescoping joint or a scissors mechanism between the construction fixture yoke and the orbiter, near the docking port. Such a joint would have to be extended frequently to clear the elbow motion when the RMS is to reach upward. However, the extra weight and complexity of electrical umbilicals introduced would render this type of solution highly undesirable. Furthermore, the current arm has only 145-degree shoulder rotation, thus limiting the possible range of upper-arm motion angles to no less than 35 degrees above the plane of the payload bay door hinges when the RMS is reaching upward. With the upper-arm rotary joint concept, the upper arm could be oriented in a plane parallel with the payload bay door hinges when reaching upward. As a practical operational consideration, the upper-arm rotary joint greatly simplifies the number of motions and time to accomplish removal of items from the payload bay and their subsequent transport and installation to structure above the payload bay (such as the primary construction fixture). This advantage has been identified in other Rockwell studies, such as those relating to the 25-kW power module or service module, as well as various erectable structures.

Another highly desirable modification to the RMS hardware is tilt and pan capability for the wrist camera and lights. Although this feature is not specifically identified as a requirement for the construction process, there are several operations which it could facilitate. Among these are the setting up of the construction stations, moving the beam builder machine, and transporting beams.

Certain software changes are essential for implementing the upper-arm rotation joint concept. A current concept for the use of this joint is that it would be limited to a single-joint rotation mode. Other joints would be braked when the upper-arm joint is rotated and vice versa. This could simplify the software changes and prevent confusions resulting from multiple solutions to specific resolved motion calculations. Other RMS software improvements are also desirable to aid construction. In particular, collision avoidance warning signals and/or disabling signals would greatly increase operational safety for handling large modules, struts, and beams in the vicinity of the construction stations. Special end effectors for use with the RMS are considered in later discussions.

(b) Construction Station No. 1

The concept for this key construction station (which has also been referred to as the *construction fixture*) sets the major activity patterns and enables on-orbit construction out of the orbiter as described in this study. As indicated in Figure 5.4-11, the station includes a basic building fixture having a yoke shape to accommodate the tri-beam configuration of the ETVP cross-section, and roller supports which grip the longitudinal beams after they are fabricated and cut off from the beam builder machine. Centrally located in the yoke is a removable cross-bridge structure incorporating a rotating head which accepts several types of auxiliary devices, including an EVA work station as well as the beam builder machine, during fabrication of the longitudinal beams. Considering the multiplicity of fabrication and assembly functions performed at this station, it may be thought of as a small satellite space factory. It is designed for cost effectiveness and power conservation, using the concept of a compact, efficient work space through which the structure is moved in either of two directions (and later rotated) to accomplish the construction.

This concept permits a minimum of power for illumination and TV services, maximizes use of a single Shuttle RMS for handling and installation of components, minimizes EVA travel time and fuel/power demand, and provides for extraordinary flexibility in scheduling installations and in LEO servicing of individual payload modules and spacecraft modules (e.g., RCS pods and control modules). It is designed to be stowed in the orbiter bay in a relatively compact manner, permitting initial removal and setup on a docking port as if it were a standard orbiter payload package. The major portion of the station is designed for semi-automatic, remotely controlled deployment which takes place within a relatively short time. Selective reconfigurations are required during the first mission. The major item of removable equipment is the central cross-structure/rotary joint complex to which are attached a beam positioner, wire-laying reel, and astronaut maneuvering arm/cherry picker during the ascent phase. During the initial setup, the beam builder on its tripod support (and carrying the attachment port installation device) is also attached. This central complex of machinery must be removed after attaching the transverse beams and crossbeams in order to permit freedom of translation of the yoke along the longitudinal axis of the platform for later installation work. Such removal activity is accomplished during the stowage of items prior to separation and return of the orbiter to the ground. Additional capabilities needed for the station to accomplish construction are discussed later in conjunction with the second and third missions.

During unattended operations (between construction periods), this station also provides libration damping and TT&C. It has solar arrays and batteries for power during this period. Thus, it functions as a part of an active satellite, controllable from the ground.

ORIGINAL PAGE IS  
OF POOR QUALITY

*(c) Beam Builder Machine Modifications*

An essential element of space fabrication technology is the automatic beam builder machine, which is defined for this study as a derivation of the General Dynamics SCAFE design (References 5-3 and 5-4). The construction concept developed herein requires serial use of the beam builder in the two construction stations, and requires selective modifications of the baseline software to provide for double cross-members (side by side) at selected points along the longitudinal beam which carries the electrical wiring. These special situations occur adjacent to the long crossbeams in order to provide stiffness and strength for supporting breakouts and connectors for the electrical wiring which is routed to the crossbeams. Software revisions are also required to provide for special end configurations on transverse beams and crossbeams. The transverse beams configurations require that one cross-member be deleted (together with adjacent cross-brace cords) at each end. Also, a shorter spacing between cross-members is needed at the end bays, in order to avoid interference with adjacent beams at the ends. This change permits the crossbeams and transverse beams to be located in the same plane at each frame station of the platform, and simplifies construction procedures over an offset plane configuration. These software modifications have been reviewed by General Dynamics and verbal agreement received regarding their feasibility.

Other basic modifications include use of thicker cap materials and larger diameter cross-brace cords. These thicker materials will require somewhat more power for heating and welding (the power estimates used in this study have been set higher to account for these differences). Another requirement for materials stored in the beam builder machine is the provision of Velcro strips on selected cross-members to support electrical wiring. Preliminary investigation has indicated space availability exists for these provisions.

In order to provide structural mounting points and pickup points for transport, some modifications to the beam builder machine framework will also be required. In a similar category are installation points for a device which installs attachment ports on the ends of the fabricated longitudinal beams and crossbeams, and targets for guiding the RMS to a favorable grapple position.

Finally, provisions are required for electrical wiring, connectors, and mechanical attachments for remote control of the beam builder, for the attachment port installation devices, for lights, and for a TV camera and its associated tilt and pan mechanisms and heaters. The TV camera, heaters, and mechanism systems are currently assumed to be identical or highly similar to those specified for the RMS elbow. It is assumed that the camera and lights can aid in observation of beam fabrication, attachment port installation, and beam handling (grappling and initial transport phases) at Construction Station No. 2 (which is discussed later).

In the construction analysis and fixture design concepts adapted for this study, the beam builder machine would be part of an assembly which includes the attachment port installation device, lights, and TV camera. Initially, it would also have attached to it a support tripod which mates with the rotating head on the central portion of the primary construction fixture. This mating interface would have both mechanical attachments and electrical power and signal connections. It would be designed to facilitate interface alignment when using the

RMS as a transporting device. Design features would include latches which are normally remotely controlled from the orbiter and manually operated in contingency modes (by EVA). Also needed are alignment guides and targets. Ideally, the joining interface would be visible using both the RMS and a separate TV camera mounted on the construction fixture.

*(d) EVA Work Station (Modified Cherry Picker and Astronaut Maneuvering Arm)*

Two major items constitute the unit called the EVA Work Station for the first mission, as shown in Figure 5.4-11. They are discussed here as separate entities because it is planned to use the modified cherry picker during the second mission in conjunction with the RMS.

The modifications are applicable to the Grumman concept of an open cherry picker platform (Reference 5-5). The first-mission requirements include removal of a stabilizer arm, a tool bin, and two light stanchions. Also, relocation of miscellaneous features is planned to minimize workspace volume requirements. It is currently assumed that there will be three 60-watt lamps on this unit and a minimal tool storage capability. The cherry picker control/display panel is used to control the astronaut maneuvering arm and to control the beam positioner.

The astronaut maneuvering arm concept is an entirely new piece of machinery, although it performs many of the same functions as the RMS. It would be much smaller in extended length and would incorporate a telescoping arm link to facilitate maneuvering within the confined space of the tri-beam platform. The mass handling capability is also severely scaled down from that of the RMS, since only the EVA crewman and modified open cherry picker are to be transported. Consequently, the power demands for driving this device are assumed to be much less than for the RMS. Also, it is presumed to require minimal (or none) heating of its drive mechanisms by virtue of its relatively short useful life and lowered requirements for accuracy in positioning.

At the end of the first mission, the cherry picker is to be returned to earth for rework. These changes, required to support the second mission, will include a stabilizer arm and tool holder as well as added light stanchions. Thus, the configuration will more nearly resemble Grumman's baseline concept for the development test article/open cherry picker (Reference 5). Earlier in the systems analysis it was planned to leave the modified open cherry picker in space, secured to the construction fixture. However, subsequent analysis of the second-mission requirements indicated the need for the added features noted above. These changes were of such significance that shop assembly was considered more desirable than field rework.

*(e) Construction Station No. 2*

ORIGINAL PAGE IS  
OF POOR QUALITY

This station consists of a number of important separate equipment items of special-purpose nature which assist in automatic fabrication of assemblies of crossbeams and transverse beams. As shown in Figure 5.4-12, the station includes a beam builder support and control, the dispensers for attachment ports, the devices for installing intersection fittings and remote servicing (teleoperator) docking ports, reels, and installation devices for electrical



lines, and supporting/translating rollers for beam translation when beyond the beam builder machine. Use of such devices facilitates rapid construction and high productivity of the crew. The location assists in achieving simultaneous production of beams and installation of beams, hookup of cross-brace cords, and electrical connections on the platform.

Design of this secondary station includes use of a structure (Y-frame) which acts both as a support cradle during launch and return and a construction fixture for on-orbit operations. There is also a separate, more specialized reel assembly fixture to which is also attached the dispenser for intersection fittings and teleoperator docking ports. These components are all returned to earth at the end of the first mission.

*(f) EVA Suit and Life Support Systems*

Baseline crew schedules for the first mission are tied to the use of a new high pressure suit (5 to 8 psi) and an eight-hour EVA life support system. Until such a suit system is designated as an inherent and integral part of the Shuttle development program, it may be considered as special-purpose construction support equipment. In fact, an extended work time capability (8 hours in lieu of 6 hours) could be separately provided by an auxiliary supply of breathing gas, fluids, and electrical power through umbilicals which could be incorporated into the cherry picker/maneuvering arm system, with minimal impact on portable life support system (backpack) development. However, a trade study to select between these approaches or other feasible means to extend work time is considered outside the scope of this study.

*(g) Miscellaneous Tools and Devices*

Included in this group of CSE are the special end effector for handling crossbeams and transverse beams with the RMS, and the hand tool for tensioning cross-brace cords. Also included is the tether used to assist handling of cross-brace cords hookup and crossover (Activity 11.2).

A set of EVA hand tools will also be required for contingency usage in the construction operations. Although unspecified at the preliminary analysis of this study, experience gives certainty that they will be needed. Illumination devices and TV cameras are also significant aids to productivity in manned construction activities. Although they have no direct physical impact on actual assembly of parts, they must be carefully located and selected due to their potential impact on power demands. Lighting and TV requirements for the first mission are discussed in greater detail in Section 5.4.3.

The electro-optical system for performing structural alignment checks of the platform is another item of rather indirect relationship to the construction operations. It is located on the central portion of the construction fixture as described in Appendix B (Construction Activity Data Sheet 16.0). Its function is in the nature of inspection and reporting rather than fabrication or assembly. Yet, like diameter gauges and micrometers for machining operations, it is a piece of construction support equipment.

(h) *Manned Maneuvering Unit (MMU)*

As currently planned, all the construction of the ETVP could be performed without the aid of an MMU. However, the MMU is included here as a construction support device which facilitates EVA crew transport for inspection and miscellaneous manual functions at the beginning and the end of the EVA work period in the first mission. As a facilitator, it saves crew transport time by deleting hand-over-hand translation by the crew along rails and handholds. The most valuable contribution of the MMU could lie in its usage for dealing with unforeseen contingencies. Examples might be manual deployment or retraction of elements with motor or solenoid failures, release of latches which hang up, assisting with alignment of parts for assembly or stowage, making repairs to loosened fasteners, or replacement of failed parts. Initial usage could be merely visual assessment of a problem to gain information for decisions on how to deal with it.

Another subsidiary, but important, usage could be photographic coverage of key construction operations. If necessary, EVA transport of structural elements could be performed in the unlikely case of failure of an RMS drive motor or other transport device.

As a means to facilitate rapid response by the EVA crew, the design of the construction fixture incorporates a fixture for holding an MMU in close proximity to the EVA work station. This holding fixture is similar to the flight support station for the MMU in the orbiter payload bay, but it has no recharge facilities.

(i) *Summary of Usage*

ORIGINAL PAGE IS  
OF POOR QUALITY

Table 5.4-4 summarizes the usage of construction support equipment in the first mission as a function of the activities performed. The chart shows that many pieces of equipment are used in different activities, demonstrating a high level of versatility. Other items have highly specialized functions, which raise questions of cost effectiveness, such as might be explored in detail trade studies in a Phase B type study.

It will be shown in analyses of later missions that the construction fixture, RMS and cherry picker are highly useful and effective equipment for additional functions.

5.4.6 Flight and Site Support Equipment Required

In addition to support equipment which is dedicated specifically to construction on the first mission, there is a need for pallets and various other flight support equipment items on components which are required to fly construction equipment and supplies to orbit and to unload/reload cargo. Also, kits containing fuel gases and various supplies for crew support may be included. The scope of this study does not include detail development of configurations or specifications for all such equipment. However, weight and volume concerns associated with end-to-end mission analysis require at least preliminary consideration of this type of equipment, particularly as regards

Table 5.4-4. Construction Support Equipment Usage - First Mission

CONSTRUCTION ACTIVITY	CONSTR. SYSTEMS		ORBITER		Beam Builder/Attach Port Installer
	Constr. Systems	Orbiter	Constr. Systems	Orbiter	
1.0 Erect and deploy construction fixture	X				
2.0 Install beam builder on construction fixture	X				
Check out beam builder					
3.1 Fabricate longitudinal beam					
3.2 Install attach ports on longitudinal beam					
7.0 Set up Construction Station No. 2					
4.0 Reposition beam builder 120 degrees					
5.1 Withdraw longitudinal beam No. 1					
5.2 Install electric lines on longitudinal beam No. 1					
6.0 Return longitudinal beam No. 1 to fabrication position					
8.1 Relocate beam builder to Construction Station No. 2					
Check out beam builder at Construction Station No. 2					
RMS end effector change					
EVA astronaut egress and inspection tour					
9.1 Fabricate transverse beam					
9.2 Join intersection fittings to transverse beam					
10.0 Transport transverse beam					
8.2 Reconfigure construction fixture & occupy EVA station					
11.1 Join transverse beam to longitudinal beams					
11.2A Initial connection of X-brace cords					
11.2B Join X-brace cords to leading and trailing ears					
11.3 Tension X-brace cords					
12.1 Transport transverse beam					
12.2 Fabricate crossbeam (long/short)					
12.3 Install attach ports on crossbeam					
12.4 Install electric lines on crossbeam					
12.5 Install teleoperator docking ports					
13.0 Transport crossbeam					
14.0 Connect electric lines from crossbeam to longitudinal beam					
15.0 Translate structure one bay length					
16.0 Check structural alignment					
17.1 Configure construction fixture for untended operations					
17.2 Slow return cargo in payload bay					

weight and volume. The cargo manifest for the first mission lists many specific items in this category under the title, *Airborne Support Equipment*. Table 5.4-5 provides a summary list of different types used for the first mission. Further discussion follows concerning unique concerns to construction missions—concerns which are generally applicable to the second and third missions.

Construction missions of the type studied in this analysis will typically require pallets which carry items which are returned to earth in a different configuration than they were launched. For example, in the first mission a portion of Construction Station No. 1 is attached to the yoke structure during ascent, but is later removed and stowed separately, for return to earth, in a different manner than it was stowed for ascent.

Table 5.4-5. Flight Support Equipment Categories  
for First Construction Mission

Support Cradles and Pallets
Trunnion Fittings - Fixed
Trunnion Fittings - Controlled Latch Type
Keel Fittings
Bridge Fittings - Longeron
Cryogenic Fuel Tanks and Supports
Nitrogen Tanks and Supply Systems
Wire Harness - Payload Latching Controls
Berthing Platform
MMU Flight Support Station
Displays and Controls
Seats and Restraints
Garments
Accessories - Crew
Personal Equipment - Crew
Rescue Equipment - Crew

ORIGINAL PAGE IS  
OF POOR QUALITY

The design of support systems which are compatible with orbiter center-of-mass limits in both ascent and descent modes is a key concern. In some cases, a pallet may have to be moved to a new position in the orbiter payload bay prior to meeting such limits for return to earth. If so, it may require a grapple fixture and target for handling by the RMS. Also, it may be desirable for a pallet to function as a construction fixture while on orbit. For the first mission, the Y-frame in Construction Station No. 2 is a specific example.

Another key concern in packaging for construction operations is the access and sequence of usage of equipment and materials. Obviously, it is desirable for those items first used to be at the top of the bay, readily reachable for usage. Alternatively, a separate, temporary stowage framework or support device may be needed. During the construction process, access considerations include not merely grappling and removal, but plans for installation or attachment to another site. Therefore, the means of attachment, including visual guidance and reach, must be carefully considered in selecting the orientation of the equipment within the payload bay.

Space-site support equipment is a relatively new category of equipment peculiar to this type of construction activity. The concept includes those items which are neither used for physical support during ascent/descent nor directly used for construction. Site support items, identified during this analysis as related to the first and second missions, are the libration damping system components, the batteries, and the TT&C equipment incorporated into Construction Station No. 1. These items provide services during unattended operations at the orbital construction site, thus maintaining the viability of the site for future rendezvous, docking, and continuation of construction.

## 5.5 CARGO MANIFEST

Table 5.5-1 briefly summarizes the cargo types and weights for the first construction mission. The detail, itemized list is presented in Appendix C. The listing has been broken down into three basic categories: platform items, construction items, and airborne support equipment (ASE).

Table 5.5-1. Cargo Manifest Weight Summary

<u>Launch Mode</u>		<u>Weight (lb)</u>	<u>Mass (kg)</u>
Platform items (satellite)		11,498	5,215
Construction items			
Construction fixture	5,814 lb		
Beam builder	5,738 lb		
Interconnect fitting			
canister	200 lb		
Support for attach			
ports	<u>300 lb</u>		
Total		12,052	5,467
Airborne support equipment		<u>11,957</u>	<u>5,424</u>
Total cargo (up)		35,507	16,106
<u>Return Mode</u>			
Construction fixture items		1,795	
Beam builder		5,738	
Interconnect fitting canister		200	
Support for attach ports		300	
Airborne support equipment		11,957	
Less expendables		<u>- 1,033</u>	
Total cargo (return)		18,917	8,581

ORIGINAL PAGE IS  
OF POOR QUALITY

The following assumptions were made in the development of the cargo mass statement:

1. Mission time reduced sufficiently from orbiter basic 28 man-days, that six men for 4.67 days results in the base 28 man-days for life support consumables; thus, no consumables were added for crew life support.
2. Ten additional airlock repressurizations; a total of 12 is required (two are orbiter baseline). Each nitrogen tank kit has a capacity of 4.5 EVA's. Thus, three additional N<sub>2</sub> tank kits are required (Kits 5, 6 and 7). The oxygen required for repressurizing the airlock is 2.7 lb. Thus, 27 lb for 10 additional repressurizations. The additional Cryokit (see next item) provides an excess of 56 lb of oxygen that can be used for this loss.

3. Cryokit 3 has been added over the orbiter two-kit baseline. In addition to supplying electrical power, it has the benefit of supplying oxygen for airlock repressurization (see Item 2).
4. Fixed life support items are added for two additional crewmen.
5. All cryo  $O_2$  and  $H_2$  are consumed for return. Forty pounds per tank of  $N_2$  gas are consumed for return.

Typical of previously analyzed space construction material shipments, the payload limits are set primarily by the volume of the orbiter payload bay, not by the orbiter's payload weight capacity. Figure 5.5-1 defines the concept of payload bay packaging for launch of the construction equipment and materials for the first mission. Included are pallets and provisions to return certain items to earth. For example, there is a special cradle included primarily for return of the central portion of Construction Station No. 1.

Figure 5.5-2 shows the cargo horizontal c.g. plotted on the orbiter c.g. envelope constraints for both the up or abort condition and for the return case. As will be noted, both cases are satisfactory from a c.g. standpoint. Also, the lateral and vertical centers of gravity are well within the orbiter c.g. envelope. The mass of the total cargo is 16,103 kg (35,507 lb). The normal return mass is 8579 kg (18,917 lb).

## 5.6 REFERENCES

1. Rivers, J. V. and Hollaway, T. W.,  
Shuttle Flight Planning and Crew Activities  
Guide. Shuttle Working Paper JSC-07996,  
NASA, JSC, 16 May 1973
2. Freeman, D. L. and Scales, L. V. S.  
STS Work Day Handbook, Orbital Flight Test,  
JSC 10541, LA-B-1180-4H, NASA, JSC, June 1978
3. Convair Division of General Dynamics  
Space Construction Automated Fabrication Experiment Definition  
Study (SCAFEDS), Part III Mid-Term Briefing, CASD-AS78-013,  
13 December 1978 (describes beam-builder machine).
4. Telephone conversation with L. Browning, Convair Division of  
General Dynamics.
5. Grumman Aerospace Corporation  
Manned Remote Work Station Development Article, Volume I,  
Book 1, Flight Article Requirements, Report NSS-MR-RP008,  
1 March 1979.
6. Ellis, J. L., Shuttle EVA Description and Design Criteria  
JSC 10615, Crew Training and Procedures Division, Flight  
Operations Directorate, NASA, L. B. Johnson Space Center, May 1976

ORIGINAL PAGE IS  
OF POOR QUALITY




Figure 5.5-1. First Mission Manifest






Figure 5.5-2. Cargo Center-of-Gravity Locations

## 6.0 SECOND CONSTRUCTION MISSION

This section describes the detailed integration of the activities for the second construction mission.

The second construction mission is characterized by installation of deployable and erectable type structures (as opposed to space fabricated). It includes installation of the system control module with deployable solar array and subsequent checkout. Rendezvous and berthing are also required.

### 6.1 CONSTRUCTION PLAN

The objective of the second mission plan was to install the forward support structure and aft support structure (thrust structure), the forward assembly (control module and solar array), and a TT&C antenna. Also included were assembly of the cross beam bracing struts, checkout of the electrical power and signal distribution system and measurement of the final alignment of the attachment ports on the long cross beams and the thrust structure. As for Mission 1, an attempt was made to include as many as possible of the modules and structural pieces required to complete the platform. The possible installation of RCS pods on this mission was investigated. However, the results showed the concept to be not feasible, due to weight and volume considerations.

The configuration resulting from construction performed during Mission 2 is shown in Figure 6.1-1.

#### 6.1.1 Construction Requirements

Construction requirements specific to the second mission are listed in Table 6.1-1. Initially, the orbiter must rendezvous and berth to the stabilized platform at the berthing port of the construction fixture. In order to perform the various installation activities with a single RMS arm without re-berthing, the docking interface is designed to rotate about an axis parallel to the orbiter Z axis. Installation of the two deployable truss structures was deemed reason to require an open cherry picker platform, and its use is continued for installation of bracing struts because of the wide-angle visibility advantages of the on-site EVA astronaut.

#### 6.1.2 Construction Logic

Figure 6.1-2 depicts the logic diagram devised for the activities performed during the second mission.

The second mission has very few parallel construction activities, since each function typically engages full attention of the crew and the available construction equipment.

**PRECEDING PAGE BLANK NOT FILMED**




Figure 6.1-1. Configuration of the Engineering and Technology  
Verification Platform at the end of the Second Mission

ORIGINAL PAGE IS  
OF POOR QUALITY

Table 6.1-1. Construction Requirements - Second Mission

- Provide means to safely rendezvous and berth the orbiter to the construction fixture in a position facing the opposite direction from that when the orbiter was separated at the end of the first mission.
- Provide means to deploy and install two folded support structures, one at each end of the platform.
- Provide means to install the forward assembly modules, make its electrical connections to the platform and partially deploy the solar array.
- Provide means to join bracing struts between ends of long and short cross beams.
- Provide means to check electrical distribution network continuity.
- Provide means to measure alignment of attachment ports for platform payloads and orbit transfer propulsion modules.
- Provide means for translation of the platform and for rotation of the platform structure relative to the orbiter to assure adequate reach of an RMS arm to the forward assembly and the aft support (thrust structure).
- Provide means to install the TT&C antenna and associated electrical wiring harness.




Figure 6.1-2. Logic Diagram for Construction Activities during Second Mission

ORIGINAL PAGE IS  
OF POOR QUALITY

## 6.2 CONSTRUCTION PROCESS - SECOND MISSION

The construction process during the second mission is preceded by an extensive series of burns and coast periods to achieve rendezvous with the orbiting platform. Upon achieving rendezvous, the RMS is checked out and deployed to prepare for berthing to the construction fixture. Also, a cannister which contains bracing struts is rotated out of the orbiter payload bay to the starboard side. In the process, this activity uncovers the berthing port and provides access to other stowed items. This requirement results from the selected packaging concept, and might be revised following further design trades. For example, the bracing struts could be stowed in a folded condition in order to require less payload bay length, but this would necessitate added on-orbit time to extend the struts.

Using the RMS, the orbiter berths to the construction fixture at the forward end of the ETVP with the port side of the orbiter facing the forward end. This orientation is  $180^{\circ}$  from that used for the first mission. The reason for this orbiter orientation is to locate a single, standard, port-side RMS in the most favorable position for reach during the first construction task.

Following berthing of the orbiter to the construction fixture, work is begun to prepare the construction systems for operations. The libration damper RCS arms on the construction fixture are withdrawn to minimize potential obstructions for RMS transport activity or damage to the libration damper arms. The construction fixture is translated closer to the end where the forward assembly is to be installed.

The RMS then engages a stowed open cherry picker (MRWS concept) and unstows it. An EVA astronaut deploys the cherry picker and boards it.

This EVA method was selected following a review of the requirements for transport, alignment, attachment and deployment of the forward structure. The key concerns involved the dexterity needed to make electrical wiring connections across the support structure between the platform and the forward assembly (control module/solar array). Another benefit is the visibility and on-site manipulation possibilities for deploying and joining the forward structure.

The first major construction activity during the second mission is the installation of the forward assembly support structure, as depicted in Figure 6.2-1. This structure consists of a number of struts joined together by hinges so they will fold into a compact unit for ease of stowing in the orbiter bay. The folded structure is removed from the orbiter bay by the EVA astronaut using the cherry picker mounted on the end of the RMS. The support structure is transported to the forward end of the ETVP, unfolded and installed.

The next item to be installed is the forward assembly, which consists of the control module and the stowed solar array. This activity is shown in Figure 6.2-2. The forward assembly is removed from the orbiter bay, again by the EVA astronaut using the cherry picker/RMS, then installed on the support structure. A deployable tray on the control module is used to bridge between

• INSTALL FORWARD STRUT ASSEMBLY




Figure 6.2-1. Installation of Forward Strut Assembly

• INSTALL SYSTEMS CONTROL MODULE




Figure 6.2-2. Installation of Systems Control Module



the control module and the ETVP and to carry all of the electrical cabling between them. This cable tray is next deployed. The joining of the pig-tailed connectors on the cable tray to the connectors on the ETVP longitudinal is performed manually by the EVA astronaut, while supported on the cherry picker.

As previously mentioned, the cannister which contains the brace struts was rotated out of the orbiter bay prior to berthing. The tray remains in this position during the entire second mission. The struts are removed one at a time from the cannister by the EVA astronaut, using the cherry picker/RMS, and installed between ends of adjacent long and short cross beams as shown in Figure 6.2-3. The port side installations on the ETVP are accomplished using a special hand-held power tool. The EVA astronaut adjusts the length of each strut as required. The orbiter translates the ETVP through the Construction Fixture #1 between each pair of installations to locate the RMS favorably for each strut set installation. At the aft end of the ETVP the orbiter rotates 180° about its Z axis, using the rotary joint in the docking port between the construction fixture and the orbiter. The purpose of this rotation is to bring the RMS into a favorable location for the next installation procedure. A rotary joint was selected because of its positive control capability and potential versatility for aiding RMS reach for payload installation.

The next task is deployment and joining of the thrust structure at the aft end of ETVP. This structure supports the three inter-orbital thrust engines and distributes their thrust into the platform structure. It consists of three separate struts and a folded assembly which contains fifteen struts hinged together. An electrical harness which is attached to the strut assembly links the three inter-orbital thrust engine attach ports to a connector located at the attach point for the apex longitudinal of the ETVP. This configuration was chosen as a compromise between ease of stowing and ease of erection and installation. The thrust structure is installed by the EVA astronaut on the cherry picker in much the same fashion that the forward support structure was installed.

The main difference between the forward and aft support structure is the need for three separate struts on the aft assembly which are installed independently before the folded strut assembly.

The main electric cable run along one of the base longitudinals of the ETVP ends in a connector at the aft end of the platform. This connection carries power and signal for the three inter-orbital thrust engines and for the TT&C antenna which is the next item to be installed.

The TT&C antenna is located at the aft end of the apex longitudinal. Therefore, it is necessary to extend the main electric cable run from the longitudinal where it currently ends, to the apex longitudinal. This special wiring and the TT&C antenna are installed by the EVA astronaut on the cherry picker/RMS as shown in Figure 6.2-4. Following this installation the EVA astronaut manually mates the connectors between the platform, the special wiring, the TT&C antenna and the thrust structure.

ORIGINAL PAGE IS  
OF POOR QUALITY




Figure 6.2-3. Installation of Cross Beam Bracing Struts




Figure 6.2-4. Installation of the TT&C Antenna Adjacent to Thrust Structure

The brace struts along the starboard side of the ETVP are installed in similar fashion to those on the port side, the orbiter translating the platform after each set of two struts is installed. After the last brace strut is installed, the orbiter again rotates  $180^\circ$  and is now back in the location and orientation as it was at the beginning of the second mission.

A check of the electric distribution system is performed via a cable which is dragged from the orbiter payload bay by the EVA astronaut on the cherry picker/RMS and connected into a receptacle on the control module. Concurrently with the distribution system checkout, the solar array is unfolded (but not extended) so that it can both rotate and nod. The drag cable is restowed in the orbiter on a spring return reel by the EVA astronaut on the cherry picker/RMS, as shown in Figure 6.2-5.

The EVA astronaut folds the stabilizer arm of the cherry picker and maneuvers to a foothold station close to the orbiter airlock, where he dismounts from the cherry picker and manually folds it to its stowed configuration. The astronaut enters the airlock and the cherry picker (still attached to the RMS) is moved by the RMS to its stowed location in the orbiter bay where it is stowed and disconnected from the RMS.

It is required that measurements be made of the orientation of the control module attitude reference system relative to the orientation of the attach ports for the payloads and the inter-orbital thrust engines. To accomplish this, two calibrated IMU's are used. Removed from a special baseline mounting fixture in the orbiter bay by the RMS, the first IMU is installed on the control module where it remains while the second IMU is installed in turn at each of the attach ports to be measured, such as indicated in Figure 6.2-6. During this procedure the orbiter translates along the port side of the ETVP, rotates  $180^\circ$  at the aft end and returns along the starboard side.

The IMU's are battery powered and each contains a system for continuously recording time and orientation. When all of the attach ports have been measured the two IMU's are returned by the RMS to the baseline mounting fixture. Subsequent to the landing of the orbiter, the IMU records are examined to calculate the required measurements.

Following the completion of the construction tasks of Mission 2, the orbiter and the ETVP prepare for separation. On the construction fixture, the libration damper arms are extended and the ETVP attitude control system is activated. The orbiter separates from the construction fixture/ETVP at the berthing port, using the RMS. The berthing port on the orbiter is retracted and the cannister for bracing struts is then stowed. The orbiter enters a barbecue phase and waiting period for opportunity to descend and land at Kennedy Space Center.

Figure 6.2-7 graphically summarizes the assembly sequence for the second mission, with particular emphasis on the relative rotations of the platform with respect to the orbiter. Since two large masses with significant moments of inertia are involved, it is not obvious which is most easily thought of as the reference "stable" mass. In Figure 6.2-7, the platform is used as the reference mass.




Figure 6.2-5. Perform Electrical Continuity Checks

ORIGINAL PAGE IS  
OF POOR QUALITY







Figure 6.2-6. Measure Structural Misalignments




- INSTALL SCM SUPPORT STRUCTURE
- INSTALL SCM
- INSTALL BRACING STRUTS
- ROTATE ORBITER



- INSTALL THRUST STRUCTURE
- INSTALL BRACING STRUTS
- ROTATE ORBITER
- CHECK-OUT ELECTRICAL LINE CONTINUITY



- INSTALL ALIGNMENT PACKAGE ON SCM
- SEQUENTIALLY INSTALL ALIGNMENT PACKAGE ON ATTACH PORTS
- ROTATE ORBITER



- SEQUENTIALLY INSTALL ALIGNMENT PACKAGE ON THRUST STRUCTURE O.T. PROPULSION MODULE PORTS
- SEQUENTIALLY INSTALL ALIGNMENT PACKAGE ON REMAINING ATTACH PORTS
- ROTATE ORBITER
- REMOVE & STOW ALIGNMENT PACKAGES

Figure 6.2-7. Second Mission Assembly Sequence

### 6.3 CONSTRUCTION ACTIVITY ANALYSES

ORIGINAL PAGE IS  
OF POOR QUALITY

General comments in Section 5.3 describing the Construction Activity Analysis sheets and the process of analysis are also applicable to the analysis of the second mission. Some differences appear in the number and scope of the activities described. There are fewer documents, since there are fewer different types of parts handled, and there are few parallel operations.

The assemblage of Construction Activity Data Sheets for the second mission comprise information about a higher percentage of the total mission time than was the case for the first mission. Many of the first mission sheets described only selected samples, usually the first, of a series which was repeated many times. In the second mission there is only one such repetitious activity handled in that manner (No. 26.0 - Rotate Platform 180°). However, note that there is one such rotation which is described as part of activity 38.1.

Copies of Construction Activity Data sheets for the second mission appear in Appendix B, and are numbered serially from 21.0 through 38.2.

### 6.4 INTEGRATION ANALYSIS

The integration analysis for Mission 2 was performed on a complete, end-to-end basis for both the activity timeline and the power profile. Otherwise, the objectives and end products of the integration analyses were essentially the same as for the first mission. Information derived during analysis of the first mission permitted better planning and format arrangement of analytical forms, which facilitated the analysis. Also, the general absence of overlapping activities made analysis much more straight forward and simpler. Results of the analyses are discussed in the following sections.

#### 6.4.1 Timelines

The integrated activity timeline analysis for Mission 2 is presented in Figure 6.4-1. Although fewer different activities are involved, the construction time is noticeably longer for Mission 2 (59.45 hrs. without design margin) as compared to 42.52 for the first mission. Note that the elapsed time for construction includes two delay periods which follow a rotation of the platform with respect to the orbiter. One of these is quite long, approximately 4.4 hours. In calculating the 50% design margin for construction activity these delays were not considered. That is, the 50% design margin of 27.3 hours is based on actual construction time of 54.6 hours, not on the elapsed time from setup to shutdown.

The delay mentioned above raises a general question peculiar to space construction schedule planning: Should EVA astronauts be left outside during extensive delays for translation, rotation or checkout, etc., in which they have no duty requirements? If they remain outside, considerable boredom and questionable exposure to hazards is incurred. If brought inside, they incur a possible requirement for extensive suit checkout prior to egress, plus the



MISSION TIME G.E.T.

0

2

1 . . . . .

ACTIVITY

- 21.0 PREPARE CONSTRUCTION SYSTEM
- 22.0 INSTALL FWD. SUPPORT STRUCTURE
- 23.0 INSTALL FWD. ASSEMBLY
- 24.0 CONNECT FWD. ASSY. ELECTRICAL
- 25.0 INSTALL STRUTS - PORT
- 26.0 ROTATE +180°
- 27.0 INSTALL THRUST STRUCTURE
- 28.0 INSTALL SPECIAL WIRING
- 29.0 CONNECT ANTENNA & WIRING
- 30.0 INSTALL STRUTS - STARBOARD
- 31.0 ROTATE - 180°
- 32.0 DISTRIBUTION SYSTEM CHECK
- 33.0 REMOVE CHERRY PICKER
- 34.0 PREPARE ALIGNMENT INSTRUMENT
- 35.0 INSTALL ALIGNMENT IMU
- 36.0 PERFORM ALIGNMENT - PORT
- 37.0 PERFORM ALIGNMENT - STARBOARD
- 38.1 RETURN IMU TO ORBITER
- 38.2 PREPARE FOR SEPARATION

DELAY

EVA ASTRONAUT No. 1 - EGRESS, REST, LUNCH & INGRES

EVA ASTRONAUT No. 2 - EGRESS, REST, LUNCH & INGRES

EVA ASTRONAUT No. 3 - EGRESS, REST, LUNCH & INGRES

4 . . . 6 . . . 18 . . . 20 . . . 22 . . . 24 . . . 26 . . . 28 . . .

55

60

59

25

21

50

31

39

50

44

32

45

47

ESS

□ □ □ □ □ □ □ □

ESS

□ □

ESS

2

FOLDOUT FRAME

26

20

30

32

34

36



50

44

32

45

47

50

5

50

**30**

50

45

44

46

27

60

**3 FOLDOUT FRAME**

५

36

**20**

10

42

44

16

48

45

44

46

27

60

45

45

15

55

51

44

266

4 GOLDGUY FRAME

48

50

52

54

56

58

60

62

51

44

32

17

31

35

50

44

50

45

47

50

32

45

45

46

50

FOLDOUT FRAME

60

62

64

66

68

70

72

2 45 45 46 50 42 50 27

60

43 55 18

20

33

144

25

□ □ □ □

□ □ □ □ □ □ □ □

6 SOLDOUT FRAME

70 72 74 76 78 80 82 84

23

144

192

111

30

DESIGN

7 FOLDOUT FRAME

2 84 86 88 100 102 104 106




Figure 6.4-1. Integrated


8 SOLDER FRAME



102

104

106



9 FOLDOUT PAGE

Figure 6.4-1. Integrated Activity Timeline—Mission 2

fatigue and psychological adjustment of a shutdown activity followed by a startup and return to somewhat hazardous duty in the same day. On the other side of the argument is the fact that a major overhead cost and effort is required to suitup for each EVA period which is likely to be limited in number of work hours both by the life support system and by crew fatigue. Policy decisions need to be formulated to cover such occurrences which happen near the middle of a given EVA work shift. In the case of this analysis, the results probably are not crucial to costs or to total time on orbit, but they may be in actual work conditions in the future.

During the early portion of the mission, some of the activities are obviously interrupted by crew rest periods. This factor was not so obvious in the Mission 1 activity timeline, due to the overlapping and simultaneous nature of the activities.

#### 6.4.2 Crew Activity

Crew activity scheduling for Mission 2 is similar to that for Mission 1. Three teams of two persons each are presumed to be operating for three shifts of eight hours per day during EVA activities. Thus, a crew of six is required to accomplish the mission using the schedule shown. Suit pressure and pre-breathing issues are similar.

Six EVA shifts of actual work are required. However, the delays mentioned above (Section 6.4.1) require suiting up and repressurizations for seven shifts of work, two of which are of short duration.

#### 6.4.3 Lighting and TV Camera Requirements

The second and third missions use many of the same lamps and TV cameras locations provided for the first mission. However, their uses will be different. For example, in the second mission the cameras and lights mounted on Construction Station No. 1 will be useful for observation of the grappling, transport and installation of the forward and aft support structure assemblies, the forward assembly (control module/solar array), the struts, the alignment measurement device, and the electrical system checkout cable. The tilt and pan mechanisms provided for the TV camera and lamp units offer desirable requisite versatility for these added functions. The orbiter payload bay lamps again are used for helping grapple and remove items or for replacing them into the bay as before, but no assembly actually takes place in the bay.

Significant changes include removal of the beam builder lamps and camera and impact of the modified cherry picker on the RMS. The wrist camera and lamp on the RMS will be of little use when the cherry picker is joined to the standard end effector. Instead, the eyes of the EVA astronaut and the cherry picker lamps will perform the functions required.

The processes and viewing angles required for installing the forward and aft support structure and the forward assembly have conflicting needs for lighting as the activity proceeds. For example, the lamps on the construction fixture yoke are helpful in grappling, removing from the payload bay and trans-

porting. However; when it comes to detailed joining operations, these lights will probably cause unacceptable glare and shadows on the key interfaces because of their location. Therefore, the construction procedure calls for turning these lamps off (or turning them aside) and relying on the cherry picker (or RMS wrist lamp) for illuminating the detail final joining or adjusting operations. Whenever these activities can be performed in daylight there is further opportunity to turn off the lamps mounted on the construction fixture (however, such reductions are not included in power and energy calculations).

The multiplicity of TV camera locations permits the crew in the cabin to view nearly all operations and to help guide the lamps to illuminate the scene effectively. Active cooperation and verbal communication between the EVA and IVA operator are necessary for illuminating cherry picker operations effectively and for avoiding counter-productive glare and shadow conditions.

Figure 6.4-2 summarizes the key locations for lights and TV cameras for the second mission. The figure also suffices to describe these items for the third mission which is described in Section 7.0.


In general, the power demand for lighting during the second mission is about 45% of the total, a greater percentage of total construction power than in the first mission. This result is primarily due to lack of power demands for beam fabrication, while other major activities (lighting and transport/assembly) are similar in power levels to those for the first mission.

#### 6.4.4 Power Demand Analysis


The key assumptions and estimating procedures for the power and energy analysis of the second mission were largely the same as for the first mission. A major difference was the lack of a beam builder machine. Another significant difference was that the entire mission was considered in an end-to-end analysis, including crew rest periods as they occurred in chronological time.

Figure 6.4-3 presents the complete power profile for the second mission. Although the second mission is longer than the first, the complexity of analysis was not as great, since there are few parallel and overlapping operations. The resulting profiles of peak and average power reflect less frequent variations of a smaller magnitude than for the first mission. In addition, there was a benefit to the analysts in learning from the analysis of the first mission. This learning resulted in more complete and rapid analysis techniques.

The average requirements for power during the second mission are significantly lower than for the first. The key factor which explains this reduction is the lack of heating requirements for forming beams or joining beams together. The other major factors which are present in both Mission 1 and Mission 2 are the RMS and the lights.



**/ FOLDOUT FRAME**



ITEM  
NO.

(1)

(2)

(3)

(4)

(5)

(6)

NOTES

(a)

(b)

(c)

(d)

2 FOLDOUT FRAME

# LIGHTS AND TV CAMERAS FOR CONST

ITEM NO.	DESCRIPTION—CHARACTERISTICS/USAGE	PEAK POWER
(1)	THREE 60-W INCANDESCENT LAMPS MOUNTED ON ADJUSTABLE BRACKETS OR STANCHIONS OF MODIFIED OPEN CHERRY PICKER (OCP) (STANDARD—PER MRWS DEVELOPMENT PLAN). <u>PURPOSE</u> —DETAILED ASSEMBLY, INSTALLATION ADJUSTMENT, AND INSPECTION OPERATIONS BY EVA OPERATOR. ALSO ASSISTS IN GRAPPLING WITH STABILIZER/MANIPULATOR ARM ON OCP.	0.180
(2)	ONE TV CAMERA UNIT (STANDARD ORBITER ITEM) WITH TILT AND PAN MOUNT. <u>LOCATION</u> —FORWARD BULKHEAD OF ORBITER PAYLOAD BAY. <u>PURPOSE</u> (FOR CONSTRUCTION)—ASSIST IN OBSERVATION OF CHERRY PICKER AND RMS OPERATIONS AT FORWARD END OF ETVP.	0.247
(3)	ONE ORBITER DOCKING LAMP (STANDARD). <u>LOCATION</u> —BETWEEN DOCKING WINDOWS ON UPPER SURFACE OF CABIN, FIXED, POINTING UPWARD. <u>PURPOSE</u> —BERTHING AND SEPARATION OF ORBITER FROM CONSTRUCTION FIXTURE	0.200
(4)	ONE ORBITER PAYLOAD BAY LAMP, METAL HALIDE TYPE, FIXED. <u>LOCATION</u> —FORWARD BULKHEAD OF ORBITER PAYLOAD BAY, BETWEEN WINDOWS. <u>PURPOSE</u> (FOR CONSTRUCTION)—ASSIST EVA EGRESS/INGRESS AND TRANSVERSE TO CHERRY PICKER MOUNTING POINT.	0.200
(5)	ONE INCANDESCENT FLOOD LAMP AND TV CAMERA FIXED TOGETHER ON TILT/PAN MOUNT. <u>LOCATION</u> —LOWER CROSSBRIDGE OF BUILDING FIXTURE YOKE. <u>PURPOSE</u> —ASSIST IN OBSERVATION OF EVA ASTRONAUT, MONITOR TRANSLATION OF ETVP THROUGH BUILDING FIXTURE.	0.247
(6)	FOUR LAMP AND TV UNITS SIMILAR TO (5) (EACH 0.247 PEAK POWER). <u>LOCATION</u> —SIDE OF BUILDING FIXTURE YOKE, FACING FORWARD END OF ETVP, DISTRIBUTED AS SHOWN. <u>PURPOSE</u> —OBSERVE EVA, RMS OPERATIONS.	0.988

## NOTES

- (a) ITEMS (2), (5), (6), (7), AND (9) MAY ALSO ASSIST OBSERVATION OF TRA
- (b) EVA SUIT WILL HAVE WORKLIGHTS.
- (c) RUNNING LIGHTS AND BEACON FOR RENDEZVOUS NOT SHOWN.
- (d) ALL LIGHTS AND TV CAMERAS SHOWN (EXCEPT OPEN CHERRY PICKER) ARE ALSO

Figure 6.4-2. Lights and TV Cameras for Const

3 FOLDOUT FRAME




CAMERAS FOR CONSTRUCTION—SECOND MISSION

	PEAK POWER	ITEM NO.	DESCRIPTION—CHARACTERISTICS/USAGE	PEAK POWER
LE D. NT,	0.180	(7)	TWO LAMP AND TV UNITS SIMILAR TO (5). <u>LOCATION</u> —SIDE OF BUILDING FIXTURE YOKE, FACING AFT END OF ETVP NEAR OUTER END. <u>PURPOSE</u> —OBSERVE EVA INSTALLATION OF THRUST STRUCTURE AND REMOVAL OF STRUTS FROM STOWAGE CANISTER ON ORBITER STAR- BOARD SIDE.	0.494
LT	0.247	(8)	SIX METAL HALIDE LAMPS OF 0.200 kW EACH (STANDARD ITEMS). <u>LOCATION</u> —SIDE WALLS OF ORBITER PAYLOAD BAY (ONE OF SIX ILLUSTRATED). <u>PURPOSE</u> (FOR CON- STRUCTION)—BACKGROUND FOR EXTRACTING AND STOWING OF CONSTRUCTION EQUIPMENT. NOTE: SPECIAL DIF- FUSERS OR BLINDS MAY BE NEEDED TO PROTECT TV CAMERAS FROM DIRECT VIEW OF LAMPS.	1.200
P-	0.200	(9)	ONE TV CAMERA UNIT (STANDARD ORBITER ITEM) WITH TILT AND PAN MOUNT. <u>LOCATION</u> —AFT BULKHEAD OF ORBITER PAYLOAD BAY. <u>PURPOSE</u> (FOR CONSTRUCTION)— ASSIST IN GRAPPLING AND EXTRACTION OF MODULES AND CHERRY PICKER IN PAYLOAD BAY, TRANSPORT OF STRUTS.	0.047
	0.200	(10)	ONE TV CAMERA WITH TILT AND PAN MOUNT. <u>LOCATION</u> —RMS ELBOW (STANDARD ITEM). <u>PURPOSE</u> (FOR CONSTRUCTION)—ASSIST IN HANDLING BEAMS, OTHER MODULES IN SETUP, CONSTRUCTION, STOWAGE.	0.047
	0.247	(11)	ONE LAMP AND TV CAMERA FIXED TOGETHER ON TILT AND PAN MOUNT. <u>LOCATION</u> —RMS WRIST (STANDARD LOCATIONS, BUT NEW MOUNT) <u>PURPOSE</u> —ASSIST IN GRAPPLING MODULES, TRANSPORT- ING THEM, AND POSITIONING OR BERTHING THEM TO PERFORM SETUP, CONSTRUCTION, AND STOWAGE.	0.220
	0.988			

ERVATION OF TRANSLATION OF STRUCTURAL ASSEMBLY AND DEPLOYMENT OF LIBRATION DAMPER.

CKER) ARE ALSO USED IN MISSION NO. 1.



MISSION TIME - G.E.T.

18

20


22

24

PRECEDING PAGE BLANK NOT FILMED

/ FOLDOUT FRAME





22

24

26

28


30

32

34


36

2 FOLDOUT FRAME




32 34 36 38 40 42 44 46

3 FOLDOUT FRAME



2 44 46 48 50 52 54 56

4 FOLDOUT FRAME



56

58

60

62

64

66

68

70




Figure 6.4-3. Power Profile--Second Mis

*EXPLOSION*  
EXPLOSION FRAME



PRECEDING PAGE BLANK NOT FILMED

Table 6.4-1 presents a summary of the power and energy requirements for the second mission. As for the first mission, the total energy demand still requires a cryogenic fuel supply kit in the orbiter to support the construction operations. However, the full potential energy capability of such a kit is never closely approached.

Table 6.4-1. Total Energy and Average Power - Second Mission


Activity Segment	Duration (Hr)	Energy Required (kWh)	Average Power (kW)
o Initial Activity - IVA	0.83	1.63	1.96
o EVA - Construction	50.12	98.91	1.97
o IVA - Alignment Measurements	8.00	17.06	2.13
o Shutdown Activity	<u>0.50</u>	<u>.41</u>	<u>0.83</u>
Nominal Total Energy	59.45	118.01	1.99
Design Margin (50% of Nominal)	<u>27.3</u>	<u>53.78</u>	<u>1.97</u>
Baseline Magnitudes for Construction Period	86.75 (3.61 days)	171.79	1.98

Lighting power requirements represent a larger percentage of power demand, about 45% for this mission as compared to about 33% for the first mission. Again, this reflects the reduced heating requirements for fabrication and assembly, rather than a greater usage of lamps.



#### 6.4.5 Construction Support Equipment

During the second mission, use is continued for several basic elements of Construction Station No. 1. Since the central cross bridge structure was removed, the platform can be translated through it in either direction. However, removal of the EVA work station requires new provisions for EVA support. These are provided by a different version of the basic open cherry picker, which is attached to the RMS. The cherry picker is now fitted with a powered maneuverable handling boom and special end effector suitable for handling both modules and struts. To minimize requirements for end effector types, the design of modules must incorporate a grapple fixture which will mate with this new end effector.

Construction support equipment for the second mission is described in Figure 6.4-4.




ROTARY HALF  
OF DOCKING PORT  
(ON ORBITER VEH.)




/ FOLDOUT FRAME






TYPICAL PLATFORM STRUT




4



6


IMU NO. 1

BRAKE CONTROL



TETHER & HOOK




5



IMU NO. 1

STRUT WITH RING

## 2 FOLDOUT FRAME



I.D.
1
2
3
4
5
6 7
8
9

3 FOLDOUT FRAME

I.D.	DESCRIPTION
①	<u>BUILDING FIXTURE ASSEMBLY.</u> THIS FIXTURE ASSEMBLY IS THE SAME PIECE OF EQUIPMENT AS THE <u>TECHNOLOGY VERIFICATION PLATFORM (ETVP)</u> , BUT WITH THE BRIDGE BEAM AND ASSOCIATED PLATFORM ASSEMBLY, ONLY THE STRUCTURAL YOKE AND THE BEAM SUPPORT ARM ASSEMBLY.
②	<u>STRUT CONTAINER.</u> A STRUT CONTAINER MODULE IS UTILIZED FOR STORING AND SUPPORTING THE ETVP. THE CONTAINER IS LOCATED AT THE FORWARD END OF THE ORBITER BAY, ON THE ORBITER. IT IS ROTATED OUT OF THE BAY FOR EASY ACCESS TO ITS CONTENTS BY THE RMS WITH THE ETVP.
③	<u>CHERRY PICKER AND HANDLING BOOM.</u> IN THE SECOND MISSION, THE CHERRY PICKER WILL BE USED WITH THIS TOOL AND AN ASTRONAUT SUPPORTED ON THE EVA WORK PLATFORM, STRUTS ARE USED TO ATTACH THE PLATFORM FOR ATTACHMENT.
④	<u>STRUT LENGTH ADJUSTING TOOL.</u> THIS IS A MANUALLY OPERATED TOOL FOR ADJUSTING THE LENGTH OF THE PLATFORM ASSEMBLY. SINCE THIS TOOL IS PORTABLE DURING ITS WORK CYCLE, IT IS USED WHEN NOT IN ACTUAL USE.
⑤	<u>HAND-CRANKED STEM DEVICE.</u> THIS DEVICE EXTENDS THE REACH OF THE ASTRONAUT FOR ATTACHING THE PLATFORM WHICH CAN BE STOWED ON A ROLLER WITHIN THE DEVICE BY USE OF THE CRANK.
⑥⑦	<u>IMU NO. 1 &amp; IMU NO. 2.</u> IMU NO. 1, SHOWN MOUNTED ONTO THE ATTACH FITTING, WILL PROVIDE DATA IN THREE ORTHOGONAL AXES, PLUS PROVIDE A TIMELINE AS TO WHEN DATA WERE TAKEN. IMU NO. 2, SHOWN MOUNTED ONTO THE RCS MODULE ATTACH PORTS AND ALL THE PROPULSION MODULE ATTACH FITTINGS, WILL BE IDENTICAL IN ITS REQUIRED PERFORMANCE TO IMU NO. 1. HOWEVER, IMU NO. 2 IS MORE ACCURATE. THE SYSTEM WILL BE USED TO MEASURE AND RECORD THE RELATIVE ORIENTATION BETWEEN THE ORBITER AND THE CM.
⑧	<u>BASELINE MOUNTING FIXTURE.</u> THE BASELINE MOUNTING FIXTURE PROVIDES A PLATFORM FOR MOUNTING THE ORBITER. THE BASE ALSO PROVIDES A FACILITY TO CALIBRATE AND COMPARE BOTH IMU UNITS. THE COVER PROVIDES A RIGID STABLE BASE TO PROTECT BOTH IMU UNITS FROM STRUCTURAL DAMAGE.
⑨	<u>CHECKOUT SYSTEM.</u> THIS MODULE IS USED TO VERIFY THE SCM OPERATIONS AND ELECTRICAL CONNECTIONS.

TELEOPERATOR  
DOCKING PORT

Figure 6.4-4. Construction Support Equipment

4 SLODOUT FRAME



#### DESCRIPTION

ATURE ASSEMBLY IS THE SAME PIECE OF EQUIPMENT USED DURING CONSTRUCTION OF THE INITIAL ENGINEERING AND (P), BUT WITH THE BRIDGE BEAM AND ASSOCIATED FABRICATION ELEMENTS REMOVED. DURING THIS SECOND PHASE LURAL YOKE AND THE BEAM SUPPORT ARM ASSEMBLIES ARE REQUIRED.

MODULE IS UTILIZED FOR STORING AND SUPPORTING ALL THE BRACING STRUTS REQUIRED FOR INSTALLATION ON THE E FORWARD END OF THE ORBITER BAY, ON THE STARBOARD SIDE. DURING ACTUAL USE, THE CONTAINER WITH STRUTS ACCESS TO ITS CONTENTS BY THE RMS WITH THE CHERRY PICKER.

THE SECOND MISSION, THE CHERRY PICKER WITH A STRUT HANDLING BOOM IS SUPPORTED ON THE END OF THE RMS. PORTED ON THE EVA WORK PLATFORM, STRUTS ARE REMOVED FROM THE STRUT CONTAINER AND TRANSPORTED TO THE

A MANUALLY OPERATED TOOL FOR ADJUSTING THE LENGTH OF THE STRUT AFTER ONE END HAS BEEN ATTACHED INTO TOOL IS PORTABLE DURING ITS WORK CYCLE, PROVISIONS ARE BUILT ONTO THE CHERRY PICKER TO SECURE THE TOOL

SE EXTENDS THE REACH OF THE ASTRONAUT FOR HANDLING STRUTS. THE POLE PORTION IS FORMED AS A THIN SHEET IN THE DEVICE BY USE OF THE CRANK.

OWN MOUNTED ONTO THE ATTACH FITTING, WILL BE UTILIZED TO MEASURE AND CONTINUOUSLY RECORD ORIENTATION DE A TIMELINE AS TO WHEN DATA WERE TAKEN. THIS PIECE OF EQUIPMENT WILL BE USED TO MEASURE ALL PAYLOAD ALL THE PROPULSION MODULE ATTACH FITTINGS, TO DETERMINE ALIGNMENT RELATIVE TO IMU NO. 2. IMU NO. 2 IS TO IMU NO. 1. HOWEVER, IMU NO. 2 IS MOUNTED ONTO A FEMALE TELEOPERATOR DOCKING PORT AS SHOWN. THIS RECORD THE RELATIVE ORIENTATION BETWEEN THE SYSTEM CONTROL G&N BASE AND THE TELEOPERATOR PORTS MOUNTED

LINE MOUNTING FIXTURE PROVIDES A PLATFORM TO TRANSPORT BOTH IMU NO. 1 AND IMU NO. 2 WHILE IN THE CILITY TO CALIBRATE AND COMPARE BOTH IMU UNITS BEFORE AND AFTER USE. THIS FIXTURE PLATFORM AND PROTECT BOTH IMU UNITS FROM STRUCTURAL OR THERMAL DISTORTION WHEN NOT IN ACTUAL USE.

TO VERIFY THE SCM OPERATIONS AND ELECTRICAL CONTINUITY OF THE ETVP.

Figure 6.4-4. Construction Support Equipment for Second Mission

#### 6.4.6 Flight and Site Support Equipment

PRECEDING PAGE BLANK NOT FILMED

General comments in Section 5.4.6 also apply herein. Unique requirements for the second mission include a stowage pallet for the open cherry picker, the checkout unit, the alignment measuring IMU storage unit, the forward assembly modules and the forward and aft deployable support structures. At the end of Mission 2, the libration damping system on the construction fixture is again employed for unattended flight stabilization.

#### 6.5 CARGO MANIFEST

Table 6.5-1 summarizes the cargo types and weights for the second construction mission. Details are presented in Appendix C.

Table 6.5-1. Cargo Manifest Weight Summary

<u>Launch Mode</u>	Weight (lb)	Mass (kg)
Platform Items (Satellite)	23,660	10,732
Construction Items	990	449
Airborne Support Equipment	<u>8,957</u>	<u>4,063</u>
Total Cargo (Up)	33,607	15,244
<u>Return Mode</u>		
Construction Items	990	449
Airborne Support Equipment	8,957	4,063
Less Expendables	<u>-1,033</u>	<u>-469</u>
Total Cargo (Return)	8,914	4,043

The following assumptions were made with respect to developing the cargo mass statement.

1. Mission based on six crewmen for six days. This 36 man days is an increase of 8 man days over the orbiter baseline of 28 man days. Thus, an additional 8 man days of crew systems is provided.
2. Eight additional airlock repressurizations. A total of 10 is required (two are orbiter baseline). Each nitrogen tank kit has a capacity of 4.5 EVA's. Thus, two additional N<sub>2</sub> tank kits are required (Kits Nos. 5 and 6). The oxygen required for repressurizing the airlock is 2.7 lb. Thus, 21.6 lbs for the eight additional repressurizations. The additional cryokit (see next item) provides an excess of 56 lbs of oxygen that can be used for this loss.

3. Eight man days of additional metabolic oxygen at 2.08 lb/man day, or 16.6 lbs, combined with the airlock loss gives 37.2 lbs which results in an 18.8 lb remaining reserve in the cryo O<sub>2</sub> kit.
4. Unit No. 3 has been added over the Orbiter 2 kit baseline. In addition to supplying electrical power, it has the benefit of supplying oxygen for the airlock loss and crew metabolic requirements.
5. Fixed life support items added for two additional crewmen.
6. All cryo expanded (as water) overboard for return. Forty pounds per tank of N<sub>2</sub> gas expended overboard for return.
7. Additional 8 man day of crew water (93 lbs) supplied by water produced from the additional cryokit.

Figure 6.5-1 shows the cargo horizontal c.g. plotted on the orbiter c.g. envelope constraints for both the up, or abort condition, and for return case. As will be noted, both cases are satisfactory from a c.g. standpoint. Also, the lateral and vertical c.g.'s are well within the orbiter c.g. envelope. The mass of the total cargo is 15,241 kg (33,607 lbs). The normal return mass is 4,043 kg (8,914 lbs).

Figure 6.5-2 illustrates the orbiter packaging arrangement for the ascent phase. Further details are shown in Drawing No. 42662-67 in Appendix A.




Figure 6.5-1. Cargo Center-of-Gravity Locations




Figure 6.5-2. Second Mission Mainfest



## 7.0 THIRD CONSTRUCTION MISSION

This section describes the detailed integration of the activities for the third construction mission.

### 7.1 CONSTRUCTION PLAN

The objective of the third mission plan was to complete the construction of the platform and activate it to begin operations in low earth orbit (LEO). This scenario concept delays installation of the three orbital propulsion modules until near the end of the operations period at LEO.

A secondary mission objective (not analyzed) could be the installation of payload modules, since it was found that considerable volume is available in the orbiter payload bay beyond that required to accomplish the primary objectives.

Completion of the platform construction requires installation of four reaction control system (RCS) pods, one on each end of the extreme forward and aft crossbeams. The resulting configuration is shown in Figure 7.1-1. Note that the construction fixture is left on the operational platform spacecraft in a passive state as an aid to later servicing, payload installation, and payload changeout or modifications during operations in low earth orbit. (The construction fixture is removed prior to transfer to GEO.)

#### 7.1.1 Construction Requirements

Construction requirements specific to the third mission are listed in Table 7.1-1.

#### 7.1 2. Construction Logic

The logic diagram for the third mission is presented in Figure 7.1-2.

### 7.2 CONSTRUCTION PROCESS

The construction process in the third mission is preceded by a rendezvous and berthing operation similar to that for the second mission. Also, as in Mission 2, initial construction preparations include stowage of libration damper RCS pods and attaching an open cherry picker to the end of the RMS, followed by unfolding of the cherry picker and boarding by an EVA astronaut.

The first actual construction operations involve the cherry picker grappling an RCS pod stowed in the aft end of the orbiter payload bay and installing it at the end of the forward crossbeam attach port. To assure both adequate clearances and adequate reach, the platform may have to be translated a short distance through the construction fixture. The installation operation is repeated for a second RCS pod at the opposite end of the crossbeam as shown in Figure 7.2-1.

PRECEDING PAGE BLANK NOT FILMED





Figure 7.1-1. ETVP Configuration at Completion  
of Third Mission

Table 7.1-1. Construction Requirements  
for the Third Mission

- PROVIDE FOR INSTALLATION OF FOUR RCS PODS.
- PROVIDE FOR MEANS TO ACTIVATE AND CHECK OUT ALL SYSTEMS ON THE ENTIRE PLATFORM TO ASSURE OPERATIONAL READINESS FOR LOW EARTH ORBIT (LEO) OPERATIONS.
- PROVIDE MEANS TO RENDEZVOUS AND SAFELY BERTH WITH THE ORBITING CONSTRUCTION FIXTURE/PLATFORM ASSEMBLY PRIOR TO BEGINNING CONSTRUCTION OPERATIONS.
- PROVIDE MEANS FOR REVISIT TO THE ORBITING PLATFORM SPACE-CRAFT FOR CHANGEOUT OR INSTALLATION OF PAYLOADS, FOR SERVICING OF PLATFORM SYSTEMS, AND FOR UPDATING/REFURBISHING PRIOR TO TRANSFER OF THE PLATFORM TO GEOSYNCHRONOUS ORBIT.
- PROVIDE MEANS FOR SAFE SEPARATION OF THE ORBITER FROM THE ACTIVATED PLATFORM.



\*Payloads may be installed in parallel with this activity.

Figure 7.1-2. Logic Diagram for Construction Activities during Third Mission

• INSTALL RCS MODULES




Figure 7.2-1. Installation of RCS Modules

ORIGINAL PAGE IS  
OF POOR QUALITY

The use of a cherry picker for this module installation operation was based on the following considerations. First, the pod is a large module, awkward to handle and align to the attach ports by using the RMS alone. The reach would be difficult. However, such considerations alone would not necessarily preclude use of the RMS. The second consideration was that the following major activity would be a checkout procedure in which the presence of the EVA astronaut could be useful in case of anomalies in measurements or hangups in operations. A third consideration is that the cherry picker provides a useful extension of reach for the RMS arm, facilitating the function of pulling an electrical umbilical cable from the orbiter to the forward assembly in order to activate the platform systems and perform final checkout. The connection site is one of the teleoperator docking ports which is fitted with a special connector. The checkout umbilical has an end fitting which mates mechanically with the teleoperator port prior to making the electrical connection.

The checkout activity includes full deployment of the solar array and test of the RF command and control links. Following checkout, the electrical umbilical cable is removed and returned to the orbiter by the EVA astronaut on the cherry picker as shown in Figure 7.2-2.

Figure 7.2-3 summarizes the major translations and rotations of the platform with respect to the orbiter during the third mission. Using the same convention as in Figure 6.2-7, the platform is portrayed as stationary, while the orbiter is shown as translating and rotating. In contrast to motions in the third mission, the orbiter reverses its direction of rotation and retraces its path, to the position and orientation it had upon berthing at the beginning of the mission. The RMS and cherry picker is, thus, in a favorable orientation to attach an electrical umbilical cable to the system control module to enable platform activation and final checkout.

### 7.3 CONSTRUCTION ACTIVITY ANALYSES

The nature of activity in the third mission is similar to that in the second, except that it is shorter and has no parallel operations. There are only two significant types of construction activities—that of installing the four RCS pods and that of performing the final activation and checkout of the platform. The other activities are actually repositioning motions which facilitate the installation and checkout. As in the second mission, there are rotations of the platform with respect to the orbiter about the berthing port axis. These are similar, but occur in opposite directions. The installation of RCS pods and the checkout operations are somewhat repetitious activities, but all tasks and movements are accounted for in the descriptions.

The Construction Activity Data Sheets for Mission 3 appear in Appendix B as numbers 41.0 through 45.0. As in the case of the previous mission analyses, the function of separation of the orbiter from the construction fixture is not described as a construction activity.




Figure 7.2-2. Removal of Umbilical Following Platform Checkout and Activation




Figure 7.2-3. Third Mission Assembly Sequence



#### 7.4 INTEGRATION ANALYSIS

The integration analysis process for the third mission closely followed that for the second mission. A complete integrated activity timeline was prepared, and the power profile and energy analysis was developed for the complete mission, as required to complete the basic platform. There is volume and weight capacity in the orbiter payload for an as yet undefined type of payload (e.g., antennas) for the platform. However, the construction analysis was performed without considering such payload installations, timelines, power, energy or crew utilization.

##### 7.4.1 Timeline Analysis

The integrated activity timeline for the third mission appears in Figure 7.4-1. The construction time is much shorter than for the previous missions, and the functions are small in number. Considerable time is spent in translation and rotation of the platform with respect to the orbiter because of the locations of the RCS pods at opposite ends of the platform. Only two EVA work shifts are required, and the EVA astronaut can hardly be described as busy during the last one. If payload installations were included in this mission, a higher utilization of crew time might be expected, as these payloads would be installed by stopping along the path of translation between the forward and aft RCS pods.

##### 7.4.2 Crew Activity

Because of the reduced workload, a crew of four was selected for the third mission. As before, the crew consists of two teams of two persons, one IVA and one EVA astronaut. Crew activity scheduling generally follows the concept shown in Figure 5.4-5. That is, a four-man crew is set up in two teams of two men each. Since the mission requires such a short duration, the nominal standard crew of four in the orbiter appeared to be adequate. In fact crew size is not a significant driver in this mission.

##### 7.4.3 Lighting and Television

Lighting and television viewing requirements for the third mission are similar to those for the second mission, which were graphically summarized in Figure 6.4-2. The only new requirements concern installation of the RCS pods at the ends of long crossbeams. Considering the short duration required for this mission, such work could well be done on the daylight side, with little penalty. However, it is expected that adequate light will be available on the construction fixture and in the payload bay to grapple the pods and transport them to their respective attachment ports. If final closure and alignment is to be done in darkness, some special provisions for lighting locations might be required on the cherry picker, the RCS pods, or the structure. One or more extendable stanchions could be the solution for this problem. The light holder device may need to be adjusted by the astronaut prior to his final approach and berthing, since there is a strong chance there could be an obstruction during the prior grasp and transport phase. In contrast to the current design locations for the open cherry picker (behind the EVA operator) a location above and forward may be preferred for this particular activity.

PRECEDING PAGE BLANK NOT FILMED

MISSION TIME - G.E.T. 0

ACTIVITY

41.0 PREPARE CONSTRUCTION SYSTEM \_\_\_\_\_

42.0 INSTALL RCS MODULES \_\_\_\_\_

43.0 TRANSLATE PLATFORM \_\_\_\_\_

44.0 ROTATE 180° \_\_\_\_\_

45.0 PLATFORM CHECKOUT \_\_\_\_\_

EVA ASTRONAUT No. 1 \_\_\_\_\_

EVA ASTRONAUT No. 2 \_\_\_\_\_

| SLODOUT FRAME

1

2

18

19

20

21

22

ss

50

42

45

50

6

10

10

10

2) FOLDOUT FRAME

21

22

23

24

25

26

27

45

42

45

58

60

60

58

10

10

10

10

10

10

3 FOLDOUT FRAME

29

30

31

32

33

34

35

36

216

157

20

10

4

FOUR OUT. LEAVE

35

36

37

38

39

40

41

DESIGN MARGIN 7 HRS. 54 MIN.

END OUT


5

10

11

12

13



*φ* FOLDOUT 14 MI

Figure 7.4-1. Integrated Activity  
Timeline - Third Mission

Such a location would place the lamps closer to the berthing interface and would permit easier reach and control by the cherry picker operator.

Deployment of the solar array should definitely take place in daylight because of the great length of the array. Attempting to illuminate the surface of the array would require two or more searchlights of considerable weight and high power requirements. Such lighting provisions are not considered cost effective.

#### 7.4.4 Power and Energy


The power profile for the third mission is illustrated in Figure 7.4-2. The highest potential power demand occurs during activation of the platform systems using orbiter power; however, the uncertainty of this demand is rather high. It is likely that power can be applied to only a portion of the systems at a time in order to avoid exceeding the orbiter 7-kW limit. Total power and energy requirements are listed in Table 7.4-1.

Table 7.4-1. Total Energy and Average Power--Third Mission

Activity Segment	Duration (hr)	Energy Required (kWh)	Average Power (kW)
• Initial activity - IVA first translation	0.83	1.65	1.99
• EVA - RCS installation	8.00	15.09	1.89
• EVA - Checkout period	6.88	22.51	3.27
• Shutdown activity - Included in above	—	—	—
Nominal total energy	15.77	39.25	2.50
Design margin (50% of nominal)	+7.89	+19.63	+2.50
	23.60	58.88	2.50
Baseline magnitudes for Construction period	(0.98 days)		

PRECEDING PAGE BLANK NOT FILMED





MISSION TIME - G.E.T.

18


19

20

21

22


FOLDOUT FRAME



20 21 22 23 24 25 26 27

2 FOLDOUT FRAME

0



25

26

27


28

29

30

31

3 FOLDOUT FRAME



30 31 32 33 34 35

4 FOLDOUT FRAME

Figure 7.4-2. Power Profile - Third Mission

PRECEDING PAGE BLANK NOT FILMED

#### 7.4.5 Construction Support Equipment

Figure 7.4-3 summarizes key construction support equipment for the third mission. No new equipment items are required as compared to those for the second mission. The RCS pods are designed to have fittings compatible with the jaw end effector on the open cherry picker.

#### 7.4.6 Flight and Site Support Equipment

The most notable new flight support item in Mission 3 is the rotating cradle support for the RCS pods in the payload bay. This support cradle concept features a revolver barrel type of mechanism which brings each RCS pod in turn to the uppermost portion of the bay to provide access for grasping by the cherry picker. This feature permits a compact stowage system in the payload bay which leaves room for additional cargo.


#### 7.5 CARGO MANIFEST

The cargo types and weights for Mission 3 are summarized in Table 7.5-1; details are included in Appendix C. Figure 7.5-1 illustrates the locations of ascent boost and return centers of gravity. The ascent c.g. location is near the aft limit as currently designed; however, this can be improved by proper packaging. There is included in the mass estimate a nominal, undefined payload mass of 3,396 lb which is the remaining capability after including the required items for Mission 3.

The following assumptions were made in the development of the cargo mass statement:

1. The mission will not exceed the orbiter baseline of 28 man-days.
2. No additional airlock repressurizations are required over the orbiter baseline.
3. One additional cryo kit is included. This requirement is based on a very small identified demand over the baseline 50 kWh which is normally available to the payload. The identified demand is based on nominal requirements for construction in the third mission, plus a 50-percent design margin. If the added payload capacity is used for platform payload items (antenna, etc.), additional power would be required for such installation, thus creating a greater need for a larger portion of the kit capacity.
4. Maximum cargo weight, without OMS kit for 250 n.m. of 30,000 lb.
5. Additional payload, over the RCS modules, c.g. located at the center of the open bay (Station 944.5).

Figure 7.5-2 illustrates the packaging arrangement of items for ascent in the payload bay of the orbiter. The hypothetical payload outline is based upon a set of communication antennas which would be installed at the ends of crossbeams on the platform. Further details are shown in Drawing No. 42662-68 in Appendix A.



I.D.	DESCRIPTION
①	CONSTRUCTION FIXTURE. SEE FIGURE 5.4-10.
②	RMS. SEE FIGURE 5.4-9.
③	MODIFIED CHERRY PICKER. SEE FIGURE 5.4-11.
④	STABILIZER. THIS BOOM IS UTILIZED FOR STABILIZING THE CHERRY PICKER DURING WORK ASSIGNMENTS. IT WILL ALSO BE USED TO TRANSPORT AND BERTH THE RCS PODS AND LARGE PAYLOAD MODULES ONTO THE PLATFORM.
⑤	SYSTEM CHECKOUT MODULE. THIS MODULE IS USED TO VERIFY THE SCM OPERATIONS AND ELECTRICAL CONTINUITY OF THE ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM. IT ALSO CONDITIONS POWER PROVIDED FROM THE ORBITER TO THE PLATFORM FOR SYSTEM ACTIVATION AND OVERALL SYSTEM CHECKOUT.

Figure 7.4-3. Key Construction Support Equipment for Third Mission

Table 7.5-1. Cargo Manifest Weight Summary

	WEIGHT (lb)	MASS (Kg)
<u>Launch Mode</u>		
Platform Items (RCS Module)	18,800	8,528
Payload (Max. for 250 n. m.)	3,396	1,541
Airborne Support Equipment	7,804	3,539
	<hr/>	<hr/>
Total Cargo (Up)	30,000	13,608
<u>Return Mode</u>		
	11,200	5,080

ORIGINAL PAGE IS  
OF POOR QUALITY




Figure 7.5-1. Cargo Center-of-Gravity Locations






Figure 7.5-2. Third Mission Manifest

PRECEDING PAGE BLANK NOT FILMED  
8.0 COMPOSITE CONSTRUCTION ANALYSIS

The following material presents an overall summary of end-to-end systems analyses performed relative to construction activity. The information first presented concerns the basic three construction missions. This is followed by brief discussions of other construction activity required, such as payload installations and changeout, outfitting for geosynchronous orbit operations and installation of propulsion modules to effect the transfer to GEO.

8.1 BASIC CONSTRUCTION MISSIONS

This section summarizes results of the analyses for the three basic construction missions. The integrated timeline summary data for these three missions are listed in Table 8.1-1.

Table 8.1-1. Summary of Mission Time Required to Perform Basic Construction Missions

Mission Phase	1st Mission (Hr)	2nd Mission (Hr)	3rd Mission (Hr)
Ascent	6.3	18.5	18.5
Construction Phase	42.4	59.5	15.7
50% Design Margin	21.2	27.3	7.9
Delay for Deorbit (Includes 5.0 hr Bar-B-Que)	22.7	10.1	26.9
Descent	1.6	1.6	1.6
Total Mission Duration	94.2 (4 Days)	117 (5 Days)	70.6 (3 Days)

Tables 8.1-2, 8.1-3 and 8.1-4 present analyses of several types of construction activity timeline concerns specific to the first, second and third construction missions, respectively. Among these are the distribution of IVA and EVA man-hours, and the total hours allocated to structural fabrication and assembly (machine time), to module installation, to transport operations and to electrical lines installation. Also shown are the durations required for setup, shutdown and checkout operations. As a basis for comparison, the activity durations are expressed as a percentage of the total elapsed time for construction time on orbit. Note that when two or more similar operations occur in parallel, the total of machine hours can be greater than 100% of the total elapsed time. Power and energy data for the three missions are summarized in Table 8.1-5.

Table 8.1-2. Mission Time Analysis for Construction  
—First Mission

	<u>Hours Required</u>	<u>Percent of Total Construction</u>
EVA: man-hours	31.65	42.7
IVA: man-hours	<u>42.43</u>	57.3
Total man-hours	74.08	
Structural fabrication and assembly —machine hours	47.76	112.6*
Transport—machine hours	39.55	93.2*
Electrical lines installation	7.2	1.7*
Construction setup (elapsed)	3.27	7.7*
Construction shutdown (elapsed)	2.28	5.4*
Checkout—work hours	1.09	2.6*
*Percent of elapsed construction time (42.43 hr). Parallel operations of different equipment can result in total machine-hours larger than elapsed time for construction.		

Table 8.1-3. Mission Time Analysis for Construction  
— Second Mission

	<u>Hours Required</u>	<u>Percent of Total Construction</u>
EVA: man-hours	44.17	42.6
IVA: man-hours	<u>59.53</u>	57.4
Total man-hours	103.7	
Structural fabrication and assembly —machine hours	7.76	13.0*
Module Installation - machine hours	.50	.8*
Transport—machine hours	30.41	51.1*
Electrical lines installation	1.32	2.2*
Construction setup (elapsed)	9.13**	15.3*
Construction shutdown (elapsed)	2.03	3.4.*
Checkout—work hours	7.34	12.3,*
*Percent of elapsed construction time (59.5 hr).		
**Includes 7-hr calibration period for alignment measurement instrumentation.		

Table 8.1-4. Mission Time Analysis for Construction  
- Third Mission

	<u>Hours Required</u>	<u>Percent of Total Construction</u>
EVA: man-hours	3.92	19.98
IVA: man-hours	<u>15.7</u>	<u>80.02</u>
Total man-hours	19.62	100
Structural fabrication and assembly —machine hours	0	0 *
Module Installation - machine hours	.53	3.4*
Transport—machine hours	7.37	46.9*
Electrical lines installation	0	0 *
Construction setup (elapsed)	1	6.4 *
Construction shutdown (elapsed)	.25	1.6 *
Checkout—work hours	4.87	31.0 *
*Percent of elapsed construction time (15.7 hr).		

Table 8.1-5. Summary of Construction Power and Energy  
—Basic Construction Missions

	<u>Mission 1</u>	<u>Mission 2</u>	<u>Mission 3</u>
Total energy (kWh) (includes 50% design margin)	217	172	58.9
Average power (kW)	3.4	1.98	2.50
Peak power (kW)	8.5	3.2	5.3

A significant result of these analyses is that transport time constitutes a large portion of construction time. Clearly, efforts to reduce transport can have a major effect on reducing on-orbit construction time.

#### 8.1.1 Crew Assignments

A crew of six persons works three 8-hour shifts per day in Missions 1 and 2, in teams of two men each. However, in Mission 3, only four persons are required in the crew, and only two shifts of work are required.

The work shift time allocation for IVA crew includes actual construction work as well as a small amount of orbiter housekeeping time. The multiple shift operations postulated for all missions required some multiple use of sleeping stations. Considerable time is required at the beginning of each mission to set up each team of two persons for each shift.

These shift concepts require training of IVA crew members and EVA crew members to be able to accomplish the specific tasks planned for their shift. If delays are encountered, a different mix of tasks may be required. This concern led to the basic assumption that crew members assigned to IVA tasks should be capable of performing all the IVA tasks on their mission, and a similar requirement applies to EVA personnel.

Since several types of construction equipment require special training, it would be desirable to have the same basic crew perform similar tasks on subsequent missions. In particular, the RMS operations and the cherry picker operations require specialized simulation experience to develop proficiency. Backup crew members will be required to assure availability of trained personnel at time of flight opportunity, and protect the investment in the scheduled Shuttle flight equipment. All crew members must be selected with reference to their skills in mechanical assembly, technical understanding of electro-mechanical systems and ability to perform fairly repetitive activities for several hours at a time during certain phases of the construction.

#### 8.1.2 Ground Support Requirements

The construction activity on orbit is presumed to require little assistance from ground support personnel. Contingency situations which could require technical consultation are a major exception which was not considered in this analysis.

As a policy issue, NASA may desire to follow progress of the construction and utilized TV coverage for public information releases. This would require a crew to process the TV data and provide voice communications.

Each flight is treated as a normal orbiter flight as regards to turn-around activity involving refurbishing supplies and loading the payloads.

## 8.2 OTHER CONSTRUCTION ACTIVITIES

Following the initial three construction missions, additional flights involving construction activities are planned as a part of the overall ETVP scenario. The following sections briefly describe these other construction activities.

### 8.2.1 ETVP Scenario

To help illustrate the overall plan for other construction activities a brief review of the platform operations scenario is presented. Figure 8.2-1 illustrates the planned missions profile in terms of altitudes, time periods and types of operations for a scenario based on communications technology development. In addition, this program will help develop and demonstrate technology in the areas of space construction, space servicing (at both high and low earth orbit) and orbit transfer.




Figure 8.2-1. ETVP Mission Scenario

The three missions described in Sections 5.0, 6.0 and 7.0 are symbolically indicated at the left of the diagram. The next phase of operations emphasizes testing at various low earth orbit altitudes. During this period the orbiter will install and/or changeout various antenna payload items and may perform some servicing operations.

The next phase involves re-outfitting the platform with antenna systems appropriate to geosynchronous orbit operations, and probably changing RCS modules, batteries, gyros and other items with significantly limited life or wearout rates.

This period is followed by three flights dedicated to installing the orbital transfer propulsion modules and a final checkout. The platform is then boosted to geosynchronous orbit for operations of approximately 7 years. One or more flights for servicing or updating are expected during or at the

end of this GEO period. Such servicing may be by teleoperator or manned vehicle designed for flight to GEO.

#### 8.2.2 Payload Installations

The platform and construction equipment designs provide for installation of payloads at 8 places, namely the ends of the four intermediate long cross beams. It is expected that such payloads will typically be some type of antenna, packaged into a compact shape for transport in the orbiter, and capable of deployment following installation. The method for installation would be similar to that for installing RCS pods in Mission 2 or that for attaching the IMU devices for measuring the alignment of the attachment ports, in which the RMS is used alone. From a construction standpoint there are significant differences in handling procedures or equipment requirements from those already described.

#### 8.2.3 Low Orbit Servicing

The primary area of concern for low-orbit servicing is the forward assembly, which contains the electronics, and several other active components. Servicing would likely be accomplished using a cherry picker on the RMS. However, the RMS can reach each unit on the control module for removal and replacement as required.

The solar array would always be retracted to assure there would be no contact with the orbiter wing when it is performing RMS reaching operations in the vicinity of the forward assembly. In low earth orbit the orbiter berths to the construction fixture as for Missions 2 and 3. The construction fixture can also be used to translate the platform so as to provide RMS/ cherry picker access to any of the payload attach ports or to the TT&C antenna at the aft end of the platform.

#### 8.2.4 High Orbit Servicing

Provisions for teleoperator docking are incorporated near the end of each long cross beam and at three locations on the system control module. These are the main provisions for servicing at geosynchronous orbits or at lower orbits not reachable by the orbiter. It is assumed the teleoperator will incorporate a manipulator arm capable of reaching the short distance from the docking port to the items in question, in order to perform removal and replacement.

In some cases during the low earth orbit operations servicing may be accomplished by flying the platform (using RCS) to a lower orbit so as to facilitate orbiter servicing methods and equipment.

#### 8.2.5 Propulsion Module Installations

Installation of the three propulsion modules for orbit transfer is a typical significant concern for construction. It involves the handling of a large bulky mass, from removal out of the orbiter payload bay to alignment

and berthing of the module onto the thrust structure attach port. The selected concept for performing this function is illustrated in Figure 8.2-2. The open cherry picker is used for the majority of the transport and berthing. However, the module is first deployed out of the starboard side of the orbiter payload bay by use of the payload installation and deployment aid (PIDA) arms. The starboard deployment was selected to permit grappling the module near the forward end and to avoid problems of reach or interference by the RMS arm. This location was selected for grappling to permit the EVA crew operator direct vision of the final berthing interface.

Considerable assistance would be expected by the crew in the orbiter cabin, who could observe operations with TV cameras strategically located to see critical clearance points not visible to the EVA operator.

### 8.3 ORBITER MODIFICATION REQUIREMENTS

The construction analysis identified three areas of concern regarding orbiter modification requirements. These are the nitrogen tank installation airlock repressurizations, the RMS mobility enhancement, and the 8-psi suit support provisions.

Additional nitrogen tanks are required to support the multiple repressurizations to perform EVA during the first and second mission. This installation requires special plumbing and tank attachments beyond the standard baseline orbiter provisions. However, the space provisions and design concepts for such modifications have been incorporated into the STS program. This is a relatively minor impact item.

The most expensive and complex modifications identified involve the RMS. These have been described and discussed in Section 5.4.5. Specifically, they include an upper arm roll joint, a wrist camera and light mount with tilt and pan capability, anti-collision software, and provisions to control the RMS from the open cherry picker.

The use of an 8-psi suit in the orbiter is likely to require new suit support provisions in the form of brackets for a larger, bulkier suit, new piping and control valves for the pressure connections, and probably provisions for a two-gas supply system for the portable life support system. In addition, some added storage capacity may be required for the larger number of suits implied in the 6-person crew concept.

### 8.4 CONSTRUCTION SUPPORT EQUIPMENT DEFINITION

This section summarizes the totality of construction support equipment and its usage as identified for fabrication and assembly of the Engineering and Technology Verification Platform (ETVP).

The most significant pieces of construction equipment appear in the complex of devices called Construction Station No. 1. The key elements of this construction station, which are used in all three construction missions are the building fixture yoke and the beam rollers and support arms. The






Figure 8.2-2. Installation of Orbit Transfer Propulsion Module

yoke and roller configuration define the orientation and location of the platform structure. More significantly, they facilitate the translation of the entire platform assembly with respect to the orbiter RMS such that access can be gained to all attachment ports at any time during the second and third missions. They provide for single beam translation, and thus, a desirable separation of the functions of fabrication and of electrical line installations on the first longitudinal beam in the first mission. In summary, they enable the work to be brought to a compact and efficient work space during all phases of construction. Attached to the yoke are the actual construction tools and devices which perform and facilitate construction. The major element of this set is the cross-bridge structure. Rotational and positioning capability is provided within the cross bridge to accomplish the motion requirements for the beam builder and the electric cable reel for wire run installation. The cross beam positioner mechanism and the modified cherry picker, used for astronaut support during platform assembly, are both attached and maneuvered by drive units within the cross bridge structure.

The libration damper booms, TT&C, solar arrays and batteries are located within the building fixture and are utilized as discussed in Section 5.4.5 and in Construction Activity Data Sheet 17.1 (Appendix B).

The basic work tool utilized for parts and equipment translation is the Remote Manipulator System (RMS). A detailed description and modification requirements to this tool are covered in Section 5.4.5(a) of this report.

Additional required construction equipment for platform assembly is located at Construction Station No. 2 (Figure 5.4-12). All ETV platform long and short cross beams with end attach ports plus intersection fittings, wiring and teleoperator docking ports are assembled at this station into complete structural members prior to attachment onto the ETV platform.

The major items required for this operation are, for the most part, non-existing and therefore require new design and fabrication. The beam builder, cherry picker and the remote manipulator system, however, are under study and evaluation by their respective engineering firms. These items were designed and built to meet certain conditions, but would have to be modified in part to meet the requirements for utilization in the large space construction system as outlined in this report. The chief driver for the beam builder selection is that this machine was configured for the SCAPE program by General Dynamics to fabricate triangular light weight beams of the same configuration as those selected for the ETV platform. The Grumman designed cherry picker was chosen as a work tool because, with simple modification, this unit can support the astronaut and provide maneuverability, lighting, and work tool retention during that time when the astronaut is required to assist in the platform assembly.

Miscellaneous tools, devices and life support systems such as RMS end effectors, EVA hand tools, illumination devices, TV cameras and optical alignment devices are all considered to be construction support equipment. Detailed descriptions of the above items and other associated equipment is covered in Section 5.4.5 and Section 5.4.6 of this report.

For ETV platform verification and checkout, an orbiter supported module with an attached storage reel holding the electrical checkout cable is provided as part of the support equipment. By using the RMS supported cherry picker to perform the task of removing the hookup from the reel, and in turn attaching the cable end to the teleoperator port provided on the control module, platform functions and data continuity can be recorded.

#### 8.4.1

Summarized in Table 8.4-1 is a listing of the construction support equipment needed to fabricate and assemble the ETV platform. The usage of the equipment is identified according to requirements for each flight, from initial construction effort, to time of vehicle readiness for delivery to a geosynchronous orbit.

#### 8.4.2 Construction Support Characteristics for Productivity and Cost Effectiveness

The basic concepts incorporated into the construction equipment are derived from good industrial engineering practice. The major benefits are that they provide means to bring the work to a compact work place, thus reducing transportation time and reducing power requirements for lighting a large facility.

Separation of parallel functions is another principal employed to reduce time for construction. The two construction stations used in Mission 1 provide examples.

Commonality of equipment and processes is another principal leading to cost effectiveness. For example, intersection fittings and teleoperator docking ports are installed by the same machine. Use of similar attachment ports in many places is another.

The RMS end effector is, in effect, a tool for transportation and installation. Only three different types are used, the standard end effector, a beam-handling effector and the jaw end effector used on the open cherry picker.

Lights and TV camera locations are selected for multiple use and provided with tilt/pan capability for several operational viewing conditions.

Considerable automation is employed to minimize crew size and on-orbit time costs. However, the builtin dexterity and judgement capabilities of humans are used where it appears that automation would be excessively costly.

#### 8.5 IMPACTS OF CONSTRUCTION ON PLATFORM

The construction of the platform using the orbiter as the construction facility, and the resulting construction scenario, created some restrictions to the configuration which required the development of some unique platform assembly items. Servicing operations concepts also introduced impacts to the platform configuration concept.

Table 8.4-1. Equipment Usage as a Function of Mission

CONSTRUCTION SUPPORT EQUIPMENT	MISSION USAGE					
	FLIGHT			PAYLOAD DEL./ATTACH	PAYLOAD UPDATE	OTV DEL./ATTACH
	1	2	3			
1. BUILDING FIXTURE	•	•	•	•	•	•
2. BEAM SUPPORT ARMS	•	•	•	•	•	•
3. CROSS BRIDGE STRUCTURE	•	•	•	•	•	•
4. BEAM BUILDING - TRIPOD & ATTACH PORT MAG	•	•	•	•	•	•
5. BEAM POSITIONER	•	•	•	•	•	•
6. CROSS CORD REEL CLUSTER	•	•	•	•	•	•
7. WIRE LAYING REEL	•	•	•	•	•	•
8. EVA WORK STATION	•	•	•	•	•	•
9. MMU/HOLDING FIXTURE	•	•	•	•	•	•
10. LIGHTING	•	•	•	•	•	•
11. TV CAMERA	•	•	•	•	•	•
12. Y-FRAME SUPPORT	•	•	•	•	•	•
13. INTERSECTION FITTING & TELEOPERATOR DOCKING PORT MAGAZINE	•	•	•	•	•	•
14. REEL ASSEMBLY FIXTURE	•	•	•	•	•	•
15. RMS	•	•	•	•	•	•
16. SPECIAL END EFFECTOR	•	•	•	•	•	•
17. CROSS CORD HAND TOOL	•	•	•	•	•	•
18. CROSS CORD TETHER	•	•	•	•	•	•
19. ELECTRO-OPTICAL STRUT ALIGNMENT DEVICE	•	•	•	•	•	•
20. CHERRY PICKER WITH STAB, ARM & RMS END EFFECT. STRUT LENGTH ADJUST. DEV.	•	•	•	•	•	•
21. IMU & BASELINE MOUNTING FIXTURE	•	•	•	•	•	•
22. CHECK OUT CABLE & MODULE	•	•	•	•	•	•
23. HAND OPERATED STEM DEVICE	•	•	•	•	•	•
24.	•	•	•	•	•	•

### 8.5.1 Basic Configuration Impacts

The basic configuration was influenced initially by the use of the orbiter as the construction facility. The principal influence was the reach capability of the RMS. Larger tri-beam sizes were also impacted by the orbiter payload bay size and the packaging complexity of the fixture that would be experienced. The platform size as defined in this study is, however, quite satisfactory to perform the anticipated missions.

In order to minimize the construction time for certain operations, such as installing the bracing struts, the orbiter was positioned so that more than one installation could be accomplished from a single position. Consequently, the lengths of the long cross beams were restricted in order to accommodate this goal, and the distance between cross beams was also influenced.

The in-plane cross beam arrangement was influenced by the desire to minimize fixture complexity and construction time. Variations to the end bays of the short cross beams was required in order to achieve the in-plane cross beam configuration. The end bay configuration changes were coordinated with General Dynamics concurrence was received that the changes were feasible with little impact to the basic beam builder.

### 8.5.2 Joints and Connections

The structural joint utilized between the longitudinal beams and the cross beams resulted from the desire to minimize construction time and to minimize complexity. An alternate joint (welding of the beam caps) required weld equipment with complex multi-motions to reach the contact surfaces. Access to these areas was also marginal. The development of the intersection fittings solved the problem of complexity of the joining equipment and reduced the time required for the joining operation (Figure 8.5-1).

The attach port concept was the result of developing a port that could efficiently transfer loads into the beams, be adaptable to various functions, and package efficiently in the orbiter cargo bay. The truss type port utilized on the platform contains these capabilities.

Two unique types of electrical connectors was identified as a result of construction concepts. The installation of the electrical lines in an automatic mode requires the automatic connection of lines to interface connectors. The interface connectors are required to mate with the RCS modules and with payloads. The interface connectors are also unique because they are actuated on command after the RCS module or payloads are mated to the attach ports (Figure 8.5-2).

The other unique connector was involved with the EVA mode of mating the electrical lines between the longitudinal run and the cross beam run. These connectors must be sufficiently large to accommodate the gloved hand of the EVA crewman. In addition, automatic final mating of the connector was desirable. The connector concept developed for this function has these




Figure 8.5-1. Beam-to-Beam Joining Concepts




Figure 8.5-2. Automated Connector Concept

characteristics. The astronaut inserts the guide probe into the mating half, releasing a spring which drives the two halves of the connector together (Figure 8.5-3).

### 8.5.3 Modularity of Systems

Modularizing components and systems resulted from the desire to simplify the installation process, and to define a feasible servicing concept. The RCS modules are a self contained unit including propellant, engines and controls and requires only the automatic mating of power and data lines. A similar concept is utilized for the components installed on the SCM. The SCM components are packaged principally to effect the servicing function of removal and replacement by use of the orbit RMS or by a similar device on a remote or manned servicing vehicle in GEO.

The modularization of the total SCM including the solar array panels and rotary joint provided an efficient package for orbiter payload bay stowage. A single installation activity utilizing the RMS and cherry picker assisted EVA astronaut installs the total SCM on to the platform (Figure 8.5-4).






Figure 8.5-3. Self-Insertion Connector Concept




Figure 8.5-4. Modularity

## 8.6 CONSTRUCTION RESOURCE UTILIZATION

A key issue in space construction is utilization of the available resources. Typically, these consist of basic supplies and additional kits which can be added to supplement nominal mission capability, such as time on orbit, payload power, or number of crew. A major concern is the amount of materials which can be carried up in the orbiter payload bay. These limits may be determined by the orbiter lifting capability or by the payload bay volume. Figure 8.6-1 summarizes four specific areas of interest in resource usage. Each of the four bar charts depicts a percentage utilization for each of the three construction missions.

The upper two charts indicate how much of the possible capacity of the orbiter weight lifting capability and payload bay volume are used in each mission. In the sense defined for this preliminary analysis, the first two missions are volume limited. That is, various construction fixtures, materials and equipment are loaded into the payload bay until the next logical item to be installed will not fit into the bay. The third mission only utilizes about a third of the payload bay volume for construction. Thus, there is space for platform payloads or other concurrent mission payloads, if desired (satellite launch, for example).

### 8.6.1 Kit Utilization

In the discussion of power and energy demand analysis it was pointed out that all missions required a cryogenic kit (hydrogen and oxygen) to provide enough power and energy for the construction activity. If one considers what could have been installed as a fuel kit without impacting the payload bay volume, the maximum is actually two kits per flight. The lower left corner of Figure 8.6-1 uses the two kit basis of 100% of capacity, and compares the calculated energy usage as a percentage of the energy available in the kits. The conclusion is that there is a healthy margin of energy available to accomplish the missions. In fact, in the third mission it would not be necessary to install the cryo kit if the 50% design margin had not been considered. (The actual calculated magnitudes for power and energy utilization for the three missions are summarized in Table 8.1-3.)

The power rate is another type of resource related to energy. As previously noted, the nominal 7 kW limit for orbiter payload power usage was occasionally exceeded in the first mission for a short time. Therefore, one could say the power resource was a limiting factor in construction for this mission, since some rescheduling might be required to avoid such exceedances.

Another kit requirement is the added nitrogen for airlock repressurizations to support the extensive EVA. The current orbiter capability of two 2-man EVA's for mission operations will not be adequate. However, additional Shuttle-type nitrogen tanks can be used, each providing nitrogen for approximately 4.5 repressurizations of the airlock. Since up to eight airlock cycles are required for the most demanding construction mission, two additional tanks will be required. This would give a total of 11 repressurizations (4.5 from each new tank plus the two provided by the baseline orbiter).




Figure 8.6-1. Resource Utilization Summary

It is estimated that up to 12 nitrogen tanks could be located beneath the cargo bay liner in the space designated for the fifth cryo energy tank set. Since the added cryo is not needed for the ETVP construction missions there is more than ample space for the required two additional nitrogen tanks. Even with the fifth cryo tank set installed there is ample volume for additional nitrogen tank installations, but they are located in more difficult locations. Modifications to the orbiter will be required for tank mounting and to provide the necessary fluid interfaces.

#### 8.6.2 Crew Utilization

The subject of crew utilization is at once a vital one, and yet one difficult to accurately quantify. The graph at the lower right of Figure 8.6-1 shows the 100% level as 42 man days. This figure is based on the concern that costs for extra supplies become excessive after nine days, and that one day is required to ascend and another to descend. The remaining time, seven days, is available for construction work by the crew of six. It is also a convenient nominal maximum in that the stowage provisions in the cabin are nominally designed to accommodate 42 man days.

The aforementioned graph indicates that the construction work time requires less than half the available 42 man-days. This implies a healthy margin exists for construction crew workload planning. Such a margin can provide for uncertainties in actual construction task workloads and may further allow consideration of the use of the currently planned 4-psi suit as a backup to the study baseline 8-psi suit. Construction productivity is reduced with the 4-psi suit because of pre-breathing requirements. Thus, the crew workload margin may offer the possibility in program planning of having a mission backup capability in the event funding and/or technical difficulties impact the availability of the 8-psi suit.

#### 8.6.3 Uncertainties

The subject of resource utilization cannot be completely discussed without some acknowledgement of the uncertainties of the estimates used to evaluate the system. Table 8.6-1 summarizes the two major types of uncertainties, design margin and contingency.

Because of the preliminary nature of the analysis and its dependence on predicted characteristics of machines and procedures not as yet developed, the design margin of 50% may be highly optimistic. In fact, little experience is available to quantify crew pauses and planning time in using the RMS for construction types of activities. The translation times are also subject to considerable error, although these times are perhaps the best known. Actual process times are also gross estimates in many cases. The beam builder machine is a key factor and has been the subject of considerable study. Yet, it has not been proved in actual space construction. The power estimates for lighting are admittedly highly optimistic in their frugality, and could be a major factor in causing power peaks which would tend to reduce parallel operations. Power for the construction machinery might be considerably above the estimates used if further analysis proves that heaters are needed for much of the machinery proposed.

Table 8.6-1. Uncertainty Issues

Uncertainty	Considerations	Used	Maybe
Design Margin	<ul style="list-style-type: none"> <li>o Crew Time</li> <li>o Translation Time</li> <li>o Process Time</li> <li>o Lighting Power</li> <li>o Process Power</li> <li>o Package Density</li> </ul>	50%	> 100%
Contingency Margin	<ul style="list-style-type: none"> <li>o Redundancy</li> <li>o Testing</li> <li>o Front-End Costs</li> </ul>	0%	≥ 0%

ORIGINAL PAGE IS  
OF POOR QUALITY

These various uncertainties related to design margin can be significantly controlled by simulation and testing of parts and procedures, in the normal course of advancing technology. It is time to start on the testing and development process now, if we are to have space construction in the near future.

The other type of uncertainty listed in Table 8.6-1 is a wild kind of variable, the contingency or accidental situation which is relatively unpredictable. Such events are partially prevented by testing of machinery and processes over many cycles, by careful training and by meticulous inspection and traceability of materials. If not preventable, the effects may be circumvented by redundancy and various alternate methods. The system analysis performed during this study has given almost no attention to such contingency possibilities. Past experience shows that additional costs are incurred by backup methods and multiple parts which reduce the likelihood of mission failure. Trade studies to evaluate the impact of such costs against the cost of additional flights to complete a given space structure need to be made as development progresses. Space construction, like construction on the ground, has an inherent set of financial and personal risks associated with it. There is much to learn about this new field of human endeavor, particularly in the areas of crew performance and safety.

PRECEDING PAGE BLANK NOT FILMED

## 9.0 CONCLUSIONS AND RECOMMENDATIONS

The foregoing analysis of construction has shown that the specific Engineering and Technology Verification Platform large space structure can be constructed in space using the Space Shuttle orbiter. The analysis was based upon a completely successful operation, without specific regard for delays or need for additional equipment, power and time for contingencies. However, it has been shown that the construction approach provides for margins in time and energy which could provide means to work around many types of contingencies. Therefore it appears that space construction, using the orbiter is both feasible and practical for structures several times larger than the orbiter.

### 9.1 CONSTRUCTION EQUIPMENT

The analysis showed that equipment currently being studied or under development for the Space Shuttle program can be utilized effectively as major aids to construction, if appropriate modifications are made. The major modifications required involve the RMS arm. It is recommended that this arm incorporate an upper arm roll joint and appropriate software changes. Another highly desirable modification is a tilt and pan capability for the wrist camera.

A case has been made for development of a higher pressure suit (eight-psi) and an eight-hour life support system to accomplish EVA for construction in a short time on orbit, using three crew shifts. In addition such a system eliminates the inconvenience and discomfort of prebreathing prior to EVA. It is recommended that EVA suit systems be developed specifically to support space construction, with particular emphasis on reducing prebreathing, donning time and doffing time.

Advantages have been demonstrated for the concept of a versatile construction fixture which permits access to all portions of the construction during the majority of the construction process. Such advantages include minimal power requirements for lighting and transportation, relatively small transport time requirements and capability to utilize existing manipulator equipment effectively.

It was concluded that several specialized mechanisms are desirable to enhance automation and thus minimize on-orbit time costs. It is recommended that selective development of such machinery be undertaken in preparation for future construction.

The process of analysis highlighted the need for a comprehensive series of simulations and tests to develop accurate and reliable data on time, power and crew requirements for performing typical space construction operations.



## 9.2 CONSTRUCTION CONCEPT IMPACT ON STRUCTURE DESIGN

The construction analysis has shown that cost effectiveness for space construction creates a profound impact on the design of the item to be constructed. This interaction is briefly summarized in Table 9.2-1. The 3-dimensional linear tri-beam structure, made of space fabricated beams was selected for the platform because of its potential for high construction productivity, its ability for growth and its legacy value in developing 3-D structures technology required for future large area space systems. Studies have shown the length of the tri-beam structure can be increased to 400 meters or more while retaining adequate loads and stiffness properties. No changes to the basic construction system or process would be required with increased length. This is a key advantage for the linear configuration. The automation afforded by space fabricated beams in conjunction with the linear shape yields the potential for high construction productivity. The main construction activity occurs as the assembled structure translates through the main fixture.

The principal dimensions of the platform were driven by several considerations. The basic tri-beam "cross sectional" dimensions, height and width, were set mainly by RMS reach limits. The resulting tri-beam spacing also facilitated the packaging of the main construction fixture. Simple swing-out rotations of key fixture members to form the basic V-shape were possible without the need for major telescoping mechanisms. Thus, RMS reach and construction fixture packaging were the drivers for the platform height/width dimensions.

The platform length was totally driven by the number of payloads and their related spacing requirements. For the advanced communications technology payloads used in the study model, provisions for 8 antenna packages with deployed diameters up to 20 meters were required.

Lap joints were utilized for joining the cross beams to the longitudinal beams because they are simpler to assemble than a butt joint. Inter-section fittings that provide the joint reaction via a materials bonding arrangement were defined. Heating elements integral to the fittings provide the bonding energy.

The truss type attach ports provide the means for attaching modules and payloads, secure the SCM and thrust structure to the platform, and secure the cross beam bracing struts. The attach ports are secured to the structure by insertion into the caps of the cross beams and bonding in place similar to the lap joints.

Deployable type truss structures are provided to support the SCM and orbit transfer propulsion modules. The deployable design permits ease of installation and reduces the time for construction.

Bracing struts are utilized to minimize torque deflections on the long cross beams that support the RCS and payload modules. The primary tri-beam section is thereby minimized in dimension, making it compatible with construction from the orbiter.

Table 9.2-1. Design Drivers Summary

PLATFORM FEATURE	DESIGN DRIVER
<p>3-D, SPACE FAB LINEAR WIDTH LENGTH STRUCTURE LAP JOINT INTERSECTION FITTINGS MODULE ATTACH PORTS DEPLOYABLE "FWD" &amp; "AFT" STRUT ASSY'S STRUT BRACING P/L ALIGN VIA GROUND ADJUST DIAGONAL CORDS SYST CONTROL MODULE OPEN "T" STRUCT, EXTERNAL LRU'S FOLD OUT RADIATOR 2-STEP S/A DEPLOYMENT PEP TYPE S/A ASYMMETRIC S/A CONFIG 250 ELECT SYST</p>	<p>POTENTIAL FOR HI CONST PRODUCTIVITY CONST EASE, GOOD GROWTH POTENTIAL, MISSION ADAPTABILITY RMS REACH P/L COMPLEMENT (COMM TECH MISSION)</p> <p>SIMPLIFIED CONSTRUCTION SIMPLIFIED JOINING EASE OF INSTALLATION &amp; SPACE SERVICING SIMPLIFIED CONSTRUCTION &amp; AID STRUCTURES TECH DEV</p> <p>ALLOW SMALLER TRI-BEAM DIMENSION REDUCED PLATFORM COMPLEXITY THRUST LOADS, TORSIONAL STIFFNESS</p> <p>LRU ACCESS FOR SPACE SERVICING ORBITER BAY PACKAGING BAY PACKAGING AS A SINGLE SCM/SA UNIT UTILIZE PLANNED TECHNOLOGY DEV SIMPLIFIED CONSTRUCTION (SINGLE INSTALL) CONDUCTOR PACKAGING (REELS) &amp; INSTALL EASE</p>

The attach ports dedicated to payloads are measured to determine their deviation from zero alignment as related to the SCM reference base. The measurement is accomplished via an IMU self-contained package that measures and records the deviations. Adjustments to the payloads are made on the ground to account for the deviations. This concept simplifies the construction operation and minimizes the on orbit construction time.

Diagonal cords in all three planes of the tri-beam provide the torsional stiffness required for orbit transfer and for operational stability.

The system control module (SCM) was driven by a combination of factors. Its open "T" shape was governed by on-orbit servicing requirements. This shape provides the needed access to the individual replaceable units (LRUs) as well as ports for teleoperator berthing for remote controlled space servicing operations. In addition, the SCM was designed with fold-out radiators and an integrally packaged solar array rotary joint assembly. The entire unit was designed for transport to orbit and installation on the platform as a single package. This simplifies orbiter logistics provisions as well as the construction operations associated with its installation.

Solar arrays comprised of PEP (Power Extension Package) type wings were specified in order to utilize planned technology developments. The assymetric solar array arrangement was selected because it offers comparative simplicities in platform design and construction, inherent design and servicing advantages of consolidated subsystems at a single location, and its potential for additional payload accommodations on the open end which could provide wide unobstructed viewing. A symetric design, while offering the advantages of downsized attitude control/CMG's, does pose design complexities for integrating the OTV thrust structure with the solar array rotary joint/mounting structure.

The electrical power system voltage (250 V) was driven by construction and packaging considerations. Use of a 250 V system allows sufficient wire flexibility that wire runs can be stowed on reels for transport to orbit. This yields compact bay packaging, which is important to construction mission payload manifests which are typically volume limited. Also, wire harness installation complexity was greatly reduced by single run deployments from reels rather than the handling of a large number of individual stiff wire segments.

All of the foregoing design interactions point to the conclusion that large area systems to be constructed in space must consider the construction system/process in the design of the project. Only the proper balance between project system features and construction system complexities will produce practical system designs.

### 9.3 IMPACT OF SPACE CONSTRUCTION ON SHUTTLE ORBITER

The specific construction project analyzed has a potential for requiring modifications to the baseline Space Shuttle Orbiter and its associated equipment. Among the most obvious potential impacts are the modifications of the RMS to provide increased mobility (upper arm roll joint), visibility of operations (wrist camera and lights tilt and pan), and provisions to accept a cherry picker.

Provisions for additional tanks of nitrogen to support multiple EVA excursions and tanks of additional fuel for payload energy are also a major significance to orbiter systems. Mission-specific controls, displays and software must be installed for space construction. However, these may not require unusual installations as compared to other payloads.

Less obvious than the above are the implications of multiple shift crew operations. Historically, space vehicle crews have found it difficult to sleep in shifts, largely due to the noise, light and general disturbances of activity of the non-sleeping crew. This problem is also experienced to some degree by night shift workers on the earth. It is clear that the solution to the problem may require some major crew accommodations revisions, and special considerations. Examples could include additional sound proofing, vibration isolators, light - tight closures around bunks, and possibly ear plugs and eye masks for the sleepers. A mild sleeping pill is also a possibility for assisting sound sleep under the admittedly abnormal, exciting and potentially hazardous situation of space flight. The selection and detail design requirements for equipment, selection of drugs, design of crew procedures and crew training methods constitute an area of technology development in the field of habitability for space vehicles. The solutions which arise from addressing these construction-specific problems of Space Shuttle Orbiter operations can also aid other mission objectives for the orbiter and thus extend its general usefulness. The technical approaches which can be used to investigate the crew operations problems and solve them are within the current state-of-the-art. However, they do require some rather expensive simulation and measurement equipment, considerable time of expert personnel and participation of astronaut subjects in a series of experimental sessions and demonstrations, much as was done for the Apollo and Skylab projects. Since preparations for such efforts require a relatively long lead time, such studies should be started soon in order to have the required solutions in place when needed.

Another area of crew accommodations concern involves provisions to stow and gain access to additional EVA pressure garments and backpacks. If such suits are of a higher-pressure design (5-8 psi) there could be other system changes required to perform recharge and checkout operations. Such suits may require a larger stowage volume than the lower pressure garments and portable life support systems. These potential impacts need further study to evaluate approaches and quantify impacts.




## APPENDIX A

### ENGINEERING CONCEPT DRAWINGS

42662-45A	Engineering and Technology Verification Platform
42662-50	Tri-Beam Construction Facility System and Operations, Configuration of
42662-52	No. 2 Construction Station Applications Technology Platform
42662-53	Shuttle Bay Packing Initial Flight
42662-55	EVA Work Station
42662-56	Electric Cable Laying Machine, Crossbeam ETVP
42662-57	Control Module Axsembly - Engineering & Technology Verification Platform
42662-59	Forward Assembly and Installation
42662-60	Interorbital Thrust Structure, Engineering Technology Verification Platform
42662-61	Payload Interface Connector (Electrical) ETVP
42662-63	Structural/Mechanical Latch for Payload ETVP
42662-64	Modification to Beam Builder - ETVP
42662-65	RCS Module Installation via, Cherry Picker
42662-67	Shuttle Bay Packaging - Second Flight
42662-68	Shuttle Bay Packaging - Third Flight
42662-71	Bracing Strut Installation Via, Cherry Picker
42662-72	Male Module Attach Port
42662-74	Solar Array Assembly
42662-78	EVA Work Station Functions - Description & Illustration

PRECEDING PAGE BLANK NOT FILMED

1 ACP-S805A



BEAM TO BEAM ATTACHMENT

FOLDOUT FRAME

ON FITTING  
DED TO CROSS  
THE CROSS BEAM  
ON FIXTURE


ION FITTING

ON MATERIAL FOR  
ING TO CROSS BEAMS  
OWN TOP SIDE)

AL CONTACTS


MATERIAL FOR BONDING  
TUDINAL BEAMS  
(ON LOWER SIDE)

S BEAM WITH ATTACHED FITTING,  
BE BONDED TO LONGITUDINAL BEAM  
URING BEAM TO BEAM ASSEMBLY IN THE  
PLATFORM CONSTRUCTION FIXTURE



LONGITUDINAL  
BEAM

VERSE BEAM WITH FITTING  
BONDED TO LONGITUDINAL  
WHILE IN PLATFORM  
FIXTURE



KU-BAND ANTENNA MAST

ANTENNA SUPPORT  
TOWER

AXIS LONGITUDINAL  
APEX BEAM

DETAIL F


1.19 M

1.09 M

TELEOPERATOR DOCKING PORT  
(BONDED TO BEAM AT THE  
CROSS BEAM FABRICATION FIXTURE)

THERMO PLASTIC FUSION  
MATERIAL FOR BONDING  
DOCKING PORT TO CROSS BEAMS


CROSS BEAM END ATTACH PORT




LONG CROSS BEAM

DETAIL L


2 FOLDOUT FRAME



ORIGINAL PAGE IS  
OF POOR QUALITY




DETAIL F





DETAIL L



FOLDOUT FRAME








ORIGINAL PAGE IS  
OF POOR QUALITY






5 FOLDOUT FRAME

42662 - 45

A I



ORIGINAL PAGE IS  
OF POOR QUALITY




TRANSVERSE BEAM  
5.60 M. LONG (TYP)


LONGITUDINAL BEAM  
FOR SUPPORTING ALL  
ELECTRICAL & DATA  
WIRE RUNS  
(SEE SHEET NO. 2)

FOLDOUT FRAME

TAIL C



FOLDOUT FRAME




FOLDOUT FRAME


8

42662-45

A I







M.

4.967 M

11 FOLDOUT NAME

DR BY: <i>John Thompson</i> 11-80		Revised Inter- Space 12214 Lakewood Boulevard	
CHK BY:		ENGINEERING VERIFICATION	
APPROVED BY:		SIZE: L	
		CODE IDENT NO: 03953	
		DRAWING: 42	
		SCALE: 1/200	

MODULES  
JUST  
(MODULE)

4.40 M. DIA (TYP)

U-BAND TTY/C  
ANTENNA  
(DWS 42662-73)

THURST

D)

Y

TRANSVERSE BEAM  
5.60 M. LONG (TYP)

LONGITUDINAL BEAM  
FOR SUPPORTING ALL  
ELECTRICAL & DATA  
WIRE RUNS  
(SEE SHEET NO. 2)

SECTION A-A

LONGITUDINAL BEAMS  
107.75 M. LONG (REF)

TELEOPERATOR PORT  
& REQD PER CROSS BEAM  
(SEE VIEW "L")

RCS MODULE (REF)

4.30  
M

12 FOLD LINE

A-1,  
A-2

DR BY <i>[Signature]</i> 1/1/80		Rockwell International Corporation Space Division 12714 Lakeside Boulevard Torrance, California 90501	
CHK BY		ENGINEERING & TECHNOLOGY VERIFICATION PLATFORM	
APPROVED BY		SIZE CODE IDENT NO DRAWING NO	
		L 03953 42662-45A	
		SCALE 1/100	

REVISIONS			
NO	DATE	DESCRIPTION	APPROVED

D

C

42662-45A

A



5-11-60-5000-0000  
DWG. NO.

48

47

46

SHORT CROSS BEAM

ORIGINAL PAGE IS  
OF POOR QUALITY

LONGITUDINAL BEAM  
WITH END ATTACH PORT  
ASSY.

POWER BUS NO. 1

POWER BUS NO. 2

M

N

PWR. LINE NO. 1

DVR LINE NO. 2

PWR. LINE NO. 3

PWR LINE NO. 4

2 CORE 2-TSP

DEDICATED ST-TSP

2 CORE 2-TSP

M

N

CONNECTORS INTERFACE  
WITH LINES TO SYSTEMS  
CONTROL MODULE / WIRE  
SUPPORT TRAY  
(SEE DWG 42662-57)

FOLDOUT FRAME


PRECEDING PAGE BLANK NOT FILMED

49

47



46

BEAM WITH ACS MODULES

DUCTOR  
POWER BUS


FOLDOUT FRAME

2

CONNECTOR ATTACHED TO  
CROSS MEMBER BY VELCRO  
STRIPTWISTED SHIELDED LEADS  
& COAX LEAD CONNECTORS


SECTION N

ORIGINAL PAGE IS  
OF POOR QUALITY




3 FOLDOUT FRAME

S BEAM




ORIGINAL PAGE IS  
OF POOR QUALITY



SECTION M-M



4 BOLDOUT FRAME



5 FOLDOUT FRAME

DED

2 BUSES  
TORS .25 mm<sup>2</sup> CA



TO SWITCH GEAR ON SAS  
U - BATTERY CHARGE UNIT, CONTAINS  
CHARGE/DISCHARGE CONTROLLER  
R - CONVERTER, REGULATOR


TT & C - TRACKING, TELEMETRY &  
COMMAND SUBSYSTEM  
S - SWITCH GEAR

GN & C - GUIDANCE, NAVIGATION  
& CONTROL SYSTEM  
TC - THERMAL CONTROL  
SYSTEM

CONTROL MODULE ELECTRICAL POWER SYSTEM

6 **EXPLODOUT FRAME**


42662-45 A 2




MEASUREMENT &  
SYSTEM

GN & C - GUIDANCE, NAVIGATION  
& CONTROL SYSTEM  
TC - THERMAL CONTROL  
SYSTEM

SYSTEM



POWER




ELECTRICAL

7 BOLDOUT FRAME

ARRAY SYSTEM

MODULE


PAYLOAD ATTACH PORTS (TYP) 8 PLACES



RCS MODULE

MODULE


POWER & DATA LINE ROUTING ARRANGEMENT  
(ENGINEERING & TECHNOLOGY VERIFICATION PLATFORM)



ELECTRICAL POWER FUNCTIONAL SCHEMATIC


8 FOLDOUT NAME





# ARRANGEMENT

(LOCATION PLATFORM)



- SAS - SOLAR ARRAY SYSTEM
- MA - MAIN ARRAY
- BCA - BATTERY CHARGE ARRAY
- ND - NODDING DRIVE
- SRA - SLIP RING ASSEMBLY
- S - SWITCH GEAR
- RCS - REACTION CONTROL SYSTEM
- C/R - CONVERTER/REGULATOR
- L - LOAD
- PM - PROPULSION MODULE


# IAL SCHEMATIC

9 FOLD

## REVISIONS

ZONE	LIN	DESCRIPTION	DATE	APPROVED

RCS MODULES - 4 PL.

PROPULSION  
MODULES (3)

MODULE

SAS - SOLAR ARRAY SYSTEM  
 MA - MAIN ARRAY  
 BCA - BATTERY CHARGE ARRAY  
 ND - NODDING DRIVE  
 SRA - SLIP RING ASSEMBLY  
 S - SWITCH GEAR  
 RCS - REACTION CONTROL SYSTEM  
 C/R - CONVERTER/REGULATOR  
 L - LOAD  
 PM - PROPULSION MODULE

10 FOLD

 A-3,  
 A-4

SIZE	CODE IDENT NO	DRAWING NO.
L	03953	42662-45A
SCALE	SHEET 2 OF 3	

72

71

70

C-4

EACD-5035P

D

C

→

B

A

10 M. DIA SUB REFLECTOR  
ANTENNA

4.52 M.

BICHORIC GRID

5.10 M


14 GHz RECEIVER

POLARIZATION GRID


12 GHz TRANSMITTING  
PHASED SCANNED ARRAY12 GHz TRANSMITTING  
HORN SPOT BEAMSCAN PHASED AR  
SCALEORIGINAL PAGE IS  
OF POOR QUALITY

FOLDOUT FRAME

M. DIA SUB REFLECTOR  
ANTENNA




ORBIT TRANSFER



ANTENNA

ORBIT TRANSFER



ANTENNA CONF 3 - 3

ORIGINAL PAGE IS  
OF POOR QUALITY

FOLDOUT FRAME

67

66

65

T DIRECTION

PLATFORM MATING  
ATTACH PORT

4.52 M.

DEPLOYABLE  
DISH ANTENNA

EXTENDABLE BOOM MAST

7.5 M. DIA

TAKE-UP REELS FOR POWER &amp; DATA CABLES

- ORBIT TRANSFER MODE

16.20 M.

ANTENNA / FEED HORN  
ELECTRICAL HOOK-UP  
CABLE LEAD

POINTED AT TRANS

POINTS TOWARD EQUATOR

DIRECTION

3.7 M. DIA REFLECTOR  
ANTENNA

- ANTENNA CONFIGURATION  
ANTENNAS SHOWN E  
DIFFERENCES (SEE

- FEED HORN AND ANTENNA  
CONTAIN THE CAPABLE  
ALIGNMENT AND BO

ISOLER REEL

FEED HORN ASSEMBLY

FOLDOUT FRAME

INTERLEAVE ANTENNA LAYOUT

SCALE 1/100


42662-45 A

3

65

64

63



4 FOLDOUT FRAME

INTERLEAVE ANTENNA CONFIG

SCALE 1/400


426E2-45A

3


64

63

TION



5 FOLDOUT FRAME




DIA 12/14 GHz  
7 SCANNING PHASED ARRAY  
TRANSMITTING / RECEIVER ANTENNA



6 FOLDOUT FRAME



107.75 M. (REF)




7 FOLDOUT FRAME




8 FOLDOUT NAME

49


SIZE	CODE IDENT NO	GRAPH NO
L	03953	42662-45A
SCALE		





FOLDOUT FRAME



2 FOLDOUT FRAME




LONGITUDINAL BEAM 3 PL.

TRAVERSE BEAM  
2 PL. PER FRAME STATIONLONGITUDINAL BEAM ROLLER SUPPORT  
ARM ASSEMBLY 1

3 BOLDOUT FRAME

# ADINAL BEAM ROLLER SUPPORT ASSEMBLY 1




4 FOLDOUT FRAME

13

12

11



ORIGINAL PAGE IS  
OF POOR QUALITY

5

FOLDOUT FRAME



ON

CROSS BEAM ELEMENT (REF)

FIRTLIE SYSTEM  
BRIDGE BEAM ASSY

1


.36 M

5.68 M


DOCKING

OUT FRAME


6 FOLDOUT FRAME




42662-50




FOLDOUT FRAME





## 8 FOLDOUT FRAME



REVISIONS			
ZONE	LTR	DESCRIPTION	DATE APPROVED
	1	SEE SHEET NO. 4 FOR DESIGN CHANGES MADE AS A RESULT OF AUTOMATED ASSEMBLY REQUIREMENTS	11-19-79 <i>Thompson</i>
	2	SEE SHEET NO. 3 FOR ADDITION OF LIBRATION DAMPER SYSTEM	11-21-79 <i>Thompson</i>

9  
FOLDOUT FRAME


A-7,  
A-8

DR BY <i>Thompson</i>		9-23-79		Rockwell International Corporation Space Division 12214 Latwood Boulevard • Downey, California 90241	
CHK BY				TRI-BEAM CONSTRUCTION FACILITY SYSTEM & OPERATIONS, CONFIGURATION OF	
APPROVED BY					
SIZE		CODE IDENT NO		DRAWING NO	
L		03953		42662-50	
SCALE				SHEET 1 OF 2	

48

47

46



CABLES

LONGITUDINAL BEAM ASSY

LONGITUDINAL/CROSS BEAM INTERSECTION FITTING

PLATFORM - CROSS BEAM

SEE SHEET NO. 4 FOR REDESIGN  
OF CROSS BRACE CABLE REELS &  
SUPPORT STRUCTURE ASSEMBLY

BUILDING FIXTURE  
YOKE ASSY (REF)LONGITUDINAL BEAM  
NO. 1 (REF)LONGITUDINAL  
Y

BUILDING FIXTURE YOKE

PLATFORM STRUCTURE  
DIAGONAL CORD REEL & SUPPORT ASSY.

1.54 M

CROSS BEAM ASSY (REF)

.20 M

LONGITUDINAL BEAM

BEAM POSITIONER SUPPORT

TRANSVERSE BEAM ASSY.

BUILDING FIXTURE  
BEAM ASSY

NO. 3 LONGITUDINAL BEAM (REF)


BUILDING FIXTURE ASSY (REF)

BUILDING FIXTURE  
YOKE ASSY (REF)

FIXTURE

CABLE CROSS BRACING  
POSITION & ASSEMBLY

FOLDOUT FRAME



3 FOLDOUT FRAME

BUILDING FIXTURE [1]  
BRIDGE BEAM ASSY. (REF)

BUILDING FIXTURE (REF)

LONGITUDINAL BEAM NO. 1 (REF)

WIRE STORAGE REEL  
INSTALLATION LOCATION

CABLE LINE  
CONNECTORS

DIRECTION OF BEAM TRAVEL  
DURING DATA/POWER LEAD  
CABLE INSTALLATION

FIXTURE SYSTEM [1]  
BRIDGE BEAM SUPPORT (REF)

BEAM BUILDER  
SWING ARM (REF)

DATA/POWER LEADS  
STORAGE REEL &  
SUPPORT STRUCTURE

SSY [1]  
E SYS.

[1] LONGITUDINAL BEAM  
ROLLER SUPPORT ARM (REF)

BUILDING FIXTURE  
YOKE ASSEMBLY (REF)


POSITIONER  
ORIENTATION

BEAM ASSY  
STRUCTURE

VER CABLE INSTALLATION  
LONGITUDINAL BEAM


4 FOLDOUT FRAME





VIEWS SHOWING ADDITION OF ATTACH  
PORT POSITIONER, WELDING SYSTEM &  
STORAGE MAGAZINES

ATTACH PORT  
AND ATTACHMENT



ATTACH PORT  
POSITIONER  
MECHANISM

180°

1.6 M STROKE


180°

ATTACH PORT

BEAM BUILDER  
STRUCTURAL FRAME


5 FOLDOUT FRAME

LONGITUDINAL BEAM



BEAM BUILDER STRUCTURAL FRAME

SECTION 13 - 13




LONGITUDINAL ROLLER

LONGITUDINAL


1 LONGITUDINAL BEAM ROLLER SUPPORT

BUILDING ASSEMBLY



**7** FOLDOUT FRAME

DETAILS AND ASSEMBLY OF  
PLATFORM BEAMS & INTERSECTION FITTING



POSITIONER  
ARM ASSY. 1

URE BRIDGE  
BLY 1

BEAM ASSY

BUILDING FIXTURE  
SYSTEM-YOKE ASSY

TRANSVERSE BEAM (REF)

CROSS BEAM POSITIONER (REF)  
(ROTATES TO 3 POSITIONS)

CROSS BEAM (REF)

4.30 M  
(REF)

BEAM POSITIONER  
SWING ARM ASSY

BUILDING FIXTURE BRIDGE  
BEAM ASSEMBLY 1

TRANSVERSE BEAM (REF)

BUILDING FIXTURE RIGIDIZING  
ARMS (TYP BOTH SIDES)

BUILDING FIXTURE  
YOKE SUPPORT & DOCKING ADAPTOR ASSY (REF)

DETAILS AND ASSEMBLY OF  
FORM BEAMS & INTERSECTION FITTINGS

9 FOLDOUT FRAME

26

25

REVISIONS			
NO.	DATE	DESCRIPTION	APPROVED
1	11-12-79	SEE SHEET NO. 4 FOR DESIGN CHANGES MADE AS A RESULT OF AUTOMATED ASSEMBLY REQUIREMENTS	<i>W. J. Longman</i>
2	11-21-79	SEE SHEET NO. 3 FOR ADDITION OF LIBRATION DAMPER SYSTEM	

ARM POSITIONER  
WING ARM ASSEMBLY 1STRUCTURE BRIDGE  
ASSEMBLY 1

ARM (REF)

RIGIDIZING  
(DES)

9 FOLDOUT FRAME

A-9,  
A-10


DATE	CODE IDENT NO.	DRAWING NO.
L	03953	42662-50
SCALE	SHEET 2 OF 4	


26

25

ORIGINAL PAGE IS  
OF POOR QUALITY


# FOLDBOUT FRAME






BATTERY MODULE (REF)

DETAIL VIEW 12



DETAIL VIEW 10

SOLAR CELL BLANKET  
(LOWER SURFACE OFDETAIL VIEWS  
LIBRATION DAM  
ASSOCIATED EC

54

53

52

COLD GAS MODULE  
WITH 1 LB. THRUSTERS

9.10 M  
(29.85 FT)

18.2 M  
(59.70 FT)

8.90 M

+Z

SOLAR CELL BLANKET (35 SA FT)  
(LOWER SURFACE OF BOOM)

ORIGINAL PAGE IS  
OF POOR QUALITY

BATTERY MODULE  
(1.12 M<sup>3</sup> - 39.5 FT<sup>3</sup>)

2.457  
(ORBITER SYS)

OMNI ANTENNA (FAR SIDE)

DETAIL VIEWS SHOWING ADDITION  
LIBRATION DAMPING SYSTEM AND  
ASSOCIATED EQUIPMENT

-Z  
(X<sub>0</sub> 679 50)

OMNI ANTENNA (NEAR SIDE)

COMPUTER MODULE  
(1.3 M x 1.3 M x .15 M)

TT & C MODULE

GYRO SENSOR MODULE  
(.58 M x .58 M)

3 FOLDOUT FRAME


54

53

52




REV		
ZONE	LTR	DESCRIP



SOLAR CELL BLANKET (35 SA. FT)  
(UPPER SURFACE OF BOOM)

18.2 M  
(59.70 FT)



PLATFORM CROSS  
BEAM-STRUCTURE ASSY

.87 M (2.85 FT.)

+X

COLD GAS MODULE  
WITH 1 LB THRUSTERS

ORIGINAL PAGE IS  
OF POOR QUALITY

COMPUTER MODULE  
(.3 M x .3 M x .15 M)

TT & C MODULE

GYRO SENSOR MODULE  
(.58 M x .58 M x .81 M)

FRONT FRAME

49

**10**

C

**B**



C

12

2

1

**1**

1

1

10

A-11,  
A-12


**FULL OUT FRAME**

50


49

## FOLDOUT FRAME

ORIGINAL PAGE IS  
OF POOR QUALITY



POWER / DATA WIRE  
CABLE STORAGE REEL



PLATFORM CROSS CABLE  
STORAGE REEL & SUPPORT  
STRUCTURE


- ① MECHANICAL LATCH BETWEEN BEAM BUILDER AND SUPPORT TRIPOD
- ② ELECTRICAL CONNECTION BETWEEN BEAM BUILDER AND SUPPORT TRIPOD
- ③ MECHANICAL LATCH BETWEEN SUPPORT TRIPOD AND CONSTRUCTION FIXTURE
- ④ ELECTRICAL CONNECTION BETWEEN SUPPORT TRIPOD AND CONST FIXTURE
- ⑤ ELECTRICAL CONNECTION BETWEEN BUILDING FIXTURE AND SHUTTLE ORBITER

NOTE: • SEE DWG 42647 603 FOR A FUNCTIONALLY SIMILAR MECHANICAL LATCH  
• SEE DWG 42642 70 FOR A FUNCTIONALLY SIMILAR ELECTRICAL INTERFACE CONNECTOR

5

*2*  
FOLDOUT FRAME


DATA WIRE  
STORAGE REEL




FOLDED CONA  
CROSS BRACING STORAGE  
DATA/ELECT. REEL

OPERATION: FOLD  
DATA/ELECT. REEL

NOTE CROSS BRACING




FOLDED CONFIG  
CROSS BRACING STORAGE REEL ASSY.  
& DATA/ELECT. REEL ASSY.



OPERATING POS  
DATA/ELECT. REEL STORAGE REEL

NOTE: CROSS BRACING REEL POS. OMITTED FOR CLARITY

FOLDOUT FRAME




CROSS BRACING STORAGE REEL ASSY  
DEPLOYED CONFIG

NOTE: DATA/ELECT. REEL OMITTED FOR CLARITY





42662-50

4




SS MAKING STORAGE REEL ASSY  
DEPLOYED CONFIG

DATA/ELECT. REEL OMITTED FOR CLARITY

VIEW B'-B'


LONGITUDINAL BEAM  
ROLLER SUPPORT ARMS  
(STOWED CONFIG - EXTENDABLE  
BOOM MOUNTED ARMS)




LONGITUDINAL BEAM  
ROLLER SUPPORT ARMS  
(STOWED POS. - FIXTURE MOUNTED ARMS)

VIEW A'-A'


FOLDOUT FRAME



ELECT. / DATA  
CABLE STORAGE  
REEL (FOLDED CONFIG)



BEAM POSITIONER





LONGITUDINAL BEAM  
SUPPORT ARMS  
(FIXED POS. - FIXTURE MOUNTED ARMS)

ELECT./DATA  
CABLE STORAGE  
REEL (FOLDED CONFIG)

BEAM POSITIONER

BRIDGE BEAM EXTENSION  
(OPERATIONAL POSITION)

MECH. LATCHES

SEPARATION PL

.48 M

.25 M

5.68 M  
(REF)

BRIDGE BEAM EXTENSION  
(FOLDED CONFIG.)

7 FOLDOUT FRAME

BRIDGE BEAM EXTENSION

3.75 M

1.0 M

.65 M

BEAM BUILDER SUPPORT  
SWING ARM

.98 M

.80 M



.48 M


.43 M

.88 M

42662-50



4






9

FOLDOUT FRAME







D

C

B


A



INTERSECTION FITTING NO SCALE

ORIGINAL PAGE IS OF POOR QUALITY

CONNECTOR INSTLN



REEL





CLIP INSTALLATION

3 BAYS

CROSSMEMBER WELD

INTERSECTION FITTING WELD STATION

CUT OFF SHEAR



VELCRO

LINE CLIP SCALE: FULL SIZE

SEQUENCE OF OPERATIONS FOR BUILDING A CROSSBEAM SCALE: 1/80

WELDOUT FRAME

① FABR SECT

② WELD FITTING WITH PAYLOAD (RC)

③ CONN POWER RCP

④ INSTAL AT EACH WELD FITTING


⑤ CONTIN LINE OF WELD FITTING

⑥ CUT OF BEAM BY DRI

⑦ WELD PORT

⑧ CONNE POWER TO RC

- ① FABRICATE SHORT SECTION OF BEAM.
- ② WELD END PORT FITTING, COMPLETE WITH REMOTE CONTROL PAYLOAD INTERFACE (RCPI)
- ③ CONNECT DATA & POWER LINES TO RCPI
- ④ INSTALL LINE CLIPS AT EACH CROSSMEMBER. WELD INTERSECTION FITTING.
- ⑤ CONTINUE TO INSTALL LINE CLIPS. WELD 2nd INTERSECTION FITTING.
- ⑥ CUT OFF BEAM. BEAM IS SUPPORTED BY DRIVE ROLLERS.
- ⑦ WELD 2nd END PORT & RCPI
- ⑧ CONNECT DATA & POWER LINES TO RCPI.



ORIGINAL PAGE IS  
OF POOR QUALITY.


VIEW BB

SCALE: 1/40


2 FOLDOUT FRAME

5 BEAM.

CTOR INSTLN

INTERSECTION  
FITTING INSTLN  
STATION

- FRAME: (1) STOWS END PORTS  
FOR TRANSPORTATION  
IN ORBITER BAY.  
(2) FORMS PART OF  
CONSTRUCTION  
STATION AS  
SHOWN HERE.





VIEW AA

SCALE: 1/40

4 FOLDOUT FRAME








42662-52

SH

1

X<sub>2</sub> 27006  
(1064)

NO 2  
CONSTRUCTION  
STATION




FOLDOUT FRAME

GENERAL ARRANGEMENT  
NO 2 CONSTRUCTION STATION  
SCALE: 1/80

6

5

4



3

2

1

REVISIONS		
NO.	DESCRIPTION	DATE
1	SEE SHEET 2 FOR DESIGN CHANGES MADE AS A RESULT OF THE ERB BRIEFING ENTITLED "SETTING UP NO2 WORK STATION EVA VS NON EVA" DATED 1 NOV 1979	2 NOV 1979 R J HART

BEAM BUILDER

9 FOLDOUT FRAME

42662-52

A-15,  
A-16

DRAWN BY R HART OCT 79 CHECK BY APPROVED BY			Rockwell International Corporation Space Division 12814 Lakewood Boulevard - Downey, California 90241		
			NO 2 CONSTRUCTION STATION		
			APPLICATIONS TECHNOLOGY PLATFORM		
SIZE		CODE IDENT NO.	DRAWING NO.		
L		03953	42662 - 52		
SCALE NOTED			SHEET 1 OF 2		

DESIGN CHANGES 2ND ITERATION

Y FRAME

STRUT DELETED.

ADDED INTEGRAL LEG.

Y FRAME SUPPORTED ON ORBITER LONGERONS  
AT 3 POINTS USING PAYLOAD RETENTION LATCHES:

RH @ X<sub>0</sub> 25733 FIXED IN XYZ AXES.

RH @ X<sub>0</sub> 28133 FIXED IN Y&Z, FLOATING IN X AXIS.

LH @ X<sub>0</sub> 25733 FIXED IN Z, FLOATING X & Y AXES.

- ① BEAM BUILDER ATTACHED TO Y FRAME AT 3 POINTS  
WITH REMOTE CONTROL SELF ALIGNING LATCHES.


REMOTE CONTROL ELECTRICAL CONNECTIONS (SIMILAR TO  
PAYLOAD INTERFACE) BETWEEN:

② LONGERON & Y FRAME.

③ Y FRAME & BEAM BUILDER.

④ Y FRAME & REEL ASSY.

ADDED EVA WORK STATIONS AT POSITIONS SHOWN  
WITH TRANSFER HANDRAILS IN BETWEEN.



REEL ASSY

REPOSITIONED THE CABLE REEL.

REEL ASSY FRAME SUPPORTED AT  
TWO MOUNTING POINTS:

LH LONGERON @ X<sub>0</sub> 27013 USING A PAYLOAD RETENTION  
LATCH FIXED IN Z FLOATING IN X&Y AXES.

FIXED TO Y FRAME @ Y<sub>0</sub> 2387 X<sub>0</sub> 25933  
WITH REMOTE CONTROL LATCH.

CABLE REEL FOLDS FOR STOWAGE IN ORBITER.

ADDED EVA WORK STATION

| FOLDOUT FRAME

# BES 2ND ITERATION

ED.

LEG.

PORTED ON ORBITER LONGERONS  
USING PAYLOAD RETENTION LATCHES:

5733 FIXED IN XYZ AXES.

28133 FIXED IN Y&Z, FLOATING IN X AXIS.

5733 FIXED IN Z, FLOATING X & Y AXES.

ATTACHED TO Y FRAME AT 3 POINTS  
CONTROL SELF ALIGNING LATCHES.

OL ELECTRICAL CONNECTIONS (SIMILAR TO  
FACE) BETWEEN:

ION & Y FRAME.

BE & BEAM BUILDER.

BE & REEL ASSY.

WORK STATIONS AT POSITIONS SHOWN  
HANDRAILS IN BETWEEN.

THE CABLE REEL.

AME SUPPORTED AT  
POINTS:


ON @ Xo 27013 USING A PAYLOAD RETENTION  
ED IN Z FLOATING IN X&Y AXES.

Y FRAME @ Yo 2387 Xo 25933

NOTE CONTROL LATCH.

FOLDS FOR STOWAGE IN ORBITER.

ORK STATION





VIEWS SHOWING CHA

Y FRAME

SCALE: 1/40




2 FOLDOUT FRAME



VIEWS SHOWING CHANGES TO  
Y FRAME  
SCALE: 1/40

3 FOLDOUT FRAME





VIEW SHOWING CHANGES TO REEL ASSY & FRAME

SCALE: 1/40.

SHOWING CHANGES TO Y FRAME

SCALE:

*4 FOLDOUT FRAME*

DR BY	R. HART	ACQ TO
CHK BY		
APPROVED BY		


3

2

1

REVISIONS				DATE	APPROVED
NO	DATE	DESCRIPTION			

Y FRAME


CABLE  
REEL  
FOLDS

VIEW SHOWING CHANGES TO  
REEL ASSY & FRAME

SCALE: 1/40.


5  
**FOLDOUT FRAME**A-17,  
A-18

R. HART		NCL 75		Rockwell International Corporation Space Division 12214 Lakewood Boulevard • Downey, California 90241	
CHK BY	APPROVED BY	NO 2 CONSTRUCTION STATION			
		ENG TECH & VERIFICATION PLATFORM			
SIZE	CODE IDENT NO.	DRAWING NO.			
L	03953	42662 52			
SCALE NOTED		SHEET 2 OF 2			




BEAM BUILDER REF

11) REF




2 FOLDOUT FRAME

SECTION C-C



SECTION B-B



X. 65993

MMU FLIGHT SUPPORT STATION

X. 576

582

BERTHING PLATFORM

AIRLOCK REF

2,400

008

FOLDOUT


X. 65993



FOLDOUT FRAME

RETURN FLIGHT


400

5









ING FIXTURE

E TARGET (TYP)

TIONER

**FOLDOUT FRAME**


MMU STOWING STATION

DIAGONAL CORD REELS (TYP)

WIRE HARNESS REEL (LONGITUDINAL BEAM)

BEAM BUILDER

C      D



1307

1302

WIRE HARNESS REEL  
(CROSS BEAM)

INTERSECTION FITTINGS &  
DEPLOYMENT CANISTER

1072.93

1175.20

C


D

ATTACH PORT INSTALLATION  
& SUPPORT ASSY

ATTACH PORTS

# CARGO MANIFEST

1. BUILDING FIXTURE
2. BEAM BUILDER
3. MMU FLIGHT SUPPORT STATION
4. EVA WORK STATION
5. BEAM POSITIONER
6. ATTACH PORTS (28)
7. WIRE HARNESS REEL (LONGITUDINAL)
8. WIRE HARNESS REEL (CROSS BEAM)
9. ATTACH PORT INSTALLATION
10. BERTHING PLATFORM
11. INTERSECTION FITTINGS & DEPLOYMENT CANISTER
12. DIAGONAL CORD REELS
13. MMU STOWING STATION



FOLDOUT FRAME

E HARNESS REEL  
(CROSS BEAM)

INTERSECTION FITTINGS &  
DEPLOYMENT CANISTER

MANIFEST

RE

SUPPORT STATION (2)

ATION

ER

(28)

BEEL (LONGITUDINAL BEAM)

BEEL (CROSS BEAM)

INSTALLATION & SUPPORT ASSY

TFORM

FITTINGS & DEPLOYMENT CANISTER

BEELS

STATION

9. WITHOUT FRAME

A-19,  
A-20



DATE 1/40	REVISED 1/1/80	Rockwell International	REVISIONS RESPANU
SHUTTLE BAY PACKAGING - INITIAL FLIGHT			42662-53 REV. A

MMU UNIT BACKS-IN  
& 'DOCKS' TO  
LEADING EDGE OF  
WORK STATION N°1

BEAM POSITIONER  
(REF.)

MMU PARK & EVA W

1  
FOLDOUT FRAME






AFTER THE MMU UNIT IS ATTACHED, THE EVA WORK STATION IS "SIGNALLED" TO A PRE-DETERMINED POSITION, WHERE THE ASTRONAUT EXTENDS HIS LEGS TO THE FOOT RESTRAINT PLATFORM. WHEN SECURE THE ASTRONAUT RELEASES HIMSELF FROM THE MMU UNIT & IS READY TO PROCEED TO HIS OPERATION ZONE.

PROCEDURE REVERSED FOR RETURN.

MMU PARK & EVA WORK STATION PICK-UP


2 FOLDBOUT FRAME






### EVA STATION POSITIONS & PROCEDURES

- A ELECTRICAL LINE HOOK-UP**
- A1 RELEASE PIGTAILS FROM CROSS BEAM.
  - A2 RELEASE PIGTAILS FROM LONGITUDINAL BEAM.
  - A1/A2 MAKE ALL ELECT. CONNECTIONS & RE-SECURE LOOSE LINES.
- B DIAGONAL CORD DEPLOYMENT (TYPICAL 3 PLACES)**
- B1 TRANSFER DIAGONAL CORD FROM BASE BEAM TO APEX BEAM.
  - B2 TRANSFER DIAGONAL CORD FROM APEX BEAM TO BASE BEAM.
- C REMOVAL OF CORD FROM REELS (TYPICAL 3 PLACES)**
- C1 REMOVE CORD FROM REEL & MAKE INITIAL ATTACHMENT TO EAR ON SIDE OF LONGITUDINAL BEAM.
  - C2 ROTATE & REPEAT OPERATION FOR OTHER SIDE OF LONGITUDINAL BEAM.
- D DIAGONAL CORD ATTACHMENT (TYPICAL 3 PLACES)**
- D1 ATTACH CORD TO TRAILING EAR, RELEASE TETHER & ROTATE TO ADJACENT BEAM AS IN B.
  - D2 ATTACH CORD TO LEADING EAR.
  - D3 ATTACH CORD TO TRAILING EAR, RELEASE TETHER & ROTATE TO ADJACENT BEAM AS IN B.
  - D4 ATTACH CORD TO LEADING EAR.
- E BEAM POSITIONER**
- SHOWN IN POSITION FOR ASSEMBLING CROSS BEAM.
  - AFTER BEAM ASSEMBLY OPERATIONS ARE COMPLETE, BEAM POSITIONER IS TO BE RETRACTED TO PLANE IN WHICH EVA FUNCTIONS ARE PERFORMED.







ORIGINAL PAGE IS  
OF POOR QUALITY

6  
FOLDOUT PAGE


### EVA FUNCTIONS

- EVA OBSERVATION GUIDANCE TO RMS FOR BEAM HANDLING.
- ALIGN BEAM POSITIONER FOR BEAM PICK-UP, VIA. RMS DELIVERY.
- SUPERVISE TRANSVERSE & CROSS BEAM ASSEMBLIES.
- APPLY ELECTRODES TO SELF WELDING INTERSECTION FITTINGS.
- VERIFICATION OF STRUCTURAL INTEGRITY VIA. CONTROL OF BEAM POSITIONER.
- TRANSLATE DIAGONAL CORDS BETWEEN LONGITUDINAL BEAMS.
- CONNECT TENSION CORDS TO INTERSECTION FITTINGS EARS.
- CHECK STRUCTURAL ALIGNMENT & TENSION DIAGONAL CORDS.
- RELEASE ELECT. PIG TAILS FROM LONGITUDINAL & CROSS BEAMS.
- MAKE ELECTRICAL CONNECTIONS & RE-SECURE LINES.

L BASE BEAM

BEAM



ER  
NING ARM)




ORIGINAL PAGE IS  
OF POOR QUALITY


EVA WORK STATION

1 FOLDOUT FRAME




BASIC CHERRY PICKER CONFIGURATION COMPLETE WITH ASTRONAUT, AS ADAPTED FOR USE WITH WORK STATION N°1






ETE WITH  
ATION N°1



OPEN CHERRY PICKER DEVELOPMENT TEST ARTICLE  
'AS IS' CONFIGURATION




ORIGINAL PAGE IS  
OF POOR QUALITY

9 FOLDOUT FRAME

A-21,  
A-22

SCALE 1/20	DR. HUGH DATE 10/21/79 BY ELSA	ROCKWELL INTERNATIONAL CORPORATION SPACE DIVISION 12344 LAKESIDE DR., TOLSON, CALIFORNIA	
EVA WORK STATION			42662-55



### DETAIL OF CABLE CLIP


SCALE: FULL SIZE

- RELATIVE EXPANSION CONTRACTION BETWEEN ELECTRIC CABLE & STRUCTURE OVER  $\pm 100^{\circ}\text{F}$ .
- DISTANCE BETWEEN CLIPS = 1.434 M.
- STRUCTURE ASSUMED TO HAVE ZERO EXPANSION.
- CABLE (COPPER) HAS  $\pm 1.32\text{mm}$  EXPANSION BETWEEN CLIPS.
- PROVIDE SLACK IN CABLE TO ACCOMMODATE  $\pm 1.32\text{mm}$ .
- DESIGN THE CABLE CLIP AS SHOWN TO INDUCE A CURVE IN THE CABLE TO PROVIDE THE NECESSARY SLACK.

### FOLDOUT FRAME

### SEQUENCE OF EVENTS FOR TO PAYLOAD


PAYLOAD INTERFACE CONNECTOR



- THE BEAM IS HALTED
- THE XBEAM CABLE CONNECTOR IS IN THE BANDOLIER & OPPOSITE THE PAYLOAD INTERFACE CONNECTOR
- THE GRASPER HAS GRASPED THE XBEAM CABLE CONNECTOR

- THE GRASPER STRIPS THE XBEAM CABLE CONNECTOR FROM THE BANDOLIER

- THE GRASPER THE XBEAM CABLE CONNECTOR TO PAYLOAD INTERFACE CONNECTOR



CABLE CLIP  
FULL SIZE

BETWEEN ELECTRIC CABLE

434 M.

VE ZERO EXPANSION.  
M EXPANSION BETWEEN CLIPS.  
ACCOMMODATE  $\pm 1.32$  MM.  
SHOWN TO INDUCE A CURVE  
THE NECESSARY SLACK.


ORIGINAL PAGE IS  
OF POOR QUALITY

2  
FOLDOUT FRAME


SEQUENCE OF EVENTS FOR MATING CROSSBEAM CABLE CONNECTORS  
TO PAYLOAD INTERFACE CONNECTORS

CTOR ON  
ND OF THE  
BEAM CABLE


R" ON THE END  
INSTALLATION ARM



- THE GRASPER STRIPS THE X-BEAM CABLE CONNECTOR FROM THE BANDOLIER




- THE GRASPER MATES THE X-BEAM CABLE CONNECTOR TO THE PAYLOAD INTERFACE CONNECTOR



- THE GATE ON THE GRASPER OPENS. THE GRASPER RETREATS




- THE GRASPER RETREATS THE PAYLOAD CABLE





3  
FOLDOUT FRAME

LOWER  
JAW





- ① • BEAM H  
(GTD)  
• CLIP IS  
• REEL  
• LOWER

42662-56



FOLDOUT FRAME

DIRECTION OF BEAM  
& CABLE FEED





- ① • BEAM HALTS FOR 40 SECS.  
(STD BEAM BUILDER SEQUENCING)
- CLIP IS ALIGNED WITH CROSSMEMBER
  - REEL FEED IS HALTED
  - LOWER JAW BEGINS TO EXTEND

- ② • LOWER JAW IS FULLY EXTENDED
- LOWER & UPPER JAWS BEGIN TO ROTATE

SEQUENCE OF EVENTS



SCALE :





ORIGINAL PAGE IS  
OF POOR QUALITY

5 FOLDOUT FRAME



JS FULLY EXTENDED  
PPER JAWS BEGIN

- ③ • LOWER & UPPER JAWS  
ARE FULLY ROTATED  
• JAWS BEGIN TO SQUEEZE

- ④ • JAWS ARE SQUEEZED &  
CLIP IS INSTALLED ON


- ⑤ • REVERSE ①②③④ TO C  
THE CYCLE

SEQUENCE OF EVENTS FOR CLIP INSTALLATION

SCALE : 1/2

ORIGINAL PAGE IS  
OF POOR QUALITY

FOLDOUT FRAME



ON CROSSMEMBER

COMPLETE

42662-56

FIXED S

DATA CABLE

POWER CABLE

OPTICAL SENSING  
DEVICES TO ALIGN  
CLIP WITH CROSSMEMBER

60

60

DRUM MOVEMENT

7 FOLDOUT FRAME

CLIP  
INSTLN  
STATION

BANDOLIER

CABLE CLIP  
INSTALLED

50lbs


SLACK IN CABLE  
FOR EXPANSION/CONTRACTION

HINGE POINT

ASSEMBLY FOLDS  
FOR STORAGE

GEN ARRG'T

SCALE: 1/10



ORIGINAL PAGE IS  
OF POOR QUALITY

9 FOLDOUT FRAME

REFERENCE DWGS

42662-52 No 2 CONSTRUCTION STATION  
42662-61 WIRING DWG

OR BY	R. HART	NOV 2	Received into National Communications Source Division 1015 Columbia Road, S.W. Washington, D.C. 20003
CHK BY			
APPROVED BY			ELECTRIC CABLE LAYING MACHINE, CROSSLAM E.T.V.P.
			SERIAL IDENT NO.      Drawing NO. 03953      42662-56
			SCALE NOTED

A23  
A24

CONTROL MODULE  
SUPPORT STRUCTURE

WIRE TRAY (STORED POS.)

PLATFORM LONGITUDINAL  
BEAMS

WIRE TRAY - PARTIALLY  
FOLDED TO CLEAR  
SUPPORT STENTS DURING  
PLATFORM ATTACH OPERATION

LATCH MECHANISM  
(WIRE TRAY TO PLATFORM BEAM)

WIRE TRAY H<sub>2</sub>

60 (1.5 M)

80 (2.03 M)


WIRE LEADS TO WIRE TRAY

SUPPORT STENT  
ATTACH FITTINGS 3 FE.

57 (1.45 M)

WIRE TRAY INSTALL CONFIG

FOLDOUT FRAME



WIRE TRAY INSTALL CONFIG

2 FOLDOUT FRAME

42662-57

STRUT ATTACH FITTINGS 3 R.

CONTROL MODULE

CONTROL MODULE  
STRUCTURE ASSY.

RADIATOR PANEL HINGE LINE

19 (4.8 M)

120 (3.05 M)

120 (3.05 M)

115 (2.92 M)

STOWED POS.

HINGE AXIS

RADIATOR PANELS 4 REQD

95.83 FT<sup>2</sup>/PANEL (8.90 M<sup>2</sup>)

TOTAL (4 PANELS)

383.3 FT<sup>2</sup> (35.61 M<sup>2</sup>)

3.0 (7.62 CM)

BATTERY  
MODULE

BATTERY MODULE  
3 PER SIDE (REF)

MECHANICAL  
WRIST ASSY.

CONTROL MODULE - RADIATOR PANEL(S) CONFIG

3

EXPLODED FRAME



13

12

11

NA

200

187 (2.718 M)

WIRE CONDUCTOR LEADS  
TO INTERFACE WITH WIRE

(3.05 M)

115 (2.98 M)

BATTERY  
MODULE

162 (REF)

TELEOPERATOR DOCKING  
PORT 3 R. (REF)

10 (REF)

BATTERY MODULE  
3 PER SIDE (REF)CONTROL MODULE  
STRUCTURE

187 (REF)

SECTION A-A

MODULE RESTRAINT

LATCH SCREW

MODULE SUPPORT BEAM

GUIDE TUBE

LATCH OPERATOR /  
MODULE GRAPPLESPECIAL PURPOSE END  
EFFECTOR

LIGHT

CCTV

MECHANICAL ARM  
WRIST ASSY.STANDARD END  
EFFECTOR

TARGET

UPPER FLOATING NUT

MODULE RESTRAINT

ELECTRICAL C  
INTERFACE AREA

ELECTRICAL CONN

LOWER FLOAT


CONTROL MODULE S  
MOUNTING INTERFA


MODULE ASSY

FOLDOUT FRAME

MODULE EXCHANGE SYSTEM







3


2

1

REVISIONS				
ZONE	LYR	DESCRIPTION	DATE	APPROVED

PLATE

LITTLE PAYLOAD ENVELOPE  
(80 IN DIA) 4.57 M.



CE AXIS

7 FOLDBOUT FRAME


A-25,  
A-26

DR BY <i>F. Thompson</i> 12-16-75		Rockwell International Corporation Space Division 12814 Lakewood Boulevard • Downey, California 90241	
CHK BY		CENTRAL MODULE ASSY- ENGINEERING & TECHNOLOGY VERIFICATION PLATFORM	
APPROVED BY			
SIZE	CODE IDENT NO.	DRAWING NO.	
L	03953	42662-57	
SCALE		SHEET	


42662-57

A

CONTROL MODULE





CONTROL MODULE



FOLDOUT FRAME



④ R<sub>1</sub>  
C<sub>6</sub>  
A<sub>7</sub>  
(R<sub>0</sub>  
AN<sub>1</sub>



- ④ ROTATE CONTROL MODULE WITH RMS AND ATTACH  
CONTROL MODULE TO TWO REMAINING BALL  
ATT. HOUSING.

(ROTATE CABLE TRAY TO OPERATING POSITION  
AND LATCH END OF CABLE TRAY TO FABRICATED BEAM)



2.  
FOLDOUT FRAME




- ③ CONTROL MODULE ATTACH WITH RMS TO ONE BALL  
END ATT. HOUSING OF STRUT ASSEMBLY INSTALLATION  
(ROTATE CABLE TRAY TO CLEAR STRUT ASSEMBLY  
INSTALLATION)

3  
FOLDOUT FRAME






STRUT ASSEMBLY  
(FOLDED)



- ② EXTENDED STRUT ASSEMBLY ATTACH WITH RMS  
TO REMAINING TWO BALL ATT. HOUSINGS


4.  
FOLDOUT FRAME

STRUT ASSEMBLY (FOLDED)




NOTE: ALL BALL END ATT. HOUSINGS TAKE LOAD ON "X" AXIS

ASSEMBLY  
(D)



① FOLDED STRUT ASSEMBLY ATTACH  
WITH RMS AT ONE BALL ATT. HOUSING


5 FOLDOUT FRAME



NOTE: ALL BALL END ATT. HOUSINGS WILL  
TAKE LOAD ON X" AXIS


6 FOLDOUT FRAME

SHT 1 OF 3  
A-27,  
A-28

SCALE 1:5	DATE	 Rockwell International	42662-59 1975
CL. 5	DATE		
FORWARD ASSEMBLY AND INSTALLATION			42662-59

C-5

2  
HINGE AND VISCOSE  
DAMPER




HINGE

SEC

SCALE


ORIGINAL PAGE IS  
OF POOR QUALITY

FOLDOUT FRAME



SECTION D-D

SCALE: 1/2




VIEW C-C

SCALE: 1/2

2 FOLDOUT FRAME


ORIGINAL PAGE IS  
OF POOR QUALITY



VIEW C-C

SCALE: 1/2

ORIGINAL PAGE IS  
OF POOR QUALITY



3 FOLDOUT FRAME

1 - SCALE: 1/2



SECTION B-B - SCALE: 1/2


HINGE AND VISCOSE DAMPER

HINGE AND VISCOSE  
DAMPER


HINGE AND VISCO  
DAMPER

ORIGINAL PAGE IS  
OF POOR QUALITY

SCALE: 1/2




HINGE AND VISCOSE DAMPER



STRUT DURING UNFOLDING

SCALE: 1/20




FOLDED STRUT ASSEMBLY

SCALE: 1/20

5 FOLDOUT FRAME


ORIGINAL PAGE IS  
OF POOR QUALITY





DURING UNFOLDING



1/20



PISTON ASSEMBLY

ORIGINAL PAGE IS  
OF POOR QUALITY

HINGE AND VISCOSE  
DAMPER - 3 PLACES





VIEW  
SCALE

HINGE AND VISCOSE  
DAMPER - 3 PLACES

BOLDOUT FRAME


6





VIEW E-E

SCALE: 1/20




SECTION F-F

SCALE: 1/20

ORIGINAL PAGE IS  
OF POOR QUALITY

HINGE AND VISCOSE  
DAMPER- 3 PLACES



3.25 M  
(128.0 IN)

E

F

DE

SC

2




HINGE AND

HOLDOUT FRAME

E

F


7



# DETAIL OF STRUT ASSEMBLY

SCALE: 1/20

2  
HINGE AND VISCOSE DAMPER- 3 PLACES




8 FOLDOUT FRAME


SCALE	NO.	
DATE	DATE	
MODEL	MODEL	

FORWARD A  
AND INSTALL

9 BOLT FRAME


SHT. 2 OF 3  
A-29,  
A-30

SCALE 1/80 UNITS	DATE 1/2	 Revell International	Model Number 1/80 1/80 1/80
FORWARD ASSEMBLY AND INSTALLATION			42662-59




CONSTRUCTION



/ FOLDOUT FRAME



SECTION G - G


FOLDOUT FRAME






FOLDOUT FRAME








TOTAL AREA BOTH SIDES  $75.25 \text{ M}^2$  (810  $\text{FT}^2$ )

6 REMOUNT FRAME

RMS  
(SERVICING CMG)

STRUT ASSEMBLY

CONTROL MODULE



8 FOLDOUT FRAME

SHT 3 OF 3

A-31,  
A-32

DURING SERVICING

SCALE 1/8"	DATE NOV 1971	Rockwell International	42662-59
FORWARD ASSEMBLY AND INSTALLATION			42662-59

00-5555-00

24

D

C

→

B

A

② LANYARD; PU  
RELEASE LA  
FOR ALL LA

GRASP POINT FOR RMS

②

②

THE ELEMENTS OF THE STRUCTURE  
ARE SECURED TOGETHER BY  
MECHANICAL LATCHES, THE RELEASE  
OF WHICH IS INITIATED MANUALLY  
BY AN EVA ASTRONAUT


CENTRAL FRAMES 7, 8 & 9 ARE  
DEPLOYED BY THE SPRING LOADED  
CYLINDERS SHOWN IN ZONE 11.

THE TWO OUTBOARD ENGINE TRUSSES  
ARE DEPLOYED BY THE ROTARY SPR  
DEVICES SHOWN IN ZONES 8A &


STRUTS 1 THRU 6 EQUIPPED WITH GRASP  
POINTS (NOT SHOWN) FOR RMS, &  
NEAR THE FREE END OF EACH STRUT

FOLDOUT FRAME

ALL AS SHOWN TO  
 EACH TYPICAL  
 FICHES.




OUTLINE OF CARGO BAY



ORIGINAL PAGE IS  
 OF POOR QUALITY  
 2 MOLDOUT FRAME

THRUST STRUCTURE IN STOW


SCALE : 1/20





STRUCTURE IN STOWED CONFIGURATION

SCALE : 1/20

3  
FOLDOUT FRAME



BOLDOUT FRAME



ENGINE MODULE ATTACH PORT

NO SCALE


42662-60



15


14

13




OUTBOARD ENGINE TRUSS

SCALE: 1/20

ELECTRICAL  
INTERFACE  
42662-61



SCALE



PROJECTION SHOWING THE 3 CENTRAL  
FRAMES IN THE STOWED POSITION,  
JOINED TOGETHER AT THEIR FWD ENDS  
BY A LATCH SYSTEM. FOR DEPLOYMENT  
THE LATCHES ARE RELEASED INDIVIDUALLY.


5. **BOLDOUT FRAME**

APEX LONGITUDINAL



CE

CAPEX LONGITUDINAL



CENTRAL  
FRAME (3 PLACES)

DEPLOYED  
STOWED

CYLINDER (3 PLACES)

1. RETAINS FRAME IN STOWED POSITION
2. DEPLOYS FRAME BY SPRING ENERGY WHEN THE LATCH AT THE FWD END IS RELEASED. SPEED OF DEPLOYMENT IS GOVERNED BY A DASH POT

ENGINE  
MODULE

SECTION AA  
CENTRAL FRAME

CENTER ENGINE MOUNT **BOLDOUT FRAME**

SCALE = 1/20

10

9


8

ENGINE  
MODULE

BOLDOUT FRAME

BOLDOUT FR


42662 -60


CENTRAL  
FRAME 7EVA ASTRONAUT UNCLIPS  
PIGTAIL FROM CENTRAL FRAME 8  
& CONNECTS TO RECEPTACLE ON  
APEX LONGITUDINALCENTRAL  
FRAME 8

APEX LONGITUDINAL

CENTRAL  
FRAME 9

3M





3

2

1

REVISIONS			
ZONE	LTR	DESCRIPTION	DATE
			APPROVED

5.0M

VIEW FROM AFT END  
LOOKING FWD  
 SCALE : 1/20

REFERENCE DWGS

42662-45 GEN ARRGT OF PLATFORM.  
 42662-63 STRUCTURAL/MECHANICAL LATCH  
 FOR PAYLOAD.  
 42662-61 PAYLOAD INTERFACE CONNECTOR (ELECTRIC).  
 42662-72 MODULE ATTACH PORTS.

5.0M


10  
 BOLDOUT FRAME

A-33,  
 A-34


DR BY		R. HART		JAN 5	
CHK BY					
APPROVED BY					
SIZE		CODE/IDENT NO.		DRAWING NO.	
L		03953		42662-60	
SCALE NOTED				SHEET	

Rockwell International Corporation  
 Space Division  
 18214 Lebrand Boulevard • Downey, California 90241



INTERORBITAL THRUST STRUCTURE  
 ENGINEERING TECHNOLOGY  
 VERIFICATION PLATFORM.





**BOLDOUT FRAME**










ORIGINAL PAGE IS OF POOR QUALITY

4 BOLDOUT FRAME



VIEW SHOWING LOCATION  
OF PAYLOAD INTERFACE  
CONNECTOR ON END PORT  
NO SCALE

REVISIONS			
NO.	DATE	DESCRIPTION	APPROVED


A FUNCTIONALLY SIMILAR INTERFACE MAY BE USED FOR

BEAM BUILDER TO SUPPORT TRIPOD	}	DWG 42662-50
SUPPORT TRIPOD TO NO1 CONSTRUCTION FIXTURE		SHEET 4 ZONE 95
BEAM BUILDER TO Y FRAME	}	DWG 42662-52
CABLE REEL ASSY FRAME TO Y FRAME		SHEET 2 ZONE 8
ORBITER TO Y FRAME		

5. BOLDOUT FRAME

A-35,  
A-36

DR BY: R. HART		Resinell International Corporation Space Division 17214 Lakeside Dr., Hayward, California 94611	
CHK BY:		LOAD INTERFACE CONNECTOR (ELECTRIC) E.T.V.P.	
APPROVED BY:		L 03953 42662-61	
SCALE:		SHEET	



PAYLOAD SIDE OF INTERFACE

HOLDOUT FRAME

GE  
DR  
UN


GEARHEAD  
DRIVE  
UNIT

✕ ECCENTRIC GENEVA  
DRIVE ROTATION


ORIGINAL PAGE IS  
2 OF POOR QUALITY  
FOLDOUT FRAME

CROSSBEAM SIDE OF  
INTERFACE

42662-63



ORIGINAL PAGE IS  
OF POOR QUALITY




GENEVA  
ATION

CROSSBEAM SIDE OF  
INTERFACE

3 **HOLDOUT FRAME**

A FUNCTIONALLY SIMILAR LATCH  
BEAM BUILDER TO SUPPO  
SUPPORT TRIPOD TO NO 1  
BEAM BUILDER TO Y F  
CABLE REEL ASSY FRAME TO



4 **BOLDOUT FRAME**

3

2

1

REVISIONS				
ZONE	LTR	DESCRIPTION	DATE	APPROVED

D

2 LATCH IS USED FOR

3 SUPPORT TRIPOD

TO NO 1 CONSTRUCTION FIXTURE } DWG 42662-50  
SHEET 4 ZONE 96

TO Y FRAME

FRAME TO Y FRAME

} DWG 42662-52

} SHEET 2 ZONE 8

C

←

B

**5 HOLDOUT FRAME**

A-37,  
A-38

A




DR BY <b>R J HART</b> PEG 77 CHK BY			<b>Rockwell International Corporation</b> Space Division 12214 Lakeside Boulevard • Downey, California 90241		
APPROVED BY			STRUCTURAL MECHANICAL		
			LATCH FOR PAYLOAD		
			ETVP		
SIZE		CODE IDENT NO	DRAWING NO.		
L		03953	42662-63		
SCALE FULL				SHEET	

3

2

1






BOLDOUT FRAME

# SYMBOL IDENTIFICATION

- ① MECHANICAL LATCH & ALIGNMENT BETWEEN BEAM BUILDER AND SUPPORT TRIPOD (FORWARD)
- ② MECHANICAL LATCH & ALIGNMENT BETWEEN BEAM BUILDER AND SUPPORT TRIPOD (AFT)
- ③ ELECTRICAL INTERFACE CONNECTION BETWEEN BEAM BUILDER AND SUPPORT TRIPOD



42662-64

LOCATION

ALIGNMENT BETWEEN  
PORT TRIPOD (FORWARD)

ALIGNMENT BETWEEN  
PORT TRIPOD (AFT)

CONNECTION BETWEEN  
PORT TRIPOD

ATTACHMENT PORT  
POSITIONER MECHANISM

BEAM FABRICATION

BEAM BUILDER


(FAR SIDE)


SEPARATION PLANE BETWEEN


ATTACHMENT PORT  
MAGAZINE

BOLDOUT FRAME

CONST. FIXTURE CROSS BEAM  
SWING ARM







BUILDER

REVISIONS				
DATE	BY	DESCRIPTION	DATE	APPROVED

D

C

B

A

42662-64

A

6 FOLDOUT FRAME


A-39,  
A-40

DR BY <i>F. Hagan</i> CHK BY		Reston International Corporation Space Division 12214 Lakeside Boulevard • Downey, California 90241	
APPROVED BY		MODIFICATION TO BEAM BUILDER - ETVP	
SIZE	CODE IDENT NO.	DRAWING NO.	
L	03953	42662-64	
SCALE		SHEET	

ACS


AN1

END  
WITH  
READ



BOLDOUT FRAME

LONGITUDINAL BEAM  
- PLATFORM




BRACING STRUTS AT  
PLATFORM ENDS (REF.)

8.5M

END EFFECTOR  
(STABILIZER) DETAIL

ORIGINAL PAGE IS  
OF POOR QUALITY




SEE SECTION C-C  
FOR TRUE VIEW

RMS SHOWN IN  
ASSEMBLY POS  
FOR RCS MODULE


RCS MODULE ASSEMBLY

SCALE: 1/40


FOLDOUT FRAME







ORIGINAL PAGE IS  
OF POOR QUALITY



WED  
ADLE


13

(RMS)  
P. 0°



FOLDOUT FRAME

ORIGINAL PAGE IS  
OF POOR QUALITY


- ④ ROTATE STABILIZER ARM  
120° & PROCEED TO  
RCS MODULE ASSEMBLY POSITION



- ③ ROTATE ROTARY JOINT IN UPPER ARM  
180° C.W. & WRIST 180° C.C.W.,  
ALSO ROTATE STABILIZER END EFFECTOR  
TOWARDS ASSEMBLY ORIENTATION  
FOR RCS MODULE.



- ② ALIGN UPPER & LOWER ARMS OF RMS





- ① ROTATE LOWER ARM  
OF RMS 'UP' 30°.

SECTION 13-13


RCS MODULE REMOVAL


SCALE: 1/40



# RELATIONSHIP OF ORBITER TO PLATFORM FOR

NOTE: ITEMS 1 & 2 REQUIRED FOR OF RCS MODULES N°3 & N°4. ITEMS 3 & 4 RETURNS ORBIT TO THE SYSTEMS MODULE END NEXT (CHECK-OUT) PROCEDURE





# RELATIONSHIP OF ORBITER TO PLATFORM FOR RCS MODULE ATTACHMENT


NOTE: ITEMS [1] & [2] REQUIRED FOR ASSEMBLY OF RCS MODULES N°3 & N°4.

ITEMS [3] & [4] RETURNS ORBITER BACK TO THE SYSTEMS MODULE END FOR THE NEXT (CHECK-OUT) PROCEDURE.


FOLDOUT FRAME

A-41,  
A-42

DATE 1/80 BY BUCK DATE 1/21/80 MODEL 305A	Rockwell International Space Division Group 17901 Lancaster Avenue Canoga Park, CA 91301	
RCS MODULE INSTALLATION VIA, CHERRY PICKER		42662-65



### RMS / CHERRY PICKER ASSEMBLY



**WELDOUT FRAME**

**DETAIL H**

IN  
PAGE  
MO

ND EFFECTOR  
(TABILIZER) DETAIL

IZER  
Y PICKER

KER - BASE

YS

Y  
R


RMS



SOLAR ARRAY ASSEMBLY (CLOSED) - REF

PLATFORM SYSTEMS CHECK - OUT UNIT

POWER CABLE UMBILICAL STORAGE REEL

2 FOLDOUT FRAME






PAYLOAD SUPPORT STRUCTURE  
(THRUST STRUCTURE)


X69

Y09




SECTION G-G


3 FOLDOUT FRAME




SECTION D-D



SECTION F-F







SECTION G-G





SECTION F-F

**BOLDOUT FRAME**







6 FOLDOUT FRAME

CHERRY PICKER  
CONTROL MODULE

Z. 414.0  
Z. 400.0

PAYLOAD ENVELOPE

PAYLOAD SUPPORT STRUCTURE  
(THRUST STRUCTURE)

X-BEAM BRACE STRUT CANISTER DEPLOYED

THRUST STRUCTURE  
FOLDED

PIVOT POINT OF CANISTER

X-BEAM BRACE STRUT  
CANISTER

SUPPORT STRUCTURE OF FWD ASSEMBLY  
FOLDED

Z. 400.0


### SECTION A-A

Z. 414.0

Z. 400.0

### SECTION

ASSEMBLY - FOLDED



Z. 400.0

CONTROL MODULE

CHERRY PICKER

WIRE TRAY FOLDED

Y. 94.0

Y. 94.0

CONTROL MODULE SUPPORT  
IN ORBITER PAYLOAD BAY

Z. 414.0

Z. 400.0

### SECTION C-C

↑ FOLDOUT FRAME

THRUSTR OF FWD. ASSEMBLY  
POINT OF CANISTER


BRACE STRUT CANISTER DEPLOYED

THRUST STRUCTURE  
FOLDED


POINT OF CANISTER

BRACE STRUT

THRUSTR OF FWD. ASSEMBLY



## SECTION B-B



ORIGINAL PAGE IS  
OF POOR QUALITY

## SECTION C-C

A-43,  
A-44

BOLDOUT FRAME

SCALE 1/10	DATE 11/11/81	Rockwell International	SHUTTLE BAY PACKAGING - SECOND FLIGHT	42662-67
---------------	------------------	---------------------------	--	----------

Xo

BERTHING PLATFORM

ORIGINAL PA IS  
OF POOR QUALITY

Xo5

RES

AVAILA

Xo

Zo 414.0

Xo 236.0


Xo

BOLDOUT FRAME

BERTHING PLATFORM









### SECTION A-A

HOLDING FIXTURE OMITTED FOR CLARITY



### SECTION B-B


HOLDING FIXTURE OMITTED FOR CLARITY



### SECTION C-C


ORIGINAL PAGE IS  
OF POOR QUALITY

FOLDOUT FRAME



### SECTION B-B

HOLDING FIXTURE OMITTED FOR CLARITY




### SECTION C-C

FOLDOUT FRAME

ORIGINAL PAGE IS  
OF POOR QUALITY

SHT 1 OF 3

A-45,  
A-46

 Rockwell International	Shuttle Bay Packaging Third Flight	42662-68
---	---------------------------------------	----------

3.7M SCAN-PHASED ARRAY -  
ANTENNA (1REQD)

BERTHING PLATFORM

3.7M SCAN-PHASED ARRAY -  
ANTENNA (1REQD)

Zo 414.0


FOLDOUT FRAME

ORIGINAL PAGE IS  
OF POOR QUALITY

Xo 236.0

BERTHING PLATFORM





1302.0

RCS MODULES (REF)

SUPPORT STRUCTURE  
IN PAYLOAD BAY

ORIGINAL PAGE IS  
OF POOR QUALITY

1307.0

281.40

LEAVED ANTENNA  
(2 REQD)

1302.0

281.40

1307.0

4M INTERLEAVED ANTENNA (2REQD)

ANTENNA (1REQD)

RCS MODULES (REF)

7.5M INTERLEAVED ANTENNA (2REQD)

3 FOLDOUT FRAME

2.414.0

7.5M INTERLEAVED FEED  
ANTENNA

REFLECTOR

CHECK-OUT PLATFORM  
SYSTEM

PAYLOAD ENVELOPE

SUPPORT STRUCTURE  
IN PAYLOAD BAY

FEED HORN

Z. 400.0

Y. 94.0

Y. 94.0

Y. 94.0

Y. 94.0

SECTION D-D

Z. 414.0

Y. 94.0

FEED HORN


SUPPORT STRUCTURE  
IN PAYLOAD BAY

Y. 94.0

Z. 400.0

SECTION






ON D-D

SECTION E-E

ORIGINAL PAGE IS  
OF POOR QUALITY




SECTION F-F

SHT 2  
A-47, A

4 FOLDOUT FRAME

SCALE 1/80	DATE 10/1/80	Rockwell International Space Systems Group 1911 International Boulevard Canoga Park, CA 91307	
SHUTTLE BAY PACKAGING - THIRD FLIGHT			4266



ORIGINAL PAGE IS  
OF POOR QUALITY

ON E-E

7.5M INTERLEAVE ANTENNA

PAYLOAD ENVELOPE

REFLECTOR

5 FOLDOUT FRAME


SHT 2 OF 3  
A-47, A-48

180	DATE 1/1/83	Rockwell International	Space Systems Group 2225 Leland Avenue Cost Mesa, CA 92626
SHUTTLE BAY PACKAGING - THIRD FLIGHT			42662-68



ORIGINAL PAGE IS  
OF POOR QUALITY

BERTHING PLATFORM



Zo 414.0

Xo 236.0

Xo 576.0

Xo 659.93

Xo 679.50

Xo 829.07

Xo 994.0

Xo 1074.0

Xo 1061.13

Xo 848.73

Xo 770.0


Xo 1112.0

Xo 1112.0


FOLDOUT FRAME

BERTHING PLATFORM

60 M




ORIGINAL PAGE IS  
OF POOR QUALITY




**FOLDOUT FRAME**


RCS MODULES (REF)



SECTION G-G




SECTION J-J



ORIGINAL PAGE IS  
OF POOR QUALITY

$Z_0 400.0$

RCS MODULES (REF)




SECTION J-J

3 FOLDOUT FRAME


FOLDOUT FRAME





SECTION H-H

ORIGINAL PAGE IS  
OF POOR QUALITY



SECTION J-J



FOLDOUT FRAME

SHT 3 OF 3  
A-49, A-50



SCALE 1/80	DATE 1/80	BY [Signature]	APPROVED [Signature]	REVISION [Signature]
SHUTTLE BAY PACKAGING - THIRD FLIGHT				42662-68



ORIGINAL PAGE IS  
OF POOR QUALITY




ORIGINAL PAGE IS  
OF POOR QUALITY




STRUT (TRAILING END) ASSEMBLY PROCEDURE  
VIA ASTRONAUT  
2 FOLDOUT FRAME



ORIGINAL PAGE IS  
OF POOR QUALITY




LENGTH ADJUSTMENT PRIOR TO ASSEMBLY  
OF STRUT END - VIA ASTRONAUT



ASSEMBLY PROCEDURE





ORIGINAL PAGE IS  
OF POOR QUALITY

CONTROL SYSTEMS MODULE

1  
1ST PLATFORM  
TRANSLATION

STRUTS (1 PAIR) IN  
ASSEMBLED POSITION

ASSEMBLY OF OPPOSING  
STRUTS NOT SHOWN IN THIS  
OPERATIONAL SEQUENCE.

ROTATE  
ORBITER  
180°

13

THRUST (AFT) STRUCTURE

2  
2ND PLATFORM  
TRANSLATION

PLATFORM - DWG 42662-45A

RELATIONSHIP OF ORBITER TO PLATFORM FOR STRUT ATTACHMENT AS DEPICTED

EACH PORT  
END OF ALL  
SHORT & LONG  
TRANSVERSE BEAMS

1ST (UPPER) STRUT ATTACHED AS SHOWN  
IN OPERATIONAL SEQUENCE.


2ND (LOWER) STRUT ATTACHED IN  
SAME SEQUENCE AS UPPER STRUT.

DETAIL 13

ASSEMBLY OF STRUTS (1 PAIR)  
TO ATTACH PORT (TYPICAL)

STRUT ATTACHED

STRUT END IN APPROX POSITION  
READY FOR THE FINAL ATTACHMENT  
OF THE 1ST STRUT.



SECTION A - A


5 HOLDOUT FRAME

E  
ER

ST (AFT) STRUCTURE

FORMATION  
ATION

APPROX POSITION  
E FINAL ATTACHMENT  
UT.



STRUT REMOVAL TO 1ST ATTACHMENT PROCEEDS

STRUT (LEADING END) ASSEMBLY ACCOMPLISHED  
VIA CHERRY PICKER

6 FOLDOUT FRAME

TRAILING STRUT END IN  
APPROX. POSITION READY  
FOR NEXT ASSEMBLY SEQUENCE

STRUT STORAGE CANNISTER  
IN DEPLOYED POSITION

② REMOVE STRUT FROM  
CANNISTER & CLEAR

① ENGAGE END OF STRUT  
IN STORAGE CANNISTER

③ ROTATE RMS WRIST,  
TURNING STRUT

⊗ STRUT IN APPROX.  
FINAL ASSEMBLY PLANE

④ ROTATE RMS SHOULDER  
MOVING STRUT FROM


⊗ TO ⊙

LOWER ARMS  
(WARD) TO  $Y_0$  AXIS

ENT PROCEEDURE.

ACCOMPLISHED


7 FOLDOUT FRAME



ASSEMBLY AS DEPICTED IN PRECEEDING

RMS/CHERRY PICKER A

**8 SPOUT FRAME**



ASSEMBLY AS DEPICTED IN PRECEEDING ILLUSTRATIONS.

**RMS/CHERRY PICKER ASSEMBLY**

ORIGINAL PAGE IS  
OF POOR QUALITY

A-51,  
A-52

1/80 3/5/14 SC 54	BUCK 3/5/14 SC 54	Rockwell International 17000 Rockwell Drive Torrance, CA 90504	
BRACING STRUT INSTALLATION VIA, CHERRY PICKER			42662-71 SHEET 1 OF 2





LONG C


ORIGINAL PAGE IS  
OF POOR QUALITY

CONSTRUC



STRUT  
IN DEP  
POSITIO



FOLDOUT FRAME



FOLDOUT FRAME



# RELATIONSHIP OF ORBITER TO PLATFORM FOR STRUT ATTACHMENT

- NOTE:**
- PLATFORM IS TRANSLATED THRU CONSTRUCTION FIXTURE & ALL STRUTS (SHEET 1 & SHEET 2) ARE ASSEMBLED ON THE SIDE OF PLATFORM CLOSEST TO AFT END OF ORBITER
  - ORBITER IS ROTATED & PROCEDURE REPEATED

OR AT THE END OF THE RMS  
FROM THE STORAGE CANNISTER  
AS DESCRIBED ON SHEET 1.

LOCATING THE WRIST ABOVE  
THE CROSS BEAM & .

IS THEN ROTATED APPROX 180°  
E ('LOOKING FORWARD') IN THE  
THE STRUT OVER ADJACENT  
IT POSITION.


MAKES 1ST ATTACHMENT (SEE SHEET 1)


STRUT 2. TRANSLATES TOWARDS  
FOR FINAL ASSEMBLY, AS PER  
DESCRIBED ON SHEET 1.

FOR CLARIFICATION OF DETAILS ETC.

# STRUT REMOVAL TO FINAL ATTACHMENT

3 FOLDOUT FRAME





RELATIONSHIP OF ORBITER TO PLATFORM FOR STRUT ATTACHMENT AS DEPICTED

NOTE: • PLATFORM IS TRANSLATED THRU CONSTRUCTION FIXTURE  
& ALL STRUTS (SHEET 1 & SHEET 2) ARE ASSEMBLED ON  
SIDE OF PLATFORM CLOSEST TO AFT END OF ORBITER:

• ORBITER IS ROTATED & PROCEDURE REPEATED

REMOVAL TO FINAL ATTACHMENT PROCEDURE

A-53,  
A-54




FOLDOUT FRAME

SCALE 1/80	BY RUCK DATE 2/5/81 MODEL SC 34	Archwell International	Space Systems Group 8711 Aerospace Parkway Downey, CA 90241	
BRACING STRUT INSTALLATION VIA, CHERRY PICKER				42662-71 SHEET 2 OF 2

INSERTION LEG GUIDE


CAP

BOTH SIDES OF LEG  
WELDED TO THE  
INNER SURFACE  
OF BEAM CAP



**DETAIL C** CAP SECTION




SCALE: FULL



**DETAIL B** CROSS MEME



SCALE: FULL

BOLDOUT FRAME



**DETAIL A**  
SCALE: 1/2

**DETAIL D**  
SCALE: 1/2




**BEAM GEOMETRY**


**ATTACH PORT ASS**

**FOLDOUT FRAME**


SCALE




**DETAIL D**  
SCALE: 1/2



**DETAIL E**  
SCALE: 1/2



INSERTION LEG  
SEE DETAIL A



**ATTACH PORT ASSEMBLED TO BEAM END**

SCALE 1/10

3

FOLDOUT FRAME

LEG END ATTACHMENT

BEAM CAP

CE FLANGE

535  
TO BEAM  
CENTROID

NT &  
DETAILS

176

40 40

110

**DETAIL E**  
SCALE: 1/2

INNER BALL END ATTACH

535  
TO BEAM  
CENTROID

FOR INFORMATION NOT SHOWN  
SEE OPPOSITE HAND FLANGE -  
DETAIL E

**DETAIL F**  
SCALE: 1/2

LEG SECURED  
TO FRAME  
(3 PLACES)

920

580

LATCH MOUNTING  
FLANGE - SEE  
LONG CROSS BEAM  
ATTACH PORT  
FOR DETAILS

150

215

353

404  
(REF.)

D

400

1212 (1.212M)

E

F

700

1400 (1.4M)

STRUT

**ATTACH PORT TRUSS ASSEMBLY**

(IDENTICAL FOR ALL PORTS)

FOLDOUT FRAME



INNER BALL END ATTACHMENT HOUSING

10.83 O.C.

5  
EAM  
ROID

NOTE! FOR ACTUAL HOUSING LOCATIONS  
SEE DWG. 42662-71

SECTION H-H  
SCALE: FULL

MAX. DIA. OF STRUT  
= 183 (7.2')

STRUT, (ALL POS  
SHOWN,  
DWG 42

STRUT E

1212 (1.212M)

875

875

STRUT, INNER HOUSING.  
(ALL POSSIBLE LOCATIONS  
SHOWN, SEE CHART-  
DWG. 42662-71)

535

535

SHORT CROSS BEAM ATTACH PORT


LONG C

CROSS BEAM END PORT DE


5

FOLDOUT FRAME

83 O.C. BALL ENDS




OUTER BALL END ATTACHMENT HOUSING




NOTE! FOR ACTUAL HOUSING LOCATIONS  
SEE DWG. 42662-71

SECTION J - J  
SCALE: FULL




STRUT, OUTER HOUSING  
(ALL POSSIBLE LOCATIONS  
SHOWN, SEE CHART -  
DWG 42771-71)



LONG CROSS BEAM ATTACH PORT




RT DETAILS



ACTIVE MALE LATE  
FOR FULL DETAILS  
SEE DWG. 42662-71


DETAIL K  
SCALE 1/2

FOLDOUT FRAME




FOR FULL DETAILS  
OF ELECTRICAL  
INTERFACE ASSEMBLY  
SEE DWG. 42662-70

ACTIVE MALE LATCH  
FOR FULL DETAILS  
SEE DWG. 42662-73




# **NOTE!**

PAYLOAD / BEAM ELECTRICAL  
INTERFACE ASSEMBLY  
INSTALLED ON L.H OR R.H  
SIDE OF ATTACH PORT TO  
ALIGN WITH THE FORWARD  
EDGE OF CROSS BEAM  
FOR LOCATION SEE CHART  
DWG. 42662-71




FOLDOUT FRAME

SECTION L - L  
SCALE: 1/4



**NOTE!**

PAYLOAD / BEAM ELECTRICAL INTERFACE ASSEMBLY INSTALLED ON L.H OR R.H SIDE OF ATTACH PORT TO ALIGN WITH THE FORWARD EDGE OF CROSS BEAM FOR LOCATION SEE CHART DWG. 42662-71





A-55,  
A-56

SCALE AS SHOWN	DATE 1-77	Rockwell International	42662-72 SHEET 1 OF 2
MALE MODULE ATTACH PORT			


ATTACH PORT HEXAGON FRAME

PLATE SPANS INSIDE  
OF HEXAGON FRAME




FOLDOUT FRAME

SECTION M - M



STIFFENING RIBS FAN OUT TO LEG INTERSECTION THEN BEND TO FOLLOW LEG ANGLE




FIXED COLLAR - TYPE A

LONGITUDINAL BEAM END PORT STRUCTURE


2 FOLDOUT FRAME

SCALE: FULL

FAN OUT  
TION  
FOLLOW



FLOATING CO





LINEAR ALLOWA

TYPE A



PORT STRUCTURE ATTACHMENT HOUSING DETAILS

SCALE: FULL

FOLDOUT FRAME



FLOATING COLLAR - TYPE C



LINEAR ALLOWANCE COLLAR - TYPE B

USING DETAILS

4 FOLDOUT FRAME



SURFACE (PLATE)

COLLAR

20MM ALL AROUND  
CLEARANCE - TOTAL  
MOVEMENT IN ANY  
DIRECTION = 40 MM

T  
ONLY  
FOR

ATTACH PORT AT END OF LONGITUDINAL BEAM

LINEAR ALLOWANCE STRUCTURAL  
ATTACHMENT USING INSTALLATION  
HOUSING WITH TYPE B COLLAR

NOTE: LINEAR MOTION IS ALONG  
LINE BETWEEN CENTER OF  
STRUCTURE & CENTER OF  
ATTACH PORT

STRUT STRUCTURE CENTER

FIXED STRUCTURAL ATTACHMENT  
USING INSTALLATION HOUSING  
WITH TYPE A COLLAR




NOTE: THE AFT THRUST STRUCTURE  
WILL ALSO USE THE 'FIXED'  
ATTACHMENT AT ALL 3  
ATTACH PORTS SEE  
DWG 42662 - 60  
FOR FULL DETAILS.

PLATFORM - FORWARD END VIEW

SCALE: 1/20

5

FOLDOUT FRAME



**DETAIL N**  
SCALE: 1/2

TYPICAL INSTALLATION  
OF STRUT ASSEMBLY TO A

ND VIEW



**FOLDOUT FRAME**

KU ANT  
SEE DWG

USE E  
FLANGE

ADD A  
FLANGE

ATTACHM  
AT AFT E  
LONGITUD



OF STRUT ASSEMBLY TO ATTACH PORT


FOLDOUT FRAME

KU ANTENNA MAST ASSEMBLY  
SEE DWG 42662-73 FOR DETAILS

USE EXISTING INTERFACE  
FLANGE FOR MOUNT

ADD ADDITIONAL MOUNTING  
FLANGE TO PORT - 2 PLACES

ATTACHMENT PORT  
AT AFT END OF APEX  
LONGITUDINAL BEAM



STRUT ATTACHMENT HOUSING (REF)

ADDITION TO ATTACH PORT

ONE ONLY


SCALE: 1/10

A-57,  
A-58

FOLDOUT FRAME


SCALE 1/10	BY R. J. C. K.	DATE 12/1/72	DESIGNED BY R. J. C. K.	CHECKED BY J. E. S. S.
MALE MODULE ATTACH PORT				42662-72 SHEET 2 OF 2


C-6




FOLDOUT FRAME

ORIGINAL PAGE IS  
OF POOR QUALITY







ORIGINAL PAGE IS  
OF POOR QUALITY







0°



OPERATING  
DOCKED OR


OPERATING MODE WITH  
DOCKED ORBITER

7 FOLDOUT FRAME

A-59,  
A-60

SHT 1 OF 2

SCALE 1/80 INCHES	DATE 1/2	Rockwell International	Sheet Number 42662-74 Total Number of Sheets 72
SOLAR ARRAY ASSEMBLY			42662-74



E MOTOR

360° ROTATION

±40° AXIS POT

RADIAL BEARING

SPUR G

SUPRING  
ASS'Y


BRUSH



360° AXIS

DUPLEX BEA

TORQUE TUBE

2 FOLDOUT FRAME







### DETAIL OF ROTARY JOINT

SCALE: 1/4


TUBE

FOLDOUT FRAME





# VIEW B-B ALTERNATIVE





ROTATION  $\pm 40^\circ$

805M(3221N)

40M(1601N)

SOLAR ARRAY  
HARNESS

CONTAINMENT BOX COVER  
AND ARRAY BLANKET OUTBOARD SUPPORT

SOLAR ARRAY HARNESS

SOLAR ARRAY BLANKET  
(FULLY EXTENDED)

ARRAY BLANKET STABILIZATION WIRES

INTERMEDIATE SUPPORT WITH PULLEY  
TENSION RESTRAINT

DEPLOYABLE MAST (FULLY EXTENDED)

CONSTRUCTION FIXTURE

14.5M  
(47 FT 6 IN)

SHUTTLE DOCKING INTERFACE

14.63M(48 FT)

FOLDING

7.31M(24 FT)

STRUT ASSEMBLY

RADIATORS - DEPLOYED

CONTROL MODULE

ROTARY JOINT WITH SLIP RING HOUSING

FOLDOUT FRAME

SOLAR ARRAYS

B

B

ED  
SIDE

CONTAINMENT BOX COVER  
AND ARRAY BLANKET OUTBOARD SUPPORT

SOLAR ARRAY HARNESS

SOLAR ARRAY BLANKET  
(FULLY EXTENDED)

ARRAY BLANKET STABILIZATION WIRES

INTERMEDIATE SUPPORT WITH PULLEY  
TENSION RESTRAINT

DEPLOYABLE MAST (FULLY EXTENDED)

CONSTRUCTION FIXTURE

2.5M  
82 FT 6 IN)

SHUTTLE DOCKING INTERFACE

STRUT ASSEMBLY

RADIATORS - DEPLOYED

CONTROL MODULE


FOLDOUT FRAME

ROTARY JOINT WITH SLIP RING HOUSING

SOLAR ARRAY BLANKET AREA  
(1 WING)

TOTAL SOLAR ARRAY BLANKET  
(4 WINGS)

OPERATING MODE WITHOUT  
DOCKED ORBITER

SCALE	DATE	REV	
1/100	12/80	1	
NOTED	DATE	REV	
SOLAR ARRAY ASSEMBLY			

RT

SOLAR ARRAY BLANKET AREA - 148 M<sup>2</sup>  
(1 WING)

XTURE

TOTAL SOLAR ARRAY BLANKET AREA - 592 M<sup>2</sup>  
(4 WINGS)


TERFACE

OPERATING MODE WITHOUT  
DOCKED ORBITER


SHT 2 OF 2

A-61,

A-62

SCALE 1/100 NOTED	DATE 12-50-73 REV 001	 Rockwell International	Rockwell International 10000 Wilshire Blvd Beverly Hills, CA 90210
SOLAR ARRAY ASSEMBLY			42662-74

8. FOLDOUT FRAME



### ⑤ POWER SUPPLY HOOK-UP TO INTERSECTION FITTING.

NOTE -

- ASTRONAUT TAKES POWER SUPPLY PIGTAIL FROM LOCATION ON BEAM POSITIONER AND CONNECTS SAME TO ELECTRODE ON THE INTERSECTION FITTING BETWEEN CROSS BEAM AND THE LONGITUDINAL BEAM.
- THE CHERRY PICKER IS TRANSLATED TO THE ADJACENT LONGITUDINAL BEAM WHERE THE PROCEDURE IS REPEATED.
- BOTH INTERSECTION FITTINGS REMAIN CONNECTED FOR THE REQUIRED "COOKING" PERIOD (THE ASTRONAUT IS FREE TO PERFORM OTHER DUTIES DURING THIS TIME, IF CONSIDERED PRACTICAL.)
- THE CROSS BEAM IS NOW WELDED TO THE LONGITUDINAL BEAM, AND THE POWER SUPPLY PIGTAILS ARE REMOVED.
- THE ABOVE PROCEDURE IS REPEATED FOR BOTH TRANSVERSE BEAMS. (TOTAL 3 SIDES - 6 CONNECTIONS)


ASTRONAUT CONNECTING  
POWER SUPPLY TO  
INTERSECTION FITTING  
ELECTRODE.

CROSS BEAM

2 FOLDOUT FRAME

### EVA FUNCTIONS

- EVA OBSERVATION GUIDANCE
- ALIGN BEAM POSITIONER FOR
- SUPERVISE TRANSVERSE & C
- APPLY ELECTRODES TO SELF
- VERIFICATION OF STRUCTURAL
- TRANSLATE DIAGONAL CORDS
- CONNECT TENSION CORDS TO
- CHECK STRUCTURAL ALIGNM
- RELEASE ELECT. PIG TAILS FR
- MAKE ELECTRICAL CONNECTI



CHERRY PICKER

POSITIONING ARM

INT  
MOU  
& B

SWING  
BEAM P  
OPPOS  
EXCEPT

TTING.

CATION ON  
ON THE

IT  
TED.

THE REQUIRED  
RM OTHER

BEAM.


IVERSE BEAMS.

### EVA WORK STATION

- ④ ASTRONAUT ABOARD CHERRY PICKER RE  
THE FOLLOWING MANUAL FUNCTI

### 3 FOLDOUT FRAME

WITH THE CHERRY PICKER IN POSITION  
THE ASTRONAUT SECURES HIS FEET INTO  
THE FOOT RESTRAINT, SECURES SAFETY  
TETHER (NOT SHOWN) AND RELEASES  
HIMSELF FROM THE MMU.



### 3 ASTRONAUT SECURING FEET INTO CHERRY PICKER

BEAM HANDLING.  
VIA RMS DELIVERY.  
SEMBLIES.  
SECTION FITTINGS.  
CONTROL OF BEAM POSITIONER.  
TUDINAL BEAMS.  
FITTINGS EARS.  
DIAGONAL CORDS.  
& CROSS BEAMS.  
RE LINES.

FOR  
WINE

TIONER (REF.)


STATION N°1  
EXTENSION

WITH  
ATED  
IG PLANE,  
SEMBLY OPERATIONS.

PERFORM

4 FOLDOUT FRAME

THE MMU IS 'DOCKED' INTO THE ATTACHMENT  
STATION WHERE THE ASTRONAUT PREPARES  
TO ATTACH HIMSELF TO THE CHERRY PICKER.




② MMU LOCKED IN ATTACHMENT STATION

**FOLDOUT FRAME**

**CONSTRUCTION FIXTURE  
(WORK STATION N°1)**

**ATTACHMENT STATION,  
(UNFOLDED FROM STOWED  
CONFIGURATION READY  
TO RECEIVE THE MMU.)**

**MMU.**




**① MMU MANEUVERING TOWARDS ATTACHMENT STATION**




7 FOLDOUT FRAME

MMU LEAVES THE ORBITER  
FLIGHT SUPPORT STATION &  
'FLIES' TOWARDS THE  
CONSTRUCTION FIXTURE.




TRANSLATION OF ASTRONAUT VIA, MMU FROM ORBITER TO CONSTRUCTION

# 8 FOLDOUT FRAME




BITER TO CONSTRUCTION FIXTURE


A-63,  
A-64

00000 by BUCK / KCV Date 2/12/83 MODEL SC5A	 Rockwell International	
EVA WORK STATION FUNCTIONS - DESCRIPTION & ILLUSTRATION	42662-78 SHEET 1 OF 3	

FOLDOUT FRAME



CORD TENSIONING OPERATION



DEVICE IN POSITION

SPRING RETENSION HOOK

HOLDING SQUARE

CORD HOLDER

ROTATIONAL LINEAR

DRIVE GEAR

HOLDER  
RETENSION  
BALL

FORWARD

L.H. OR R.H  
THUMB  
OPERATED  
SWITCH

BATTERY


DRIVE MOTOR WITH  
OVERLOAD CLUTCH

LONGITUDINAL

HAND HELD CORD  
TENSIONING DEVICE

NOTE-

AFTER DIAGONAL CORD HAS BEEN ASSEMBLED  
HAND HELD DEVICE IS USED, AS SHOWN, TO TENSION  
CORD (VIA, LEADING HOOK) TO PRE-DETERMINED AMOUNT.



### 3 FOLDOUT FRAME

ASTRONAUT REMOVING TETHER  
FROM TRAILING HOOK & ATTACHING  
SAME TO THE CHERRY PICKER

ASTRONAUT ATTACHING DIAGONAL CORD  
TO LEADING EAR OF ADJACENT  
INTERSECTION FITTING.

CORD HAS BEEN ATTACHED  
TO TRAILING EAR OF  
INTERSECTION FITTING

CHERRY PICKER

2ND & SUBSEQUENT  
TRANSVERSE BEAMS


### 8 DECOUPLING OF DIAGONAL

#### NOTE -

- AT THE 2ND & SUBSEQUENT BEAM INTERSECTIONS THE ASTRONAUT ATTACHES THE TRAILING HOOK ON THE CORD TO THE TRAILING EAR OF THE INTERSECTION FITTING.
- THE TETHER ATTACHED TO THE TRAILING CORD HOOK IS REMOVED FROM THE TRAILING HOOK & ATTACHED TO AN ATTACHMENT PROVIDED ON THE CHERRY PICKER.
- THE CHERRY PICKER IS ROTATED TO THE ADJACENT BEAM INTERSECTION. THE ASTRONAUT ATTACHES THE LEADING HOOK TO THE LEADING EAR OF THE INTERSECTION FITTING.
- THE TETHER IS REMOVED FROM THE LEADING CORD HOOK & ATTACHED TO THE TRAILING HOOK. THIS PROCESS IS REPEATED, CROSSING THE CORDS. (TYP. FOR ALL 3 SIDES)

FOOT NOTE: AN ALTERNATE TO INDIVIDUAL TETHERS WOULD BE A PERMANENT ATTACHMENT WITH A DOUBLE ENDED TETHER PERMANENTLY ATTACHED TO THE CHERRY PICKER.

CH OF DIAGONAL CORD



### 8 DECOUPLING OF DIAGONAL CORD

SUBSEQUENT BEAM INTERSECTIONS THE ASTRONAUT ATTACHES THE HOOK ON THE CORD TO THE TRAILING EAR OF THE INTERSECTION FITTING.

ATTACHED TO THE TRAILING CORD HOOK IS REMOVED & SECURED BY THE ATTACHMENT PROVIDED ON THE CHERRY PICKER.

CHERRY PICKER IS ROTATED TO THE ADJACENT BEAM INTERSECTION WHERE THE ASTRONAUT ATTACHES THE LEADING HOOK TO THE LEADING EAR OF THE INTERSECTION FITTING.

THE HOOK IS REMOVED FROM THE LEADING CORD HOOK & THE PROCEDURE IS REPEATED CROSSING THE CORDS. (TYP. FOR ALL 3 SIDES OF THE PLATFORM.)

AN ALTERNATE TO INDIVIDUAL TETHERS WOULD BE A CORD HOOK TO HOOK SYSTEM WITH A DOUBLE ENDED TETHER PERMANENTLY ATTACHED TO THE CHERRY PICKER.

7 INI

# 5 FOLDOUT FRAME

SUBSEQUENT CROSS BEAM


ASTRONAUT REMOVING  
FROM STORAGE REEL

DIAGONAL CORD FROM ATTACHMENT  
AT PREVIOUS BEAM INTERSECTION

DIAGONAL CORD STORAGE REEL

ASTRONAUT ATTACHING CORD  
TO INTERSECTION FITTING

TRANSLATION



CONSTRUCT

## 6 INITIAL DIAGONAL

NOTE -  
• AT THE FIRST  
THE CORD EN  
TRAILING EN

## 7 INITIAL DIAGONAL CORD ATTACHMENT

• ABOVE PRO  
INTERSECTION

4 FOLDOUT FRAME  
FOLDOUT FRAME

REMOVING CORD  
STORAGE REEL

CHERRY PICKER

STORAGE REEL

→ DIRECTION OF PLATFORM T

TRANSVERSE BEAM  
AT 1ST BEAM INTERSECTION

LONGITUDINAL BEAM

CONSTRUCTION FIXTURE - WORK STATION №1

DIAGONAL CORD

# DIAGONAL CORD REMOVAL FROM REEL


- AT THE FIRST BEAM INTERSECTION ASTRONAUT REMOVES THE CORD END FROM REEL AND ATTACHES SAME TO THE TRAILING EAR OF THE INTERSECTION FITTING.
- ABOVE PROCEDURE REPEATED AT EACH BEAM TO BEAM INTERSECTION (TOTAL 6 PLACES)

✓	1
✓	2
✓	3
✓	4
✓	5
✓	6
✓	7
✓	8
✓	9
✓	10
✓	11
✓	12
✓	13
✓	14
✓	15
✓	16
✓	17
✓	18
✓	19
✓	20
✓	21
✓	22
✓	23
✓	24
✓	25
✓	26
✓	27
✓	28
✓	29
✓	30
✓	31
✓	32
✓	33
✓	34
✓	35
✓	36
✓	37
✓	38
✓	39
✓	40
✓	41
✓	42
✓	43
✓	44
✓	45
✓	46
✓	47
✓	48
✓	49
✓	50
✓	51
✓	52
✓	53
✓	54
✓	55
✓	56
✓	57
✓	58
✓	59
✓	60
✓	61
✓	62
✓	63
✓	64
✓	65
✓	66
✓	67
✓	68
✓	69
✓	70
✓	71
✓	72
✓	73
✓	74
✓	75
✓	76
✓	77
✓	78
✓	79
✓	80
✓	81
✓	82
✓	83
✓	84
✓	85
✓	86
✓	87
✓	88
✓	89
✓	90
✓	91
✓	92
✓	93
✓	94
✓	95
✓	96
✓	97
✓	98
✓	99
✓	100

EVA  
- DES



# 7 FOLDOUT FRAME



## DIAGONAL CORD INSTALLATION


NO 1


M REEL

T REMOVES  
TO THE

TO BEAM

A-65,  
A-66

DESIGNED BY BUCKLEY DATE 2/12/80 REVISED SC5A	 Rockwell International <small>Space Station Group 1974 - 1980 Beverly Hills, CA 90212</small>	
EVA WORK STATION FUNCTIONS - DESCRIPTION & ILLUSTRATION	42662-78 SHEET 2 OF 3	



TRANSVERSE BEAM

## (12) PIGTAILS SECURED TO STRUCTURE

### NOTE -

- ASTRONAUT REMOVES TIES ON CROSS BEAM, FOR THE PIGTAIL CABLES.
- PIGTAIL ENDS ARE TRANSFERED TO THE LONGITUDINAL BEAM WHERE THE CONNECTOR END IS MATED WITH THE LONGITUDINAL BEAM CONNECTOR.
- THE PIGTAILS ARE BOUND TOGETHER AT THEIR MID-POINT VIA, A VELCRO STRAP /OR SIMILAR, IS THEN WRAPPED AROUND AND SECURED TO THE PLATFORM STRUCTURE.

2 **HOLDOUT FRAME**

ASTRONAUT BINDING PIGTAILS  
AT MID-POINT READY FOR  
ATTACHMENT TO STRUCTURE

ASTRONAUT CONNECTING  
PIGTAIL ENDS TO INTERFACE  
ON LONGITUDINAL BEAM

STRUCTURE


CROSS BEAM, FREEING

TO THE LONGITUDINAL  
IS MATED WITH  
CTOR.


IER AT THEIR APPROX.  
(OR SIMILAR) WHICH  
ECURED TO THE

II CABLE INTERFACE CONNECTION

ELECTRICAL CABLE




## 2. FOLDOUT FRAME



## ELECTRICAL CABLE INTERFACE CONNECTION PROCEEDURE

# 4 FOLDOUT FRAME



## REMOVAL OF CABLE PIGTAILS


## SECTION PROCEDURE

	BY: BUCK/FRY DATE: 2/18/80 DRAWN: SC34	Rockwell International 12000 International Boulevard Irvine, CA 92618	
EVA WORK STATION FUNCTIONS - DESCRIPTION & ILLUSTRATION			4266 SHEET

5 FOLDOUT FRAME

LONGITUDINAL BEAM

A-67,  
A-68

 BUCK/FBY 2/12/80 SC34	 Rockwell International 12110 L. International Beverly Hills, CA 90211	
EVA WORK STATION FUNCTIONS - DESCRIPTION & ILLUSTRATION		42662-78 SHEET 3 OF 3

APPENDIX B  
CONSTRUCTION ACTIVITY DATA SHEETS  
AND SUPPORTING DATA PACKAGES


The following material is formally documented results of analyses of specific construction activities identified during the study of design and construction of an Engineering and Technology Verification Platform (ETVP). The sheets are arranged in numerical order, and represent analytical effort performed for three successive missions. Mission 1 analyses begin with No. 1.0 and continue through No. 17.2. Mission 2 analyses begin with No. 21.0, and Mission 3 analyses begin with No. 41.0. A total of 43 separate packages of data is included.

PRECEDING PAGE BLANK NOT FILMED

## ACTIVITY 1.0

### CONSTRUCTION ACTIVITY DATA SHEET

PROJECT: ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM



### REFERENCE DATA

1. Space Construction Data Base
2. Drawing 42662-50 Construction Fixture
3. Drawing 42662-64 Modifications to Beam Builder
4. Drawing 42662-66 Orbiter Stowage and Return, First Flight

### DESCRIPTION OF ACTIVITY

Following checkout of the RMS, the construction fixture (described in Attachment No. 1) is removed by the RMS from the orbiter bay, rotated, and mated to the elevated docking interface of the orbiter. Remotely actuated connectors will complete the electrical interface. The various subsystems of the fixture are deployed remotely at astronaut command initiated from the orbiter crew cabin. Subsequent to checkout and installation of the beam builder, the fixture is ready to fabricate the first longitudinal beam. Selected aspects of the deployment are illustrated in Attachment 3.

CONSTRUCTION SUPPORT EQUIPMENT: RMS, lighting, and TV

### TIMELINE

- 86 minutes, 30 seconds to erect, deploy, and check out the fixture (see Attachment No. 2 and Section 5.3)

### POWER/ENERGY

- Average power, 0.665 kW; peak power, 2.4 kW; energy, 3450 kJ.  
(See Attachment 2 and Section 5.3)


### CREW LOAD

- IVA: One man, continuous
- EVA: 0

### TECHNOLOGY DEVELOPMENT REQUIREMENTS

- None required for the activity.



PREPARED BY: R. HART		Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 2
CHECKED BY:			ACTIVITY 1.0
DATE: 21 NOV 1979		ERECT AND DEPLOY CONSTRUCTION FIXTURE	MODEL NO. ETVP
SHEET NO.	ATTACHMENT NO. 1		DWG. NO. REF: 42662-50
1	<p>Construction fixture is shown on Drawing 42662-50, Sheets 1 through 4.</p> <p>The installed orientation of the construction fixture on the orbiter and an early conceptual concept of fixture assembly are presented. Sheet 4 illustrates the revised current construction fixture concept.</p>		
2	<p>Shows the addition of the attach port magazine and welder to the beam machine. Conceptual details of the intersection fitting used to structurally join the crossbeams to the longitudinal beams are shown in Zone 30. In Zones 40 through 43 the approach for installing the electrical lines from the cable storage reels is illustrated.</p>		
3	<p>Shows the addition of the arms supporting the libration damping RCS, together with the associated black boxes, batteries, antennas, etc.</p>		
4	<p>Illustrates the latest concept for the construction fixture system which supersedes the initial building block approach. The new system is basically self-contained and involves extensive deployment of the principal elements. The advantages of the new system are:</p> <ul style="list-style-type: none"> <li>• Reduced crew workload</li> <li>• Reduced time to configure system for operation</li> <li>• Frees the RMS for other activities</li> <li>• The complete assembly can be checked out on the ground</li> <li>• Reduces the number of electrical and mechanical interfaces</li> </ul> <p>The disadvantage of the deployable system is its increased cost because of the mechanical complexity.</p> <p>The construction fixture consists of the following items:</p> <ul style="list-style-type: none"> <li>• Yoke structure</li> <li>• Rigidizing links</li> <li>• Folding bridge structure</li> <li>• Folding bridge structure separation latches</li> <li>• Libration damping RCS, gyros, electronics, and articulated arms</li> <li>• Batteries</li> <li>• Omni antennas</li> <li>• Navigation lights</li> <li>• Beam builder interface, elec. and mech.</li> <li>• Crossbeam positioner</li> <li>• Platform drive rollers and extending support arms</li> <li>• Six cross-brace cable reels, deployment arms, and all cross-brace cables</li> <li>• Electric cable laying machine, deployment mechanism and all electric cables for longitudinal beam</li> <li>• Cherry picker and maneuvering arm</li> <li>• Attach points for MMU and contingency equipment</li> <li>• Work lights and TV</li> <li>• Attach points for RMS</li> <li>• Emergency EVA handholds, footholds, etc.</li> <li>• Orbiter attachments (stowage)</li> </ul>		

FORM 994-B-1 REV 12-78



# ACTIVITY 1.0

## ATTACHMENT 2

TIME, POWER, & ENERGY ESTIMATION FOR ERECTION, DEPLOYMENT AND CHECKOUT OF THE CONSTRUCTION FIXTURE

TASK DESCRIPTION	DURATION (SEC)	PEAK POWER (kW)	AVG POWER (kW)	ENERGY (kJ)
NOTE: THE FIRST SECTION OF THIS TABLE DEALS ONLY WITH THE ERECTION & DEPLOYMENT OF THE CONSTRUCTION FIXTURE.				
1. GRASP THE CONSTRUCTION FIXTURE WITH THE RMS	60	0.845 (a) 1.050 (b)	0.845 1.050	50.7 63.0
2. RELEASE THE PAYLOAD RETENTION LATCHES	30	0.02	0.02	6
3. USE THE RMS TO REMOVE THE CONSTRUCTION FIXTURE FROM THE ORBITER BAY AND RAISE IT TO A POSITION IN LINE WITH THE DOCKING FIXTURE IN THE ORBITER BAY	600	0.845 (a) 1.050 (b)	0.845 1.050	507 630
4. RAISE THE DOCKING FIXTURE TO ITS DEPLOYED POSITION	60	0.05	0.05	3
5. ROTATE THE CONSTRUCTION FIXTURE 90 DEGREES ABOUT ITS Z-AXIS	180	0.845 (a) 1.050 (b)	0.845 1.050	152.1 189
6. MATE THE CONSTRUCTION FIXTURE TO THE DOCKING FIXTURE; OPERATE THE STRUCTURAL LATCHES AND THE ELECTRICAL INTERFACE CONNECTOR; THE CONSTRUCTION FIXTURE NOW HAS ELECTRICAL POWER; RELEASE THE RMS	600	0.845 (a) 1.050 (b) 0.10 (LATCHES)	0.845 1.050	507 630 (NEGL.)
7. EXPAND & RIGIDIZE THE YOKE (MAIN ARMS) OF THE CONSTR. FIXTURE; THE FOLDING BRIDGE STRUCTURE IS DEPLOYED BY THE ACTION OF THE YOKE	300	0.1	0.1	30
8. LOCK THE LINKS & HINGES OF YOKE & BRIDGE STRUCT.	30	0.02	0.02	0.6
9. ROTATE CENTER EXTENSION OF THE BRIDGE THROUGH 90 DEGREES & LOCK	90	0.02	0.02	1.8
10. EXTEND & LOCK THE 4 SUPPORT ARMS WHICH CARRY THE 27 BEAM DRIVE ROLLERS	90	0.08	0.08	7.2
11. TV, 120 W; TV HEATING, 24 W; LIGHTING 200 W FOR 1530 SECONDS (TASKS 1 THROUGH 10)	1530	0.344	0.344	526.3
TOTAL, ERECTION & DEPLOYMENT	2040	2.339*	1.703***	3298.3
(a) BASIC RMS (b) RMS HEATER				
*SEE NOTE AT END OF THIS ATTACHMENT				
**SEE NOTE AT END OF THIS ATTACHMENT				

ATTACHMENT 2 (CONT.)

ACTIVITY 1.0

TASK DESCRIPTION	DURATION (SEC)	PEAK POWER (kW)	AVG POWER (kW)	ENERGY (KJ)
NOTE: THIS SECOND SECTION OF TABLE DEALS ONLY WITH THE CHECKOUT OF THE CONSTRUCTION FIXTURE PRIOR TO FABRICATION OF THE PLATFORM.				
12. ACTIVATE THE BEAM DRIVE ROLLERS FORWARD & REVERSE; 27 ROLLERS X 2 DIRECTIONS X 10 SEC EACH	270	0.01	0.01	2.7
13. ACTIVATE CHERRY PICKER AT WORK STATION NO. 1; USE EACH ARTICULATION IN SEQUENCE; 6 ARTICULATIONS X 60 SECONDS	360	0.1	0.1	36
14. STOW CHERRY PICKER IN A CENTRAL POSITION TO AVOID INTERFERENCE WITH BEAM BUILDER OPERATIONS	180	0.1	0.1	18
15. MOVE CROSS-BRACE CABLE REELS FROM THE STOWED TO THE DEPLOYED POSITION & LOCK	120	0.05	0.05	6
16. MOVE ELECTRIC CABLE REEL FROM THE STOWED TO THE DEPLOYED POSITION & LOCK	60	0.05	0.05	3
17. RETURN THE ELECTRIC CABLE REEL TO THE STOWED POSITION & LOCK	60	0.05	0.05	3
18. RETURN THE CROSS-BRACE CABLE REELS TO THE STOWED POSITION & LOCK	120	0.05	0.05	6
19. CHECK OUT THE BEAM POSITIONER; MOVE EACH ARTICULATION (6 DEGREES OF FREEDOM); 6 ARTICULATIONS X 60 SEC—NOTE: THIS ALSO IS A CHECK FOR BEAM BUILDER ROTATION	360	0.05	0.05	18
20. DEPLOY & LOCK THE TWO ARTICULATED ARMS WHICH CARRY THE LIBRATION DAMPING RCS	180	0.05	0.05	9
21. CHECK OUT THE LIBRATION DAMPING RCS	300	0.001	0.001	0.3
22. RESTOW THE TWO ARTICULATED ARMS & LOCK	180	0.05	0.05	9

ATTACHMENT 2 (CONCL.)

ACTIVITY 1.0

TASK DESCRIPTION	DURATION (SEC)	PEAK POWER (kW)	AVG POWER (kW)	ENERGY (KJ)
23. TURN ON LIGHTS & TV FOR CHECKOUT—TV, 120 W; TV HEATING, 24 W; LIGHTING, 500 W	60	0.644	0.644	38.6
24. CHECK OUT BATTERIES	300	0.001	0.001	0.3
25. CHECK OUT BLACK BOXES	600	0.001	0.001	0.6
TOTAL, CHECKOUT	3150 52 MIN., 20 SEC	0.644*	0.048**	150.5
TOTAL, ERECTION & DEPLOYMENT	2040	2.339*	1.703**	3298.3
GRAND TOTAL	5190 86 MIN., 30 SEC	2.339*	0.665**	3448.8
*PEAK POWER SUMMARY BASED UPON PEAK POWER OF INDIVIDUAL ACTIVITIES SUBJECTIVELY ESTIMATED AS BEING PERFORMED SIMULTANEOUSLY.				
**AVERAGE POWER = $\frac{\text{ENERGY SUMMATION}}{\text{ACTIVITY TIME SUMMATION}}$				

PREPARED BY:

Space Systems Group



Rockwell  
International

PAGE NO. OF

CHECKED BY:

ACTIVITY 1.0  
REPORT NO.

DATE:

ERECT & DEPLOY CONSTRUCTION  
FIXTURE


MODEL NO. ETVP

DWG. NO.

REF.

### ATTACHMENT #3

- REMOVE THE CONSTRUCTION FIXTURE FROM THE ORBITER BAY
- RAISE THE ORBITER DOCKING FIXTURE
- ROTATE THE CONSTRUCTION FIXTURE
- MATE TO THE DOCKING FIXTURE



PREPARED BY:

Space Systems Group



Rockwell  
International

PAGE NO.

OF

CHECKED BY:

ACTIVITY 1.0  
REPORT NO.

DATE:

ERECT & DEPLOY CONSTRUCTION  
FIXTURE


MODEL NO. ETVP

DWG. NO.


REF.

### ATTACHMENT #3 (CONTD)

ELECTRICAL CABLE & CROSS  
BRACE REELS



DEPLOYMENT OF CENTER  
SECTION OF BRIDGE



NOTE:

LONGITUDINAL BEAMS SHOWN FOR REFERENCE ONLY

PREPARED BY:

Space Systems Group



Rockwell  
International

PAGE NO. OF

CHECKED BY:

ACTIVITY 1.0  
REPORT NO.

DATE:


ERECT & DEPLOY CONSTRUCTION  
FIXTURE

MODEL NO. ETVP

DWG. NO.


REF.

ATTACHMENT #3 (CONTD)



CROSS BRACE CABLE  
REELS DEPLOYED

ELECTRICAL CABLE REEL  
STOWED & DEPLOYED



CROSS BRACE CABLE  
REELS STOWED

ORIGINAL PAGE IS  
OF POOR QUALITY

NOTE:

LONGITUDINAL BEAMS SHOWN FOR REFERENCE ONLY


FORM 994-B-1 REV 12-78



## ACTIVITY 2.0

### CONSTRUCTION ACTIVITY DATA SHEET

PROJECT: ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM



### REFERENCE DATA

1. Space Construction Data Base
2. Drawing 42662-50 Construction Fixture
3. Drawing 42662-64 Modifications to Beam Builder
4. Drawing 42662-66 Orbiter Stowage and Return, First Flight

### DESCRIPTION OF ACTIVITY

The beam builder assembly is removed by the RMS from the orbiter bay and installed on the construction fixture at the interface provided. The beam builder assembly (see Attachment 2) consists of:

- Magazine and six end attach ports
- Positioner and welder for the end attach ports
- Mechanical and electrical interface latches and connectors
- Beam builder
- Support tripod

### CONSTRUCTION SUPPORT EQUIPMENT

- RMS
- TV
- Lighting
- Construction fixture

### TIMELINE

1560 seconds (26 minutes)—see Attachment 1

ORIGINAL PAGE IS  
OF POOR QUALITY

### POWER, ENERGY

Peak power, 2.2 kW; average power 1.53 kW; energy, 2374.7 kJ  
(see Attachment 1)

### CREW LOAD

- IVA: One man, continuous
- EVA: None

### TECHNOLOGY DEVELOPMENT REQUIREMENTS


Electrical interface connector between fixture and beam builder assembly

# ACTIVITY 2.0


## ATTACHMENT 1

TIME, POWER, & ENERGY ESTIMATION FOR INSTALLING THE BEAM BUILDER ON CONSTRUCTION FIXTURE

TASK DESCRIPTION	DURATION (SEC)	PEAK POWER (kW)	AVG POWER (kW)	ENERGY (KJ)
1. GRASP THE BEAM BUILDER ASSEMBLY WITH THE RMS	60	0.845 (a) 1.050 (b)	0.845 0.525	50.7 31.5
2. RELEASE THE PAYLOAD RETENTION LATCHES (REMOTE CONTROL FROM ORBITER CREW CABIN)	30	0.02	0.02	6
3. REMOVE THE BEAM BUILDER FROM THE ORBITER & TRANSPORT IT TO THE VICINITY OF THE FIXTURE	600	0.845 (a) 1.050 (b)	0.845 0.525	507 315
4. MATE THE BEAM BUILDER ASSEMBLY TO THE INTERFACE ON THE FIXTURE	600	0.845 (a) 1.050 (b)	0.845 0.525	507 315
5. SECURE THE MECHANICAL LATCHES BETWEEN THE BEAM BUILDER ASSEMBLY AND THE FIXTURE (REMOTE CONTROL FROM ORBITER CREW CABIN)	30	0.02	0.02	6
6. MATE THE ELECTRICAL INTERFACE CONNECTOR BETWEEN THE BEAM BUILDER ASSEMBLY AND THE FIXTURE (REMOTE CONTROL FROM ORBITER CREW CABIN)	30	0.02	0.02	6
7. RELEASE THE RMS & MOVE AWAY FROM THE FIXTURE/BUILDING ASSEMBLY	200	0.845 (a) 0.050 (b)	0.845 0.525	169 105
8. RMS TV's & ELBOW TILT & PAN, 34 W; HEATERS (TV's + TILT & PAN), 46 W (ASSUME 50% DUTY CYCLE); LIGHTING, 137 W; FOR 1550 SEC (TASKS 1 THROUGH 7)	1550	0.253	0.230	356.5
TOTAL	1550 (25 MIN, 50 S)	2.168 (c)	1.53 (d)	2374.7
(a) BASIC RMS				
(b) RMS HTG				
(c) PEAK POWER SUMMARY BASED UPON PEAK POWER OF INDIVIDUAL ACTIVITIES, SUBJECTIVELY ESTIMATED, BEING PERFORMED SIMULTANEOUSLY				
(d) AVERAGE POWER = ENERGY SUMMATION/ACTIVITY TIME SUMMATION				

PREPARED BY:	Satellite Systems Division Space Systems Group	 Rockwell International	PAGE NO. _____ OF _____
CHECKED BY:			ACTIVITY 2.0
DATE:	INSTALL BEAM BUILDER ON CONSTRUCTION FIXTURE		MODEL NO. ETVP
REF.	ATTACHMENT 2		DWG. NO.

ORIGINAL PAGE IS  
OF POOR QUALITY




### ACTIVITY 3.1

#### CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

ACTIVITY



REFERENCE DATA

PRECEDING PAGE BLANK NOT FILMED

1. Convair Division of General Dynamics, *Space Construction Automated Fabrication Experiment Definition Study (SCAFEDS)*, Part III, Mid-Term Briefing, CASD-AS78-013, 13 December 1978 (describes beam-builder machine)
2. Drawing 42662-45, Rockwell Tri-Beam Concept, ETVP
3. Space Construction Data Base
4. Drawing 42662-72, Attachment Port Details
5. Drawing 42662-50, Tri-Beam Construction Fixture

ORIGINAL PAGE IS  
OF POOR QUALITY

DESCRIPTION OF ACTIVITY

Begins with initial heating of cap material and continues until cutoff of beam and separation from beam machine, leaving sufficient cap stub length to permit joining of attachment port on the end. Fabrication methods per Reference 1, with modifications per Reference 4 (pertinent to end stub size). Beam is supported on construction fixture per Reference 5, beam fabrication rates per Reference 5, but first attachment port joining interrupts beam building.

CONSTRUCTION SUPPORT EQUIPMENT

1. Tri-beam construction fixture system (Reference 6)
2. Lighting and TV system—Attachment 1
3. Beam-builder machine per Reference 1

TIMELINE: 1.08 m/min. (Reference 5); 1.66 hr for 108 m (see Section 5.3)


POWER/ENERGY (see Section 5.3)

- Beam Builder: 2242 W avg, 3545 W peak, 179.2 kJ/bay, 125 kJ/m, 3.72 kWh/beam
- Lighting: 200 W
- TV: 120 W plus 34 W for heater

CREW LOAD

- IVA: Approximately 0.5 man continuously monitoring
- EVA: 0

TECHNOLOGY DEVELOPMENT REQUIREMENTS: Development of beam builder

PREPARED BY:	Satellite Systems Division Space Systems Group	 <b>Rockwell International</b>	PAGE NO. 1 OF 1
CHECKED BY:			ACTIVITY NO. 3.1
DATE:	FABRICATE BASE LONGITUDINAL BEAM NO. 1		MODEL NO. ETVP
			DWG. NO.

**ATTACHMENT 1**


Lighting and TV System Concept Description (see Figure below)

1. Nominal Operations

- Lamps. Two 100-W incandescent lamps, one mounted on each side of TV camera on beam machine, generally illuminates in same direction as beam is generated, and area where attachment ports are installed.
- TV. One camera mounted on beam machine, looking outward in same direction as beam is generated. View should permit observing installation of attachment ports and inspection of beam straightness for gross monitoring by crew in cabin. Tilt capability may be required.
- Hardware can be adapted from RMS system components.

2. Contingency and Special Operations

- RMS camera and lights can be utilized as required (not included in power/energy data in Data Sheet)



(\*Not to scale)


TV and Lamp Location and Orientation

## ACTIVITY 3.2

### CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

#### ACTIVITY



#### REFERENCE DATA

1. Drawing 42662-72, Attachment Port Details
2. Drawing 42662-50, Tri-Beam Construction Fixture
3. Space Construction Data Base
4. Convair Division of General Dynamics, *Space Construction Automated Fabrication Experiment Definition Study (SCAFEDS)* Part III, Mid-Term Briefing, CASD-AS78-013, 13 Dec. 1978 (Describes beam-builder machine.)

#### DESCRIPTION OF ACTIVITY

The activity consists of installing an attachment port at each end of the longitudinal beam. The function begins with rotating an installation device (loaded with attachment port) into alignment with the beam machine. A short section of the beam is fabricated, then the legs of the attachment port are inserted into the beam caps, as shown in Reference 1, and welded in place. The port is released, then the installation device is rotated out of alignment and reloaded with the second attachment port. After the crossbeam is fabricated, cut off, and translated axially away from the beam-builder machine, installation of the second port is performed in a manner similar to that for the first—but in opposite direction of motion. The function is complete when the installation device is rotated out of alignment with the beam.

#### CONSTRUCTION SUPPORT EQUIPMENT

1. Tri-beam construction fixture system and beam-builder machine (Reference 2), including installation device for attachment ports (see Attachment 3).
2. Beam-builder machine, per Reference 4
3. Controls and display systems for operation of installation device for attachment ports
4. TV camera and lights on beam-builder machine (see Attachment 1).

## ACTIVITY 3.2

### TIMELINE

First Port: 4.12 minutes (interrupts beam fabrication 2.28 minutes)

Second Port (after beam fabrication): 3.86 minutes

Total time for port installation: 7.98 minutes (See Attachment 2)

### POWER/ENERGY

Installation Device: Average Power: .146 kW Peak Power: .981 kW

Energy (for two ports): 67.85 kJ (See Attachment 2) Lighting: 200 Watts

TV Camera with Heater, 23W average, 33W peak


### CREW LOAD

IVA: One person - continuously during each installation sequence

EVA: 0

### TECHNOLOGY DEVELOPMENT REQUIREMENTS

- o Development of space-qualified installation device for attachment ports.
- o Resistance heating of intermediate filler material for welding of composite materials without active clamping.

PREPARED BY:	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:		ACTIVITY NO. 3.2
DATE:	INSTALL ATTACHMENT PORTS ON LONGITUDINAL BEAM NO. 1	MODEL NO. ETVP
		DWG. NO.

**ATTACHMENT 1**


Lighting and TV System Concept Description (see Figure below)

1. Nominal Operations

- Lamps. Two 100-W incandescent lamps, one mounted on each side of TV camera on beam machine, generally illuminates in same direction as beam is generated, and area where attachment ports are installed.
- TV. One camera mounted on beam machine, looking outward in same direction as beam is generated. View should permit observing installation of attachment ports and inspection of beam straightness for gross monitoring by crew in cabin. Tilt capability may be required.
- Hardware can be adapted from RMS system components.

2. Contingency and Special Operations


- RMS camera and lights can be utilized as required (not included in power/energy data in Data Sheet)



(\*Not to scale)

TV and Lamp Location and Orientation



PREPARED BY:	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 3
CHECKED BY:		ACTIVITY NO. 3.2
DATE:	TIME, POWER & ENERGY ANALYSIS—ATTACHMENT PORT INSTALLATION—LONGITUDINAL BEAMS	MODEL NO. ETVP
		DWG. NO.

ATTACHMENT 2

1	<p>Initial installation and checkout of installation device includes running attachment port holder head back to stowed stack of attachment ports mounted on beam machine, grasping one port and axially positioning ready for installation. Subsequently, the attachment port is aligned with the beam; overall concept is shown in Attachment 3.</p> <p>The loading function for attaching the second port on the beam can be done in parallel with the resumption of fabrication, saving time of installation at the end of beam fabrication. This makes each cycle start with a loaded installation device.</p> <p>The initial loading operation could be done while the first bay is being fabricated, but this could be an undesirable division of attention of the crew for these initial, critical operations.</p>
2	Electrical resistance welding is performed without any auxiliary clamps, with power supplied through the installation device holder head.
3	Attachment port clip (includes mandrel) can be separately detached from cradle in orbiter payload bay.

	<p><b>ANALYSIS</b></p> <p>The tables included herein list tasks, time, power, and energy estimates for each attachment port installation on one longitudinal beam. Thus, summing results of the two time analyses—</p> <div style="text-align: right; margin-right: 100px;">         Total times: 4.12 (1st port)                            <u>3.86</u> (2nd port)                            7.98 minutes (0.133 hr)       </div> <p><u>Note:</u> Similar results apply to crossbeam fabrication/assembly. The data in the tables will be incorporated into "Space Construction Standards and Practices" for future use.</p> <p>For the two power/energy analyses—</p> <div style="text-align: right; margin-right: 100px;">         Total energy: 35.9 (1st port)                            <u>33.95</u> (2nd port)                            69.85 kJ       </div> <p>Average energy was derived by dividing total energy by time, e.g.,</p> <div style="text-align: center; margin: 10px 0;"> <math display="block">\frac{33.95 \text{ kJ} \times 1000}{232 \text{ sec}} (\text{watt-sec}) = 0.146 \text{ kW}</math> </div> <p>In both cases, the peak power estimate was derived from the scaled-up estimate of power for welding crossmembers on the GD beams, per "Space Construction Standards and Practices."</p>
--	---

FORM 994-B-1 REV 12-78

# ACTIVITY 3.2

## ATTACHMENT 2 (CONT.)

Page 2 of 3

### TIME, POWER, AND ENERGY ESTIMATION FOR ATTACHMENT PORT INSTALLATION DEVICE

TASK DESCRIPTION (FIRST PORT)	DURATION (SEC)	PEAK PWR (kW)	AVG PWR (kW)	ENERGY (kJ)
• ROTATE ATTACHMENT PORT HOLDER 180° INTO ALIGNMENT WITH BEAM BUILDER MACHINE	30		0.075	2.2
• DRIVE ATTACHMENT PORT INTO END OF BEAM	5		0.150	0.75
• WELD (ELECTR. RESISTANCE—ASSUME POWER IS SAME AS FOR BUILDING BEAM)	15	0.981	0.294	23.5
• VERIFY WELD—PULL TEST, 3 TIMES—ONCE PER LEG	15	0.150	0.150	2.25
• RELEASE ATTACH PORT	2		0.010	0.10
• RETRACT INSTALLATION DEVICE AXIALLY	10		0.075	0.75
• ROTATE 180° TO ALIGN WITH DISPENSER FOR ATTACH PORTS (BEAM FABR. MAY RESUME)	30		0.030	0.9
• REPOSITION AXIALLY AND GRASP NEXT ATTACH PORT APPROX. 2 m	30		0.075	2.2
• REPOSITION AXIALLY TO CLEAR ATTACH PORT	15		0.100	1.50
• ROTATE HEAD TO ORIENT PORT FOR SECOND INSTALLATION (180° FROM FIRST PORT)	10		0.075	0.75
• DELAY PERIODS BETWEEN STEPS (VISUAL VERIFICATION/CONTROL OF OPERATIONS) 11 x 5 SEC = 55 SEC	55			
• SHUTDOWN 2 HR UNTIL BEAM FABRICATED (FOR LONGITUDINALS)	20			
TOTALS (FIRST PORT)	247 4.12 MIN.	0.981*	0.145	35.9

\*PEAK POWER BASED UPON PEAK POWER OF INDIVIDUAL ACTIVITIES, SUBJECTIVELY ESTIMATED, BEING PERFORMED SIMULTANEOUSLY.

# ACTIVITY 3.2

## ATTACHMENT 2 (CONCL.)

### TIME, POWER, AND ENERGY ESTIMATION FOR ATTACHMENT PORT INSTALLATION DEVICE

TASK DESCRIPTION (SECOND PORT)	DURATION (SEC)	PEAK PWR (kW)	AVG PWR (kW)	ENERGY (kJ)
<ul style="list-style-type: none"> <li>• ROTATE ATTACHMENT PORT HOLDER 180° INTO ALIGNMENT WITH BEAM BUILDER MACHINE*</li> <li>• DRIVE ATTACHMENT PORT INTO END OF BEAM</li> <li>• WELD (ELECTR. RESISTANCE—ASSUME POWER IS SAME AS FOR BUILDING BEAM)</li> <li>• VERIFY WELD—PULL TEST, 3 TIMES—ONCE PER LEG</li> <li>• RELEASE ATTACH PORT</li> <li>• RETRACT INSTALLATION DEVICE AXIALLY</li> <li>• ROTATE 180° TO ALIGN WITH DISPENSER FOR ATTACH PORTS</li> <li>• ROTATE HEAD 180° FOR GRASPING ATTACH PORT</li> <li>• REPOSITION AXIALLY &amp; GRASP NEXT ATTACH PORT APPROX. 2 METERS</li> <li>• REPOSITION AXIALLY TO PREPARE FOR FIRST PORT INSTALLATION ON FOLLOWING BEAM</li> <li>• DELAY PERIODS BETWEEN STEPS (VISUAL VERIFICATION/CONTROL OPERATIONS) 11 x 5 SEC = 55 SEC</li> <li>• SHUTDOWN/LOCK FOR RELOCATING BEAM BUILDER ON CONSTR. FIXTURE</li> </ul>	30 5 15 15 2 10 30 10 30 10 55 20	  0.981 0.150          0.981**	0.075 0.150 0.294 0.150 0.010 0.075 0.030 0.030 0.075 0.100	2.2 0.75 23.5 2.25 0.10 0.75 0.9 0.3 2.2 1.00
TOTALS (SECOND PORT)	232 3.86 MIN.	0.981**	0.146	33.95
<p>*PREVIOUSLY LOADED</p> <p>**PEAK POWER BASED UPON PEAK POWER OF INDIVIDUAL ACTIVITIES, SUBJECTIVELY ESTIMATED, BEING PERFORMED SIMULTANEOUSLY</p>				

PREPARED BY:

Space Systems Group



Rockwell  
International

PAGE NO. 1 OF 2

CHECKED BY:

ACTIVITY 3.2  
REPORT NO.

DATE:


INSTALLATION OF ATTACHMENT PORTS


MODEL NO. ETVP

REF.


ATTACHMENT 3

DWG. NO.



PREPARED BY:		Space Systems Group  Rockwell International	PAGE NO. 2 OF 2
CHECKED BY:			ACTIVITY 3.2 REPORT NO.
DATE:		INSTALLATION OF ATTACHMENT PORTS	
REF.		MODEL NO. ETVP DWG. NO.	

ATTACHMENT 3




The diagram illustrates the installation of Attachment 3. It features a central vertical beam machine. To its left is an attachment port positioner mechanism, which is a horizontal assembly with a vertical beam and a horizontal beam. The positioner mechanism is labeled 'POSITIONER FOR PORT ORIENTATION AND ATTACHMENT'. The beam machine is labeled 'BEAM MACHINE'. The attachment port positioner mechanism is shown in two positions, with a '180°' rotation indicated. The beam machine has a '1.6 M STROKE' dimension. The beam machine is connected to a 'BEAM BUILDER STRUCTURAL FRAME'. The beam builder structural frame is a triangular structure with a 'WELD HEAD' at one corner. The beam builder structural frame is labeled 'BEAM ASSY STRUCTURE'.

## ACTIVITY 4.0

### CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

ACTIVITY



REFERENCE DATA

1. Convair Division of General Dynamics, *Space Construction Automated Fabrication Experiment Definition Study (SCAFEDS)*, Part III, Mid-Term Briefing, CASD-AS78-013, 13 December 1978.
2. Drawing 42662-45, Rockwell Tri-Beam Concept, ETVP
3. Space Construction Data Base
4. Drawing 42662-50, Tri-Beam Construction Fixture

DESCRIPTION OF ACTIVITY: Initial activity to permit relocation of the beam builder is to activate the release mechanism of the locking device which provides structural attachment and alignment of the beam builder to the construction fixture. After the release function is performed, the beam builder's power drive unit, located in the crossbeam support of the building fixture, is actuated, driving the swing arm supporting the beam builder from position No. 1, 120 degrees counterclockwise to beam position No. 2. Activation of the positioning and locking mechanism will secure the beam builder in its proper orientation so fabrication of longitudinal beam No. 2 can be initiated. (See Attachment 2.)

CONSTRUCTION SUPPORT EQUIPMENT

1. Tri-beam construction fixture (Reference 4)
2. Beam builder machine (Reference 1)
3. Lighting and TV system (Attachment 1)

TIMELINE: 7 minutes (see Attachment 2)

POWER/ENERGY


Peak power, 2.7 kW; average power 2.5 kW; energy, 0.29 kWh (see Attachment 2)

CREW LOAD

IVA: Approximately 0.5 man for monitoring operation  
EVA: None

TECHNOLOGY DEVELOPMENT REQUIREMENTS

Developing techniques for platform assembly

PREPARED BY:	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:		ACTIVITY NO. 4.0
DATE:	INSTALL ATTACHMENT PORTS ON LONGITUDINAL BEAM NO. 1	MODEL NO. ETVP
		DWG. NO.

ATTACHMENT 1


Lighting and TV System Concept Description (see Figure below)

1. Nominal Operations

- Lamps. Two 100-W incandescent lamps, one mounted on each side of TV camera on beam machine, generally illuminates in same direction as beam is generated, and area where attachment ports are installed.
- TV. One camera mounted on beam machine, looking outward in same direction as beam is generated. View should permit observing installation of attachment ports and inspection of beam straightness for gross monitoring by crew in cabin. Tilt capability may be required.
- Hardware can be adapted from RMS system components.

2. Contingency and Special Operations

- RMS camera and lights can be utilized as required (not included in power/energy data in Data Sheet)



(\*Not to scale)

TV and Lamp Location and Orientation

## ACTIVITY 4.0

### ATTACHMENT 2

#### TIME, POWER, AND ENERGY ANALYSIS FOR REPOSITIONING THE BEAM BUILDER WHILE SUPPORTED ON THE BUILDING FIXTURE

##### Assumptions

For the effort of repositioning the beam builder, certain assumptions have to be considered as a normal condition for this operation. The first is that all electrical and data leads will remain connected during any rotation cycle. The rotation drive mechanism for the swing arm support will be located inside the structure portion of the fixture crossbeam. Orientation and position verification, plus locking features, would also be built into the beam builder support and fixture crossbeam structure.

##### Analysis

The following table lists tasks, time, power, and energy estimates for the beam builder and fixture configuration.

Task Description	Duration (sec)	Power (kW)		Energy (kJ)
		Peak	Average	
Preparation	120	-	-	-
Disconnect locking device	5	0.005	0.005	Negl.
Rotate beam builder	120	0.200	0.200	2.4
Reconnect locking device	5			Negl.
Position port attach fitting	30	0.075	0.075	2.2
Checkout (B.B. average power)	140			
• Lighting		0.200	0.200	0.84
• TV camera and heater	(420)*	0.033	0.023	0.10
• Beam builder standby		2.24	2.24	940.8
Summary	420	2.673†	2.526††	1061 (0.295 kWh)
<p>*Non-additive time</p> <p>†Peak power summary based upon peak power of individual activities, subjectively estimated, being performed simultaneously.</p> <p>††Average power = <math>\frac{\text{energy summation}}{\text{activity time summation}}</math></p>				




ACTIVITY: 5.1 & 5.2

CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

ACTIVITY



REFERENCE DATA

1. Dwg. 42662-45, Rockwell Tri-Beam Concept, ETVP
2. Space Construction Data Base
3. Dwg. 42662-50, Tri-Beam Construction Fixture

DESCRIPTION OF ACTIVITY

Power and communications line bundles are packaged on a single reel with the Velcro attachment strips in place, as shown in Attachment 3. The bundles are first attached to the longitudinal beam near the aft end and then "laid on" as the beam is withdrawn under the reel. The Velcro attachment strips are automatically attached to the beam crossmembers as the beam is withdrawn (Attachment 3). The final attachment is at a crossmember near the control center module end, after which the reel is removed.

CONSTRUCTION SUPPORT EQUIPMENT: (1) RMS with appropriate end effector, (2) wire bundle dispensing reel, (3) wire bundle attachment mechanism—see Attachment 3, (4) lighting and TV, and (5) tri-beam construction fixture.

TIMELINE: See Attachments 1 and 2; 8280 seconds (2 hr, 18 min.)


POWER/ENERGY: Beam withdrawal and wire attachment—peak power, 0.1 kW; average power, 0.05 kW; energy, 3840 kJ. Lighting—200 W. TV camera with heater—23 W average, 33 W peak.


CREW LOAD: IVA—One man continuously, monitoring; EVA—none

TECHNOLOGY DEVELOPMENT REQUIREMENTS

Wire bundle dispensing and attachment system.

PRECEDING PAGE BLANK NOT FILMED

PREPARED BY: C. Fritz	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:	5.1 Withdraw Base Longitudinal Beam No. 1 5.2 Install Elec. Lines on Base Long. Beam No. 1	ACTIVITIES 5.1 & 5.2
DATE: 11/20/79		MODEL NO. ETVP
	<div data-bbox="591 401 874 478" data-label="Section-Header"> <p>ATTACHMENT 1</p> </div> <p data-bbox="326 548 605 574">BASIS FOR TIMELINE</p> <ol style="list-style-type: none"> <li data-bbox="331 607 1305 666">(1) Beam withdrawal rate assumed to be 2.16 meters/minute, which is the same as the rate of beam advance.</li> <li data-bbox="331 698 1305 757">(2) Wire bundle attachment to be automatic; time estimated to be 40 seconds, maximum, per crossmember.</li> </ol>	<div data-bbox="1246 345 1350 366" data-label="Text"> <p>DWG. NO.</p> </div>

PREPARED BY: C. Fritz	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:		ACTIVITIES 5.1 & 5.2
DATE: 11/20/79	5.1 Withdraw Base Longitudinal Beam No. 1 5.2 Install Elec. Lines on Base Long. Beam No. 1	MODEL NO. ETVF
		DWG. NO.

ATTACHMENT 2


Timeline Summary

Operation		Time
1.	Activate reel and attachment mech.	5 min.
2.	Initial attachment	40 sec
3.	Withdraw beam 1.434 meters	40 sec
4.	Attach wire bundle to beam	40 sec
5.-194.	Repeat Steps 3 and 4 95 times each	126 min.
195.	Deactivate reel	5 min.
Total		138 min. (2 hr, 18 min.)


PREPARED BY: C. Fritz	Satellite Systems Division Space Systems Group	Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:			ACTIVITIES 5.1 & 5.2
DATE: 11/20/79	5.1 Withdraw Base Longitudinal Beam No. 1 5.2 Install Elec. Lines on Base Long. Beam No. 1	MODEL NO. ETVP	DWG. NO.

ATTACHMENT 3

# WIRE INSTALLATION—LONGITUDINAL BEAM



- DURING WITHDRAW TRANSLATION  
WORK STATION NO. 1
- INTEGRAL CABLE RUN
  - SINGLE REEL
  - FLEX RAILROAD TRACK CONCEPT
  - INTEG. CROSSBEAM CONNECTORS
- "LINEAR" REEL DRIVE
- AUTOMATED VELCRO ATTACHMENT




VELCRO ATTACHMENT

## ACTIVITY 6.0

### CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

#### ACTIVITY



#### REFERENCE DATA

1. Space Construction Data Base
2. Drawing 42662-45, Rockwell Tri-Beam Concept, ETVP
3. Drawing 42662-50, Tri-Beam Construction Fixture

#### DESCRIPTION OF ACTIVITY

When the laying of the wire bundles has been completed (Activity 5.2), Beam No. 1 is translated through the construction fixture rollers back to the position which it occupied at the completion of fabrication.

#### CONSTRUCTION SUPPORT EQUIPMENT

Tri-beam construction fixture—rollers, roller drive mechanism, and control system. (See Attachment 1.)


TIMELINE 2.16 meters/minute, 50 minutes for 108 meters (see Section 5.3)

POWER/ENERGY Construction fixture—peak power = 0.10 kW, average power = 0.10 kW, energy = 381 kJ. Lights—200 W. TV with heater—23 W average, 33 W peak. Total energy—0.356 kJ. (see Section 5.3)

CREW LOAD IVA—approximately 0.5 man continuously monitoring; EVA—none

#### TECHNOLOGY DEVELOPMENT REQUIREMENTS

Development of construction fixture roller drive and control system.

J. Roebuck PREPARED BY:		Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:			Activity No. 6.0
DATE: 11/28/79		Return Base Longitudinal Beam No. 1 to Fabrication Position	MODEL NO. ETVP
			DWG. NO.

**ATTACHMENT 1**


The rollers and roller drive mechanisms must accommodate the specific mass of just one longitudinal beam plus attached electrical wiring (approximately 4177 lb = 1894 kg), as well as the lower mass of beam alone (at start of previous activity (5.1), and mass of completed platform with payloads.


A constant speed drive control is required once the beam has been accelerated. A braking method also must be incorporated to stop motion. A position sensing system is needed to assure correct stopping location. Adequate redundancy in sensing may include a physical power shutoff trigger device and a revolution counter or timer to alert crew for monitoring the stopping period.

The translation speed selected for this activity is very conservative, being that used by the beam builder (during its motion periods). A further analysis may indicate much faster translation rates would be desirable to minimize overall time and energy requirements. A free-wheeling roller system might also be employed, since only friction of the rollers will require power, once motion is initiated. This approach would permit variable (non-controlled) translation rates.

At this time there is no apparent schedule impact due to the selected translation rate, since beam fabrication (which is proceeding simultaneously) is probably the pacing activity.

FORM 994-B-1 REV 12-78

J. Roebuck		Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
PREPARED BY:			ACTIVITY NO. 6.0
CHECKED BY:		Return Base Longitudinal Beam No. 1 to Fabrication Position	MODEL NO. ETVP
DATE: 11/28/79			DWG. NO.



ATTACHMENT 2

6.0 POWER/ENERGY ANALYSIS

Two methods were investigated as means to estimate power requirements for the translation of the beam.

Method 1

This method is based upon fundamental physics analysis of accelerating the mass to the stated velocity, then assuming a constant power draw at the same rate until the beam is stopped. Efficiency factors of 25% and 2.5% were assumed.

Method 2

This method is based on an overall power demand proportional to weight and velocity, derived from empirical considerations. The results were higher and judged more conservative and acceptable for the application in this activity.

SUMMARY


The power requirements for actual beam translation are trivial compared to other demands, even those for lighting and TV to monitor the motion.

## ACTIVITY 7.0

### CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

#### ACTIVITY



#### REFERENCE DATA

1. Space Construction Data Base
2. Drawing 42662-52, No. 2 Construction Station—General Arrangement
3. Drawing 42662-66, Orbiter Bay Stowage, First Launch

#### DESCRIPTION OF ACTIVITY

Remove elements of the No. 2 station from the orbiter bay and set up astride the longerons. (See Attachments 1 and 2 for details.)

#### CONSTRUCTION SUPPORT EQUIPMENT

1. RMS with rotational joint between shoulder and elbow and special end effector
2. Lighting and TV system

TIMELINE 52.67 minutes (see Attachment 1)

#### POWER/ENERGY

Peak power, 2.199 kW; average power, 1.767 kW; energy, 5800 kJ  
(See Attachment 1)

#### CREW LOAD

IVA astronaut—52.67 minutes, continuous

#### TECHNOLOGY DEVELOPMENT REQUIREMENTS

Remote control, self-aligning, electrical connector

PRECEDING PAGE BLANK NOT FILMED



## ACTIVITY 7.0

### ATTACHMENT 1

Time, Power, and Energy Estimates for setting up No. 2 Construction Station

ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVERAGE PWR. (kW)	ENERGY (kJ)
1. OPEN THE PAYLOAD RETENTION LATCHES WHICH SECURE THE Y-FRAME, WITH ITS STACKS OF END PORT FITTINGS, IN THE ORBITER BAY.	30	0.02	0.02	0.6
2. USE THE RMS TO REMOVE THE Y-FRAME FROM THE ORBITER BAY, ROTATE IT 90°, AND SEAT THE MOUNTING TRUNNIONS IN THE PAYLOAD RETENTION LATCHES.	1380	0.845 <sup>(1)</sup> (BASIC RMS) 1.050 <sup>(2)</sup> (RMS HEATER)	0.845  0.525 (50% DUTY)	1166.1  724.5
3. CLOSE THE LATCHES, RELEASE THE RMS, AND MOVE RMS TO TEMPORARY HOLD POSITION.	50 (LATCHES) 60 (RMS)	0.03  1.895	0.03  1.37	1.5  82.2
4. ACTUATE THE REMOTE ELECTRICAL CONNECTION BETWEEN THE Y-FRAME AND THE ORBITER BAY.	30	0.01	0.01	0.3
5. OPEN THE PAYLOAD RETENTION LATCHES WHICH SECURE THE REEL ASSEMBLY IN ORBITER BAY. REEL ASSEMBLY CONSISTS OF:	30	0.02	0.02	0.6
<ul style="list-style-type: none"> <li>• ELECTRICAL CABLE REEL (FOLDED)</li> <li>• INTERSECTION FITTING APPLICATOR</li> <li>• DRIVE ROLLERS</li> <li>• STRUCTURAL FRAME ASSEMBLY</li> </ul>				
6. USE THE RMS TO REMOVE THE REEL ASSEMBLY FROM THE ORBITER BAY, ROTATE IT, AND SET IT IN ITS DEPLOYED LOCATION ON THE RH LONGERON AND Y-FRAME, AND IN THE RETENTION LATCHES.	1380	1.895	1.37	1890.6
7. CLOSE THE LATCHES AND REMOVE THE RMS TO TEMPORARY HOLD POSITION	50 (LATCH) 60 (RMS)	0.02  1.895	0.02  1.37	1.0  82.2

# ACTIVITY 7.0


## ATTACHMENT 1 (Cont.)

Time, Power, and Energy Estimates for setting up No. 2 Constructor Station


ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVERAGE PWR. (kW)	ENERGY (kJ)
8. ACTUATE THE REMOTE ELECTRICAL CONNECTION BETWEEN THE Y-FRAME AND THE REEL ASSEMBLY FRAME.	30	0.01	0.01	0.3
9. UNFOLD THE ELECTRICAL CABLE REEL FROM ITS STOWED POSITION AND ROTATE IT TO ITS DEPLOYED LOCATION AND LATCH IT IN PLACE.	60	0.03	0.03	1.8
10. TV AND LIGHTING REQUIRED THROUGHOUT THE SETTING UP OF NO. 2 STATION.	(3160, TIME NOT ADDITIVE)	0.585 <sup>(3)</sup>	0.565	1848.6
TOTALS AND AVERAGES	3160	2.199 <sup>(5)</sup> (1)+(2)+(3)	1.767 <sup>(6)</sup>	5800.3

### NOTES

- (1) THE RMS IS DIRECTED FROM THE ORBITER CABIN AND NOT IN A CHERRY PICKER MODE.
- (2) THE FOLLOWING ACTIVITY STEPS ARE INITIATED FROM THE ORBITER CABIN BY ELECTRICAL SWITCHES—  
STEPS 1, 3, 4, 5, 7, 8, 9.
- (3) TV WITH HEATERS: 46 W AVERAGE, 66 W PEAK (2 TV CAMERAS)
- (4) LIGHTING, 519 W (3 LAMPS).
- (5) PEAK POWER SUMMARY BASED UPON PEAK POWER OF INDIVIDUAL ACTIVITIES, SUBJECTIVELY ESTIMATED, BEING PERFORMED SIMULTANEOUSLY.
- (6) AVERAGE POWER =  $\frac{\text{ENERGY SUMMATION}}{\text{ACTIVITY TIME SUMMATION}}$

PREPARED BY:	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:		ACTIVITY 7.0
DATE:	SET UP CONSTRUCTION STATION NO. 2	MODEL NO. ETVP
REF.		DWG. NO.

ATTACHMENT 2




FOR CLARITY, THE STORED  
END PORTS ARE OMITTED  
FROM THIS VIEW.

## ACTIVITY 8.1

### CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

#### ACTIVITY



#### REFERENCE DATA

1. Space Construction Data Base
2. Drawing 42662-50, Construction Fixture No. 1
3. Drawing 42662-52, Construction Station No. 2

#### DESCRIPTION OF ACTIVITY (see Attachments 1, 2, and 3)

The activity consists of releasing the beam builder from the support tripod and using the RMS to transport and install the beam builder onto the Y-frame of Construction Station No. 2. The support tripod is removed from Construction Fixture No. 1, using the RMS, and stowed in the orbiter bay.

#### CONSTRUCTION SUPPORT EQUIPMENT

RMS, lighting, and TV

#### TIMELINE

3070 seconds (51 minutes, 10 seconds) (see Attachment 1)

#### POWER ENERGY

Average power, 2.156 kW; peak power, 2.259 kW; energy, 6619.5 kJ  
(see Attachment 1)

#### CREW LOAD

IVA, one man continuous; EVA, none

#### TECHNOLOGY DEVELOPMENT REQUIREMENTS

None.

# ACTIVITY 8.1

## ATTACHMENT 1

Time, Power, and Energy Estimation for Relocation of Beam Builder onto Construction Station No. 2

TASK DESCRIPTION	DURATION (sec)	PEAK POWER (kW)	AVERAGE PWR (kW)	ENERGY (kJ)
1. GRASP THE BEAM BUILDER (ON THE SUPPORT TRIPOD AT CONSTRUCTION FIXTURE NO. 1) WITH THE RMS.	60	0.845* 1.050**	0.845 1.050	50.7 63.0
2. BY REMOTE CONTROL FROM THE ORBITER CREW CABIN, RELEASE THE MECHANICAL AND ELECTRICAL CONNECTIONS BETWEEN THE BEAM BUILDER AND THE SUPPORT TRIPOD.	30	0.02	0.02	6
3. USING THE RMS, TRANSPORT THE BEAM BUILDER TO THE VICINITY OF CONSTRUCTION STATION NO. 2.	600	0.845* 1.050**	0.845 1.050	507 630
4. USING THE RMS, PLACE THE BEAM BUILDER IN POSITION ON CONSTRUCTION STATION NO. 2	600	0.845* 1.050**	0.845 1.050	507 630
5. BY REMOTE CONTROL FROM THE ORBITER CREW CABIN, SECURE THE MECHANICAL LATCHES TO RETAIN THE BEAM BUILDER TO CONSTRUCTION STATION NO. 2	30	0.02	0.02	6
6. BY REMOTE CONTROL FROM THE ORBITER CREW CABIN, MATE THE ELECTRIC INTERFACE CONNECTOR BETWEEN THE BEAM BUILDER AND CONSTRUCTION STATION NO. 2	30	0.02	0.02	6
7. RELEASE THE RMS FROM THE BEAM BUILDER AND MOVE AWAY FROM CONSTRUCTION STATION NO. 2 TOWARD CONSTRUCTION FIXTURE NO. 1	200	0.845* 1.050**	0.845 1.050	169 210
8. GRASP THE SUPPORT TRIPOD (ON CONSTRUCTION FIXTURE NO. 1) WITH THE RMS	60	0.845* 1.050**	0.845 1.050	50.7 63.0
9. BY REMOTE CONTROL FROM THE ORBITER CREW CABIN, RELEASE THE MECHANICAL AND ELECTRICAL CONNECTIONS BETWEEN THE SUPPORT TRIPOD AND CONSTRUCTION FIXTURE NO. 1	30	0.02	0.02	6
*BASIC RMS **RMS HEATING				

ACTIVITY 8.1

ATTACHMENT 1 (Cont.)

Time, Power, and Energy Estimation for Relocation of Beam Builder onto Construction Station No. 2

TASK DESCRIPTION	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
10. USING THE RMS, TRANSPORT THE SUPPORT TRIPOD TO THE ORBITER BAY.	600	0.845* 1.050**	0.845 1.050	507 630
11. USING THE RMS, PLACE THE SUPPORT TRIPOD IN ITS PAYLOAD RETENTION LATCHES IN THE ORBITER BAY.	600	0.845* 1.050**	0.845 1.050	507 630
12. BY REMOTE CONTROL FROM THE ORBITER BAY, SECURE THE PAYLOAD RETENTION LATCHES FOR THE SUPPORT TRIPOD.	30	0.02	0.02	6
13. RELEASE THE RMS AND MOVE IT AWAY FROM THE SUPPORT TRIPOD.	200	0.845* 1.050**	0.845 1.050	169 210
14. RMS TV WITH HEATER—23 W AVERAGE, 33 W PEAK; LIGHTING, 200 W—FOR 2870 SECONDS (TASKS 1 THROUGH 13).	3070	0.233	0.223	684.6
TOTAL	3070 50 MIN., 10 SEC	2.259†	2.023	6212
*BASIC RMS **RMS HEATING †PEAK POWER SUMMARY BASED UPON PEAK POWER OF INDIVIDUAL ACTIVITIES, SUBJECTIVELY ESTIMATED, BEING PERFORMED SIMULTANEOUSLY.				

PREPARED BY: R. HART

Space Systems Group



Rockwell  
International

PAGE NO. 1 OF 1

CHECKED BY:

ACTIVITY 8.1


DATE: 27 NOV 1979

RELOCATE BEAM BUILDER FOR CROSS/TRANSVERSE  
BEAM FABRICATION

MODEL NO. ETVP

DWG. NO.

ATTACHMENT 2




PREPARED BY: R. HART	Satellite Systems Division Space Systems Group	Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:			ACTIVITY 8.1
DATE: 27 NOV 1979	RELOCATE BEAM BUILDER FOR CROSS/TRANSVERSE BEAM FABRICATION		MODEL NO. ETVP
			DWG. NO.

ATTACHMENT 3

# BEAM BUILDER INSTALLED AT CONSTRUCTION STATION NO. 2

- ① MECHANICAL LATCHES
- ② ELECTRICAL INTERFACE BETWEEN BEAM BUILDER AND NO. 2 STATION






## ACTIVITY 8.2

### CONSTRUCTION ACTIVITY DATA SHEET

PROJECT    ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

#### ACTIVITY



#### REFERENCE DATA

1. Space Construction Data Base
2. Dwg. 42662-50, Construction Fixture No. 1
3. Dwg. 42662-55, EVA Work Station

#### DESCRIPTION OF ACTIVITY

The activity begins when the EVA astronaut with MMU arrives at the docking station at Construction Fixture No. 1, as shown on Attachment 2. The astronaut docks the MMU to the construction fixture and remotely controls the cherry picker to his vicinity. He transfers to the cherry picker and maneuvers to his work position to join Transverse Beam No. 1. Parallel in time to these EVA operations, the construction fixture is reconfigured by remote control from the orbiter crew cabin. The reconfiguration consists of repositioning the cross-brace cable reels and the beam positioner.

#### CONSTRUCTION SUPPORT EQUIPMENT

MMU, TV, lights

PRECEDING PAGE BLANK NOT FILMED

#### TIMELINE

780 seconds (13 minutes) (see Attachment 1)

#### POWER/ENERGY

Peak power, 0.433 kW; average power, 0.258 kW; energy, 201 kJ  
(see Attachment 1)

#### CREW LOAD

EVA: One man, continuous  
IVA: One man, part time

#### TECHNOLOGY DEVELOPMENT REQUIREMENTS

None

# ACTIVITY 8.2


## ATTACHMENT 1

Time, Power, and Energy Estimation for EVA Astronaut Arrives at Construction Fixture No. 1 and Reconfiguration of Construction Fixture No. 1

TASK DESCRIPTION	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
1. EVA ASTRONAUT IN MMU ARRIVES AT THE DOCKING STATION ON CONSTRUCTION FIXTURE NO. 1, MANUALLY UNFOLDS THE TWO ARM RESTRAINTS AND THE FOOT RESTRAINTS WHICH ARE PART OF THE DOCKING STATION.	180	-	-	-
2. EVA ASTRONAUT IN MMU MANEUVERS TO BACK INTO THE DOCKING STATION AND SECURE HIMSELF	120	-	-	-
3. BY REMOTE CONTROL FROM THE ORBITER CREW CABIN, THE CHERRY PICKER IS MANEUVERED TO BE WITHIN REACH OF THE EVA ASTRONAUT.	180	0.10	0.10	18
4. THE EVA ASTRONAUT TRANSFERS FROM THE DOCKING STATION TO THE CHERRY PICKER, LEAVING THE MMU SECURED IN THE DOCKING STATION.	120	-	-	-
5. THE EVA ASTRONAUT IN THE CHERRY PICKER MANEUVERS TO HIS WORK STATION TO JOIN TRANSVERSE BEAM NO. 1	180	-	-	-
6. BY REMOTE CONTROL FROM THE ORBITER CREW CABIN: • DEPLOY THE 6 CROSS-BRACE CABLE REELS & LOCK • DEPLOY THE BEAM POSITIONER (PARALLEL IN TIME TO TASK 1)	(120) ( 60)	0.05 0.05	0.05 0.05	6 3
7. LIGHTS, 200 W (20 W AT DOCKING STATION, 180 W AT CHERRY PICKER)	780	0.20	0.20	156
8. TV WITH HEATER: 23 W AVERAGE, 33 W PEAK	240	0.33	0.23	18
*PEAK POWER SUMMARY BASED ON PEAK POWER OF INDIVIDUAL ACTIVITIES, SUBJECTIVELY ESTIMATED, BEING PERFORMED SIMULTANEOUSLY.	780 (13 MIN.)	0.433*	0.258	201

PREPARED BY: R. HART	Satellite Systems Division Space Systems Group	Rockwell International	PAGE NO. 1 OF 2
CHECKED BY:			ACTIVITY 8.2
DATE: 26 NOV 1979	EVA ASTRONAUT ARRIVES AT CONSTRUCTION FIXTURE NO. 1		MODEL NO. ETVP
			DWG. NO.

ATTACHMENT 2




ASTRONAUT WITH MMU BACKS INTO THE DOCKING STATION

PREPARED BY:	Satellite Systems Division Space Systems Group	Rockwell International	PAGE NO. 2 OF 2
CHECKED BY:			ACTIVITY 8.2
DATE:	EVA ASTRONAUT ARRIVES AT CONSTRUCTION FIXTURE NO. 1		MODEL NO. ETVP
REF.			DWG. NO.

ATTACHMENT 2  
(Cont.)

CHERRY PICKER IS MOVED INTO  
POSITION FOR BOARDING BY  
ASTRONAUT.




## ACTIVITY 9.1

### CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM

#### ACTIVITY



#### REFERENCE DATA

1. Convair Division of General Dynamics, Space Construction Automated Fabrication Experiment Definition Study (SCAFEDS), Part III Mid-Term Briefing, CASD-AS78-013, 13 December 1978 (describes beam-builder machine)
2. Drawing No. 42662-45, Rockwell Tri-Beam Concept, ETVP
3. Space Construction Data Base
4. Drawing No. 42662-52, Number 2 Construction Station

#### DESCRIPTION OF ACTIVITY

Begins with initial heating of cap material and continues until cutoff of beam and separation from beam machine a sufficient distance to permit joining of intersection fitting on end (per Reference 2). Fabrication methods per Reference 1, with modifications per Attachment 1 (pertinent to end stub length). Beam is supported at work station no. 2 construction fixture per Reference 4 (see Attachment 2). Beam fabrication rates per Reference 1, but first joining of intersection fitting interrupts beam building. (Typical for all transverse beams)

#### CONSTRUCTION SUPPORT EQUIPMENT

1. Work Station No. 2 Construction Fixture System (Reference 4)
2. Lighting & TV System (see Construction Activity Data Sheet 3.1)
3. Beam-Builder Machine per Reference 1

TIMELINE 1.08 meters/minute (Reference 5); 5.31 min for 5.736 meters

POWER/ENERGY Beam Builder: 2.242 kW avg, 3.546 kW peak, 179.2 kJ/Bay, 125 kJ/M, .20 KWH/Beam. Lighting: 200 W. TV with heater 23 W avg, 33 W peak

CREW LOAD IVA: Approx. 0.5 man continuously monitoring EVA: 0


TECHNOLOGY DEVELOPMENT REQUIREMENTS Development of beam builder


## ACTIVITY 9.1

### CONSTRUCTION ACTIVITY DATA SHEET ATTACHMENT 1 (Page 1 of 3)

#### 9.1 FABRICATE TRANSVERSE BEAM NO. 1

The following two pages illustrate proposed modifications of the baseline spacing of cross-members on the General Dynamics Space Fabricated Beam - at the ends of the transverse beams. The modifications are necessary to prevent interferences of ends of the transverse beams with each other or with the cross beams when all three of the beams are in the same plane at a given frame station along the longitudinals. Note that one side of the transverse beam end also has the last cross-member and the diagonal cords omitted. This prevents interference with the diagonal cords on the longitudinal beam at the interface.

<b>J. ROEBUCK</b> PREPARED BY:	Space Systems Group  <b>Rockwell International</b>	PAGE NO.      OF
CHECKED BY:		ACTIVITY REPORT NO.    9.1
DATE: NOV. 20, 1979	FABRICATE TRANSVERSE BEAM NO. 1	MODEL NO. ETV P
REF.	<div data-bbox="621 380 1216 417" data-label="Section-Header">           ATTACHMENT 1 (PG 2 OF 3)         </div> <div data-bbox="487 511 1308 1908" data-label="Diagram"> </div> <div data-bbox="1274 729 1465 1734" data-label="Text"> <p>             DIMENSIONS:              MILLIMETERS              ATTACHMENT 1 (PAGE 2 OF 3)              II.1 FABRICATE TRANSVERSE BEAM NO. 1              DIMENSIONAL MODIFICATIONS-END BAY           </p> </div>	


<b>J. ROEBUCK</b> PREPARED BY:		Space Systems Group  <b>Rockwell International</b>	PAGE NO.      OF
CHECKED BY:			ACTIVITY REPORT NO.      9.1
DATE: NOV. 20, 1979		FABRICATE TRANSVERSE BEAM NO. 1	
REF.		MODEL NO.      ETVP	
		DWG. NO.	

ATTACHMENT 1 (PG. 3 OF 3)


  


RI TRI-BEAM CONF.  
WITH MODIFICATIONS  
TO GDS BEAM  
MACHINE SPECS.



$A = 20 \left( \frac{25}{32} \right)$   
 NOMINAL CLEARANCE  
 AT REGULAR  
 INTERSECTION -  
 ATTACHMENT 1 (P. 3 OF 3)  
 DUCK 9/16/79



PREPARED BY:	Space Systems Group  Rockwell International	PAGE NO.	OF
CHECKED BY:		ACTIVITY 9.1 REPORT NO.	
DATE:	FABRICATE TRANSVERSE BEAM	MODEL NO.	ETVP
REF.	ATTACHMENT 2	DWG. NO.	




ACTIVITY 9.2

CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

ACTIVITY



REFERENCE DATA

1. Space Construction Data Base
2. Drawing 42662-45, Rockwell Tri-Beam Concept, ETVP
3. Drawing 42662-52, No. 2 Construction Station

DESCRIPTION OF ACTIVITY

Two intersection fittings are automatically positioned and welded to the transverse beam at Construction Station No. 2. Activity is typical for all transverse beams and crossbeams.

CONSTRUCTION SUPPORT EQUIPMENT

Applicator for intersection fitting (see Attachment 1)

TIMELINE

38 seconds (see Attachment 2). *NOTE: This occurs in parallel with beam building. No additional time is consumed.*

POWER/ENERGY

Peak power, 1.0 kW; average power, 0.795 kW; energy, 30.2 kJ  
(see Attachments 2 and 3)

CREW LOAD

None

PRECEDING PAGE BLANK NOT FILMED

TECHNOLOGY DEVELOPMENT REQUIREMENTS

Material and welding techniques for intersection fittings


## ACTIVITY 9.2

### ATTACHMENT 2


Time, Power, and Energy Estimate for Joining of Intersection Fitting to Crossbeam No. 1

TASK DESCRIPTION	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
1. CROSSBEAM ADVANCES TO FIRST INTERSECTION POSITION.	N/A	N/A	N/A	N/A
2. PLUNGER DESCENDS WITH INTERSECTION FITTING AND CLAMPS IT TO THE CROSSBEAM.	2	-	0.025	0.05
3. WELD INTERSECTION FITTING TO CROSSBEAM. MEANWHILE, THE BELTS ON THE APPLICATOR ADVANCE THE SPACE OF ONE FITTING.	15	1	1	15
4. RETRACT THE PLUNGER AND GRASP THE NEXT FITTING IN THE STACK.	2	-	0.025	0.05
REPEAT STEPS 1, 2, 3, AND 4 TO JOIN THE SECOND FITTING TO THE CROSSBEAM.	19	1	-	15.1
NOTE: These operations each occur while the beam builder is halted for 40 seconds to install a crossmember.				
TOTAL	38	1*	0.795**	30.2
*PEAK POWER SUMMARY IS BASED UPON PEAK POWER OF INDIVIDUAL ACTIVITIES, SUBJECTIVELY ESTIMATED, BEING PERFORMED SIMULTANEOUSLY.				
**AVERAGE POWER = $\frac{\text{TOTAL ENERGY}}{\text{TOTAL ACTIVITY TIME}}$				

PREPARED BY:	Satellite Systems Division Space Systems Group	Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:			ACTIVITY 9.2
DATE:	JOIN INTERSECTION FITTINGS TO TRANSFERSE BEAM (NO. 1)		MODEL NO. ETVP
REF.	ATTACHMENT NO. 1		DWG. NO.



FORM 994-B-1 REV 12-78

PREPARED BY: Roebuck	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:		ACTIVITY 9.2
DATE: 1/24/80	JOIN INTERSECTION FITTINGS TO TRANSVERSE BEAMS	MODEL NO. ETVP
		DWG. NO.

ATTACHMENT 3

ENERGY ANALYSIS OF FUSION BONDING OF INTERSECTION FITTING TO CROSSBEAM OR TRANSVERSE BEAM


- Assume specific heat of material: 0.35  
 Energy rate to heat:  $0.35 \text{ 1 Btu/lb/}^{\circ}\text{F} = 0.35 \text{ Btu/lb/}^{\circ}\text{F}$
- Assume density of material is  $0.05 \text{ lb/in}^3$
- Volume estimation:  
 Since heating and clamping is performed under closely controlled conditions, only a small area of bond is required (as compared to later bonding to the longitudinal beams where pressure is applied by beam positioner). Assume actual heated volume is four spots, each  $2 \text{ in.} \times 2 \text{ in.} \times 1/8 \text{ in.}$   
 Volume is  $4 \times 2 \times 2 \times 1/8 = 2 \text{ in}$
- Weight is  $0.05 \times 2 = 0.10 \text{ lb}$   
 ∴ Energy per  $^{\circ}\text{F} = 0.10 \times 0.35 = 0.035 \text{ Btu/}^{\circ}\text{F}$
- Assume temperature rise of  $200^{\circ}\text{F}$
- Energy required is  $200 \times 0.035 = 7 \text{ Btu}$  at 100% efficiency  
 One Btu = 0.2931 watt-hour (Wh)  
 ∴  $7 \text{ Btu} = 2.05 \text{ Wh}$
- Assume 50% heating efficiency. Then, energy required is  $2 \times 2.05 = 4.1 \text{ Wh}$  or  $4.1 \times 60 = 246 \text{ watt-min.}$   
 Assume heating is done in 15 sec = 0.25 min.
- Power =  $\frac{246}{0.25} = 984 \text{ watts}$ , say 1000 watts for working number

## ACTIVITY 10.0

### CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

#### ACTIVITY



#### REFERENCE DATA

1. Space Construction Data Base
2. Drawing 42662-50, Construction Fixture Assembly
3. Drawing 42662-55, EVA Work Station
4. Convair Division of General Dynamics, *Space Construction Automated Fabrication Experiment Definition Study (SCAFEDS), Part III, Mid-Term Briefing*, CASD-AS78-013, 13 December 1978 (describes beam-builder machine).
5. *Space Shuttle System Payload Accommodations, Level II Program Definition and Requirements*, Volume XIV, JSC 07700, Rev. F, August 17, 1979.
6. *Performance Specification Manipulator Arm, Shuttle RMS*, SPAR-SG 366, Issue F, May 1978, Corrections through April 1979.

#### DESCRIPTION OF ACTIVITY

The modified RMS grasps and transports a transverse beam from Work Station No. 2 to within "capture range" of the beam positioner at Work Station No. 1 (see Attachment 1), releases the beam, and returns (as shown in Attachments 1 through 4). The beam positioner receives the transverse beam for joining to the longitudinal beams. The RMS is under control of the IVA operator. However, during the last five minutes an EVA astronaut will provide verbal/visual feedback.

ACTIVITY 10.0 (Cont.)

CONSTRUCTION SUPPORT EQUIPMENT

1. Beam-builder machine (Reference 5)
2. Modified orbiter RMS with upper arm roll joint and special end effector (Reference 6)
3. Tri-beam construction fixture (Reference 3)

TIMELINE

41 minutes (see Attachments 4 and 5)

POWER/ENERGY

Peak power, 2.25 kW; average power, 1.6 kW; total energy, 3950 kJ  
(see Attachment 5)

CREW LOAD

IVA: 1.0 man, 41 minutes

EVA: 1.0 man, 5 minutes

TECHNOLOGY DEVELOPMENT REQUIREMENTS

1. Roll joint for RMS upper arm ( $\pm 100$  degrees)
2. RMS end effector for grasping transverse beam
3. Beam positioner and position sensing system

PREPARED BY:

Satellite Systems Division  
Space Systems Group



Rockwell  
International

PAGE NO. 1 OF 1

CHECKED BY:

ACTIVITY 10.0


DATE:

TRANSPORT TRANSVERSE BEAM (NO. 1) AND POSITION  
FOR JOINING


MODEL NO. ETVP

DWG. NO.


ATTACHMENT 1





PREPARED BY:	Satellite Systems Division Space Systems Group	 <b>Rockwell International</b>	PAGE NO. 1 OF 1
CHECKED BY:			ACTIVITY 10.0
DATE:	TRANSPORT TRANSVERSE BEAM (NO. 1) AND POSITION FOR JOINING		MODEL NO. ETVP
			DWG. NO.

ATTACHMENT 2



PREPARED BY: C. FRITZ

Satellite Systems Division  
Space Systems Group



Rockwell  
International

PAGE NO. 1 OF 1

CHECKED BY:

ACTIVITY 10.0

DATE: 11-28-79

TRANSPORT TRANSVERSE BEAM (NO. 1) AND  
POSITION FOR JOINING

MODEL NO. ETVP



DWG. NO.

ATTACHMENT 3

RMS JOINT INITIAL  
SET-UP ANGLES

JOINT LEGEND


1. SHOULDER YAW
2. SHOULDER PITCH
3. UPPER ARM ROLL
4. ELBOW PITCH
5. WRIST PITCH
6. WRIST YAW
7. WRIST ROLL



FORM 994-R-1 REV 12-78

ATTACHMENT 4

TRANSPORT TRANSVERSE BEAM (NO. 1) AND POSITION FOR JOINING--SINGLE JOINT DRIVE MODE  
ACTIVITY 10.0

INITIAL SETUP ANGLES 	JOINT 1	JOINT 2	JOINT 3	JOINT 4	JOINT 5	JOINT 6	JOINT 7
	$\alpha = 10^\circ$ YAW	$\beta = 20^\circ$ PITCH	$\gamma = 0^\circ$ ROLL	$\delta = 10^\circ$ PITCH	$\epsilon = 99^\circ$ PITCH	$\theta = 0^\circ$ YAW	$\lambda = 0^\circ$ ROLL
TRANSPORT STEPS							
1							
2	100°	10°	150°	60°	10°		150°
3							
4							
5							
6							
7							
JOINT RATES (DEGREES/MINUTE)	13.74	13.74	13.74	19.26	28.56	28.56	28.56
TIME (MINUTES)	7.28	0.73	10.92	3.89	0.35	-	5.25
$\Sigma$ TIME (MINUTES)	7.28	8.01	18.93	22.82	23.17	23.17	28.42

ACTIVITY 10.0  
ATTACHMENT 5  
TIME AND POWER SUMMARY


ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. PWR. (kW)	ENERGY (kJ)
1. MOVE RMS TO POSITION	60	0.845 1.050†	0.845 0.525†	50.7 31.5
2. GRASP COMPLETED BEAM WITH RMS, RELEASE BEAM FROM BEAM BUILDER	180	0.845 1.050†	0.845 0.525†	152.1 94.5
3. TRANSPORT BEAM WITH RMS FROM BEAM BUILDER TO ASSEMBLY FIXTURE BEAM POSITIONER "ACCEPTANCE" LOCATION	1680	0.845 1.050†	0.845 0.525†	1419.6 882.0
4. GRASP BEAM WITH BEAM POSITIONER; RELEASE RMS	120	0.845 1.050† 0.100††	0.845 0.525† 0.100††	101.4 63.0 12.0
5. RETURN RMS TO BEAM BUILDER LOCATION (USE 25% OF ITEM 3)	420	0.845 1.050†	0.845 0.525†	354.9 220.5
SIMULTANEOUS OPERATIONS (NON-ADDITIVE) LIGHTS, TV CAMERAS & HEATERS	(2460)	0.173 0.80	0.173 0.057	425.6 140.2
TOTALS	2460	2.248*	1.605**	3948
<p>*PEAK POWER AND SUMMARY BASED UPON PEAK POWER OF INDIVIDUAL ACTIVITIES SUBJECTIVELY ESTIMATED BEING PERFORMED SIMULTANEOUSLY.</p> <p>**AVERAGE POWER = <math>\frac{\text{ENERGY SUMMARY}}{\text{TOTAL ACTIVITY TIME}}</math></p> <p>†HEATER ††BEAM POSITIONER</p>				

## ACTIVITY 11.1

### CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

#### ACTIVITY



#### REFERENCE DATA

1. Drawing 42662-45, Rockwell Tri-Beam Concept, ETVP
2. Space Construction Data Base
3. Drawing 42662-50, Tri-Beam Construction Fixture
4. Drawing 42662-55, EVA Work Station

#### DESCRIPTION OF ACTIVITY

The activity begins after the beam positioner has grasped the transverse beam and the RMS has released it. The EVA astronaut waits until the RMS is clear of the area (approximately 30 sec), then activates the beam positioner (which automatically maneuvers the beam to joining position), and hold a slight closing pressure so the intersection fittings press firmly against the longitudinal beams (see Attachment 1). The EVA astronaut maneuvers to one joint, connects electrical power to fuse the bonding material of the intersection fitting at the interface to the longitudinal beam, and then does the same for the opposite joint. After the bond has cooled, the astronaut activates the beam positioner to exert a predetermined outward load to test the joint, releases and retracts the beam positioner, and then rotates and extends it to "ready" position for the next beam joining. This activity is typical for all transverse beams and crossbeams.

#### CONSTRUCTION SUPPORT EQUIPMENT

1. Tri-beam construction fixture (Ref. 4), including beam positioner
2. Cherry picker or positioning arm
3. Lighting and TV system

#### TIMELINE

17 minutes per beam (see Attachment 2)

PRECEDING PAGE BLANK NOT FILMED

ACTIVITY 11.1 (Cont.)

POWER/ENERGY

Peak power, 1.9 kW; average power, 1.3 kW; total energy, 1360 kJ  
(see Attachment 2)

CREW LOAD

Intermittant IVA: 0.5 man  
EVA: one man, continuous

TECHNICAL DEVELOPMENT REQUIREMENTS


1. Development of material and methods for intersection fitting joining by electrical heating of interface material.
2. Control functions for beam positioner and EVA work station.
3. Modified open cherry picker compatible with limited work volume.

Roebuck/ PREPARED BY: Fritz	Satellite Systems Division Space Systems Group	Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:	JOIN TRANSVERSE BEAM TO LONGITUDINAL BEAM		ACTIVITY 11.1
DATE: 11 Dec. 1979			MODEL NO. ETVP
			DWG. NO. 42662-45

ATTACHMENT 1

INTERSECTION FITTING CONCEPT

The fitting is bonded to the transverse beam during fabrication and then to the longitudinal beam during joining of the transverse beam to the longitudinal beam. The activity is similar for joining crossbeams to longitudinal beams.



B-71

# ACTIVITY 11.1

## ATTACHMENT 2

Duration, Power, and Energy Estimations for Joining Transverse Beam to Longitudinal Beams

TASK DESCRIPTION	DURATION (sec)	PEAK PWR (kW)	AVG. PWR (kW)	ENERGY (kJ)
1. WAIT UNTIL RMS IS CLEAR	30 (a)	0.4 (b)	0.3	9
2. POSITION BEAM FOR JOINING	90	0.5	0.4	36
3. MANEUVER EVA WORK STATION AND CONNECT ELECTR. POWER. (c)	120	0.5	0.4	48
4. HEAT INTERS. FITTING (c)	300	1.3	1.3	390
5. MANEUVERS TO SECOND JOINT STATION AND CONNECT ELECTR. POWER (TIME NON-ADDITIVE)	(150)	0.5	0.4	60
6. WAIT UNTIL FIRST JOINT HEATED (TIME NON-ADD.)	(150)	0.4	0.3	45
7. HEAT INTERSECT. FITTING	300	1.3† 0.4††	1.3† 0.3††	480
8. POWER OFF, LEADS REMOVED	30	0.4	0.3	9
9. MANEUVER EVA WORK STATION TO NEUTRAL POSITION	60	0.5	0.4	24
10. WAIT FOR COOLING AND PERFORM LOAD TEST	60	0.5	0.4	24
11. RETRACT BEAM POSITIONER	30	0.5	0.4	12
12. LIGHTS & TV ON CONSTR. FIXTURE (TIME NON-ADD.)	(1020)	0.233	0.223	227
SUMMARY	1020	1.933*	1.334**	1364

†HEATING ††CHERRY PICKER

(a) RMS PWR IS LISTED IN CONSTR. ACTIVITY ANALYSIS 10.0; TIME FOR 10.0 OVERLAPS TIME FOR ACTIVITY 11.1 DURING THIS 30-SEC PERIOD.


(b) ASSUME LIGHTING POWER FOR ASTRONAUT DETAIL TASKS INCLUDED IN CHERRY PICKER POWER (WHICH IS ASSUMED AS 200 W)

(c) SEE ATTACHMENT 3 FOR HEATING POWER ANALYSIS

\*PEAK POWER SUMMARY BASED UPON PEAK POWER OF INDIVIDUAL ACTIVITIES SUBJECTIVELY ESTIMATED AS BEING PERFORMED SIMULTANEOUSLY.

\*\*AVERAGE POWER = ENERGY SUMMATION/TOTAL ACTIVITY TIME



PREPARED BY: ROEBUCK	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:		ACTIVITY 11.1
DATE:	JOIN TRANSVERSE BEAM (NO. 1) TO LONGITUDINAL BEAMS	MODEL NO. ETVP
		DWG. NO.

ATTACHMENT 3

ENERGY ANALYSIS OF FUSION BONDING FOR INTERSECTION FITTINGS

Assumed *specific heat* of material: 0.35

Actual energy rate to heat:  $0.35 \times 1 \text{ Btu/lb/}^\circ\text{F} = 0.35 \text{ Btu/lb/}^\circ\text{F}$

Assume  $0.05 \text{ lb/in.}^3$  density of material

$0.05 \times 50.75 \text{ in.}^3 \approx 2.54 \text{ lb weight}$

•• Energy per  $^\circ\text{F} = 2.54 \times 0.35 = 0.89 \text{ Btu/}^\circ\text{F}$

Assume *temperature rise*:  $200^\circ\text{F}$ . Energy is  $200 \times 0.89 = 178 \text{ Btu}$  to bond joint at 100-percent eff.  $1 \text{ Btu} = .2931 \text{ Wh}$ .

••  $178 \text{ Btu} = 52.2 \text{ Wh}$

Assume 50% efficiency input of heat. Then, energy required is 104 Wh, or  $104 \text{ Wh} \times 60 = 6240 \text{ W-min}$ . If heating is done in 5 minutes\*, power required is  $6240 \div 5 = 1248 \text{ W}$ , say 1.3 kW.

\_\_\_\_\_  
 \*Assumed reasonable waiting time for EVA astronaut, compatible with beam fabrication times.


ACTIVITIES 11.2 & 11.3

PRECEDING PAGE BLANK NOT FILMED

CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

ACTIVITY



REFERENCE DATA

1. Drawing 42662-45, Rockwell Tri-Beam Concept, Engineering and Technology Verification Platform
2. Space Construction Data Base
3. Drawing 42662-50, Tri-Beam Construction Fixture
4. Drawing 42662-55, EVA Work Station

DESCRIPTION OF ACTIVITY

After joining each transverse beam (or crossbeam), the EVA astronaut performs crossover and hookup of one pair of X-brace cords, according to crew positions and procedures in Attachments 1, 2, 3, and 4. (Note: beam positioner is first relocated to next joining position, thus providing astronaut maneuvering space.) Tensioning of each cord follows its hookup procedure. The first cord is tensioned to 6.4 N (15 lb), and the second cord is tensioned to the final load of 2355 N (530 lb), which creates the same load on the first cord. Tension is applied by a special torquing tool designed for use with the turnbuckle/hook device at the end of each X-brace cord (see Attachment 5). This activity is typical for all transverse beams and crossbeams, except the first and last frame set (see discussion, Attachment 1).

ACTIVITIES 11.2 AND 11.3  
(Cont.)

CONSTRUCTION SUPPORT EQUIPMENT

1. Tri-beam construction fixture (Reference 1)
2. X-brace cord dispensing system (See Attachment 1 and Reference 1 and 5)
3. Astronaut cherry picker and maneuvering arm (EVA work station) per Reference 5 and Attachment 1
4. Torque tool and turnbuckle device (see Attachment 4)

TIMELINE

Refer to Attachments 1 and 2; 16 minutes per pair of X-brace cords

POWER/ENERGY


Peak power, 0.5 kW; average power, 0.3 kW; energy, 314 kJ  
(see Attachment 6)

CREW LOAD

EVA: 1.0 man continuously  
IVA: None

TECHNOLOGY DEVELOPMENT REQUIREMENTS

1. Astronaut cherry picker and maneuvering arm
2. X-brace cord dispensing system
3. Torque tool and turnbuckle device

PREPARED BY: Roebuck	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:		ACTIVITY 11.2
DATE: 1/28/80	JOIN X-BRACE CORDS TO LEADING AND TRAILING EARS	MODEL NO. ETVP
		DWG. NO.

ATTACHMENT 1


DISCUSSION

The cross-brace cords are contained on six reels which are attached to the central structure of the construction fixture. The cords are prefabricated in segments of the appropriate length (plus a small allowance for takeup) to reach across the diagonal distance of a bay between frames. Each cord has a simple hook at one end which attaches to the so-called trailing ear of an intersection fitting. The other end of the cord has a combination hook and turnbuckle which is attached to the leading ear of another intersection fitting. The turnbuckle is actuated, as indicated in Attachment 4, to a desired tension prior to operation.

When the cords are wound around the reels, they are interconnected end-to-end by their hooks.

After joining the first transverse beam to the longitudinal beams, the EVA astronaut grasps the end of one cord from a reel and hooks it to the trailing ear of one of the intersection fittings. Then, he repeats this for the next intersection fitting. These actions are repeated for each of the three beams of the first frame set. When the platform assembly translates, it pulls the six cords out from their storage reels. Subsequently, the astronaut performs the activities, described in Attachment 3, as follows:

First, the hooks connecting the extended cord and the reeled cords are disconnected and retained under control of the astronaut on the cherry picker. A short length of tether is carried by the EVA astronaut for this purpose. The end of the cord, still wound on the reel, is attached to the trailing ear of the appropriate intersection fitting (Point B in Attachment 2). The tether is then released from this cord and the other cord end is carried across to the intersection fitting at the opposite side of the beam. There, it is hooked to the leading ear of the intersection fitting; then, the cord is tensioned. The tether is then released and the hookup sequence is repeated in the opposite sense. Thus, the two cords (which were unrolled during the translation of the assembly into a position roughly parallel to the longitudinal beams) are now crossed and fully tensioned in a plane parallel to the recently installed crossbeam or transverse beam. This sequence is repeated for each beam.


PREPARED BY: C. FRITZ	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:		ACTIVITIES 11.2, 11.3
DATE: 12/5/79	11.2 JOIN X-BRACE CORDS 11.3 TENSION X-BRACE CORDS	MODEL NO. ETVP
		DWG. NO.

ATTACHMENT 2


OPERATION	DISTANCE (FT)	TIME (MIN)
0. ASTRONAUT IN NEUTRAL POSITION	-	-
1. RELOCATE BEAM POSITIONER	-	1.00
2. GO TO POINT A	8.5	0.85
3. DISCONNECT TWO HOOKS	-	1.00
4. GO TO POINT B	3.0	0.30
5. CONNECT REEL CORD B	-	1.00
6. GO TO POINT F	10.0	1.00
7. CONNECT DIAGONAL CORD F	-	1.00
8. TENSION CORD F TO 14.4 LB	-	2.00
9. GO TO POINT D	1.7	0.17
10. DISCONNECT TWO HOOKS	-	1.00
11. GO TO POINT E	3.0	0.30
12. CONNECT REEL CORD E	-	1.00
13. GO TO POINT C	10.0	1.00
14. CONNECT DIAGONAL CORD C	-	1.00
15. TENSION CORD C TO 530 LB	-	2.00
16. GO TO NEUTRAL POSITION	10.0	1.00
TOTAL		15.62

NOTES

- 1 RATE OF ASTRONAUT MOVEMENT ESTIMATED TO BE 10 FT/MIN = 3.04 M/MIN
- 2 INSTALLATION OF X-BRACE CORD PAIRS H AND L, AND P AND S, TO BE SIMILAR TO ABOVE.

PREPARED BY:	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:		ACTIVITIES 11.2, 11.3
DATE:	11.2 JOIN X-BRACE CORDS 11.3 TENSION X-BRACE CORDS	MODEL NO. ETVP
		DWG. NO.


ATTACHMENT 3



FORM 994-B-1 REV 12-78

PREPARED BY:	Satellite Systems Division Space Systems Group	Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:			ACTIVITIES: 11.2 & 11.3
DATE:	11.2 JOIN X-BRACE CORDS 11.3 TENSION X-BRACE CORDS		MODEL NO. ETVP
			DWG. NO.

ATTACHMENT 4




VIEW A-A

(REF. ATTACHMENT NO. 1)


PREPARED BY:	Satellite Systems Division Space Systems Group	Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:			ACTIVITIES 11.2 & 11.3
DATE:	11.2 JOIN X-BRACE CORDS 11.3 TENSION X-BRACE CORDS		MODEL NO. ETVP
			DWG. NO.

ATTACHMENT 5


ORIGINAL PAGE IS  
OF POOR QUALITY



STEP 1  
ATTACH TENSIONER




STEP 2



STEP 3  
ACTUATE TENSIONING DRIVE SYSTEM



PREPARED BY:	Satellite Systems Division Space Systems Group	 Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:			ACTIVITIES: 11.2 & 11.3
DATE:	JOIN X-BRACE CORDS AND TENSION		MODEL NO. ETVP
			DWG. NO.

ATTACHMENT 6

DURATION, POWER, AND ENERGY ESTIMATIONS FOR ATTACHING AND TENSIONING X-BRACE CORDS

OPERATION	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
1. RELOCATE BEAM POSITIONER	60	0.5	0.4	24
2. GO TO POINT A	51	0.5	0.4	20
3. DISCONNECT TWO HOOKS	60	0.4	0.3	18
4. GO TO POINT B	18	0.5	0.4	7
5. CONNECT REEL CORD B	60	0.4	0.3	18
6. GO TO POINT F	60	0.5	0.4	24
7. CONNECT DIAG. CORD F	60	0.4	0.3	18
8. TENSION CORD F	120	0.4	0.3	36
9. GO TO POINT D	10	0.5	0.4	4
10. DISCONNECT TWO HOOKS	60	0.4	0.3	18
11. GO TO POINT E	18	0.5	0.4	7
12. CONNECT REEL CORD E	60	0.4	0.3	18
13. GO TO POINT C	60	0.5	0.4	24
14. CONNECT DIAG. CORD C	60	0.4	0.3	36
15. TENSION CORD C	120	0.4	0.3	36
16. GO TO NEUTRAL	60	0.5	0.4	24
SUMMARY	937	0.5*	0.33**	314

NOTE: POWER ESTIMATES INCLUDE 0.180 kW FOR LIGHTS ON CHERRY PICKER

\*PEAK POWER IS HIGHEST OF INDIVIDUAL TASK PEAKS


\*\*AVERAGE POWER =  $\frac{\text{ENERGY SUMMARY}}{\text{TOTAL ACTIVITY TIME}}$

## ACTIVITY 12.1

### CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

#### ACTIVITY



#### REFERENCE DATA

1. Space Construction Data Base
2. Drawing 42662-50, Construction Fixture
3. Drawing 42662-55, EVA Work Station
4. Convair Division of General Dynamics, *Space Construction Automated Fabrication Experiment Definition Study (SCAFEDS), Part III*, Mid-Term Briefing, CASD-AS78-013, 13 December 1978 (describes beam-builder machine).
5. *Space Shuttle System Payload Accommodations, Level II Program Definition and Requirements*, Volume XIV, JSC 07700, Revision F, August 17, 1979.
6. *Performance Specification Manipulator Arm, Shuttle RMS*, SPAR-SG 366, Issue F, May, 1978, Corrections through April 1979.

#### DESCRIPTION OF ACTIVITY

The modified RMS grasps and transports a transverse beam from Work Station No. 2 to within "capture range" of the beam positioner at Work Station No. 1, releases the beam, and returns (as shown in Attachments 1 through 4). The beam positioner receives the transverse beam for joining to the longitudinal beams. The RMS is under control of the IVA operator. However, during the last five minutes, an EVA astronaut provides verbal/visual feedback.

## ACTIVITY 12.1

### CONSTRUCTION SUPPORT EQUIPMENT

1. Beam-builder machine (Reference 5)
2. Modified orbiter RMS with upper arm roll joint and special end effector (Reference 6)
3. Tri-beam construction fixture (Reference 3)

### TIMELINE

30 minutes (see Attachments 4 and 5)

### POWER/ENERGY


Peak power, 2.25 kW; average power, 1.606 kW, energy 2892 kJ  
(see Attachment 5)

### CREW LOAD


IVA: 1.0 man, 30 minutes  
EVA: 1.0 man, 5 minutes

### TECHNOLOGY DEVELOPMENT REQUIREMENTS

1. Roll joint for RMS upper arm ( $\pm 100^\circ$ )
2. RMS end effector for grasping transverse beam
3. Beam positioner and position sensing system

PREPARED BY: C. FRITZ	Satellite Systems Division Space Systems Group	 Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:			ACTIVITY 12.1
DATE: 11-29-79	TRANSPORT TRANSVERSE BEAM NO. 2		MODEL NO. ETVP
			DWG. NO.

ATTACHMENT 1



TRANVERSE BEAM NO. 2

RMS

BEAM BUILDER

NO. 2 CONSTRUCTION STATION

The diagram is a perspective view of a complex space station structure. It features several long, truss-like beams extending horizontally. A central vertical structure is labeled 'RMS' (Remote Manipulator System). To the right, a large, multi-ported cylindrical component is labeled 'BEAM BUILDER'. The entire assembly is mounted on a base structure labeled 'NO. 2 CONSTRUCTION STATION'. Various cables and smaller components are visible throughout the structure.

B-85

FORM 324-B-1 REV 12-78

PREPARED BY:

Space Systems Group



Rockwell  
International

PAGE NO.

OF

CHECKED BY:

REPORT NO.


DATE:

MODEL NO.

REF.

DWG. NO.

ATTACHMENT 2



B-86

PREPARED BY: C.H. FRITZ

Space Systems Group



Rockwell  
International

PAGE NO. OF

CHECKED BY:

REPORT NO. 12.1

DATE:

11-29-79

TRANSPORT TRANSVERSE BEAM  
NO. 2 AND POSITION FOR JOINING

MODEL NO. ETVP

DWG. NO.



REF.

# ATTACHMENT No. 3

## RRIS JOINT INITIAL SETUP ANGLES

## JOINT LEGEND

1. SHOULDER YAW
2. SHOULDER PITCH
3. UPPER ARM ROLL
4. ELBOW PITCH
5. WRIST PITCH
6. WRIST YAW
7. WRIST ROLL



ATTACHMENT 4

ACTIVITY 12.1

TRANSPORT TRANSVERSE BEAM (NO. 2) AND POSITION FOR JOINING—SINGLE JOINT DRIVE MODE

INITIAL SETUP ANGLES →	JOINT 1	JOINT 2	JOINT 3	JOINT 4	JOINT 5	JOINT 6	JOINT 7
	$\alpha = 10^\circ$ YAW	$\beta = 20^\circ$ PITCH	$\gamma = 0^\circ$ ROLL	$\delta = 10^\circ$ PITCH	$\epsilon = 99^\circ$ PITCH	$\theta = 0^\circ$ YAW	$\lambda = 0^\circ$ ROLL
TRANSPORT STEPS							
1							
2		30°					
3							
4	20°						
5			30°				
6				50°			
7							
8	20°						
JOINT RATES (DEGREES/MINUTE) *	13.74	13.74**	13.74	19.26	28.56	28.56	28.56
TIME (MINUTES)	2.91	2.18	2.18	2.60	-	4.20	6.30
Σ TIME (MINUTES)	2.91	5.09	7.27	9.87	-	14.07	20.37

\*PER REFERENCE 6, pp. 3-39, JOINT RATE MAXIMUM.

\*\*ASSUMED VALUE FOR PROPOSED ADDITIONAL RMS JOINT.

ACTIVITY 12.1  
ATTACHMENT 5  
TIME AND POWER SUMMARY

ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. PWR. (kW)	ENERGY (kJ)
1. MOVE RMS TO POSITION				
2. GRASP COMPLETED BEAM WITH RMS, RELEASE BEAM FROM BEAM BUILDER	180	0.845 1.050†	0.845 0.525†	152.1 94.5
3. TRANSPORT BEAM WITH RMS FROM BEAM BUILDER TO ASSEMBLY FIXTURE BEAM POSITIONER "ACCEPTANCE" LOCATION	1200	0.845 1.050†	0.845 0.525†	1014.0 630.0
4. GRASP BEAM WITH BEAM POSITIONER; RELEASE RMS	1200	0.845 1.050† 0.100††	0.845 0.525† 0.100††	101.4 63.0 12.0
5. RETURN RMS TO BEAM BUILDER LOCATION (USE 25% OF ITEM 3)	300	0.845 1.050†	0.845 0.525†	253.5 157.5
SIMULTANEOUS OPERATIONS (NON-ADDITIVE) LIGHTS, TV CAMERAS & HEATERS	(1800)	0.173 0.80	0.173 0.057	311.4 102.6
TOTALS	1800	2.248*	1.606**	2892.0
*PEAK POWER AND SUMMARY BASED UPON PEAK POWER OF INDIVIDUAL ACTIVITIES, SUBJECTIVELY ESTIMATED, BEING PERFORMED SIMULTANEOUSLY.				
**AVERAGE POWER = $\frac{\text{ENERGY SUMMARY}}{\text{TOTAL ACTIVITY TIME}}$				
†HEATER ††BEAM POSITIONER				




PRECEDING PAGE BLANK NOT FILMED

ACTIVITY 12.2

CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

ACTIVITY



REFERENCE DATA

1. Convair Division of General Dynamics, *Space Construction Automated Fabrication Experiment Definition Study (SCAFEDS)*, Part III Mid-Term Briefing, CASD-AS78-013, 13 December 1978 (describes beam-builder machine).
2. Drawing 42662-45, Rockwell Tri-Beam Concept, ETVP
3. Space Construction Data Base
4. Drawing 42662-72, Attach Port
5. Drawing 42662-52, No. 2 Construction Station
6. Construction Activity Data Sheet: 12.3—*Install Attachment Ports*

DESCRIPTION OF ACTIVITY

Begins with initial heating of cap material and continues until cutoff of beam and separation from beam machine a sufficient distance to permit joining of attachment port on end (per References 4, 5, and 6). Fabrication methods are discussed in Reference 1, with modifications per Attachment 1 (pertinent to end stub length). Beam is supported at Work Station No. 2 construction fixture per Reference 5 (see Attachment 2). Beam fabrication rates are per Reference 1, but first joining of attachment port and joining of two intersection fittings interrupt beam building. The basic fabrication activity is typical for all crossbeams, but timelines vary for short and long crossbeams.

## ACTIVITY 12.2 (Cont.)

### CONSTRUCTION SUPPORT EQUIPMENT

1. Work station No. 2 construction fixture system (Reference 5)
2. Lighting and TV system (see Construction Activity Data Sheet 3.1)
3. Beam-builder machine (per Reference 1)

### TIMELINE (see Section 5.3)

1.08 meters/minute (Reference 5); 16.1 minutes for 17.4 meters  
(long crossbeam); 7.8 minutes for 8.4 meters (short crossbeam)

### POWER/ENERGY (see Section 5.3)

Beam builder: 2.242 kW, average; 3.546 kW, peak; 179.2 kJ/bay;  
2509 kJ for long crossbeam, 1075 kJ for short crossbeam

Lighting: 200 W

TV with heater: 23 W average, 33 W peak

### CREW LOAD

IVA: Approximately 0.5 man continuously monitoring

EVA: None

### TECHNOLOGY DEVELOPMENT REQUIREMENTS

Development of beam builder

J. ROEBUCK

PREPARED BY:

Space Systems Group



Rockwell  
International

PAGE NO. OF

CHECKED BY:

ACTIVITY 12.2  
REPORT NO.

DATE: 4 DEC 1979

FABRICATE CROSS BEAM


MODEL NO. ETVP

DWG. NO.

REF.

ATTACHMENT 1

BEAM END MODIFICATION TO GENERAL  
DYNAMICS FABRICATED BEAM BASELINE  
(TYPICAL FOR LONG AND SHORT CROSS BEAMS)



FORM 994-B-1 REV 12-78

PREPARED BY: ROEBUCK

Satellite Systems Division  
Space Systems Group



Rockwell  
International

PAGE NO. 1 OF 1

CHECKED BY:

ACTIVITY 12.2


DATE: 12/4/79

FABRICATE CROSSBEAM

MODEL NO. ETVP

DWG. NO.

ATTACHMENT 2




### ACTIVITY 12.3

#### CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

#### ACTIVITY



#### REFERENCE DATA

1. Drawing 42662-52, No. 2 Construction Station
2. Drawing 42662-72, Attach Port
3. Space Construction Data Base
4. Convair Division of General Dynamics, *Space Construction Automated Fabrication Experiment Definition Study (SCAFEDS), Part III, Mid-Term Briefing, CASD-AS78-013, 13 December 1978*
5. Construction Activity Data Sheet: 3.2, *Install Attachment Ports on Longitudinal Beam No. 1*

#### DESCRIPTION OF ACTIVITY (see Attachments)

The activity consists of installing an attachment port at each end of the crossbeam during construction at Work Station No. 2 as shown in Reference 2. This activity is identical for both long and short crossbeams. The attach ports for the long crossbeams are designed to mate with payloads; therefore, they are equipped with electrical connections. The connector interface to the crossbeam electrical lines is mechanized for remote actuation. (see Attachment 2). The two types of attach ports are stacked in the sequence required on the attach port magazine.

The function begins with rotating an installation device (loaded with attachment port) into alignment with the beam machine after a short section of beam is fabricated. Then, the legs of the attachment port are inserted into the beam caps, as shown in Reference 2, and welded in place. The weld is load-tested and the port is released; then, the installation device is rotated out of alignment and reloaded with the second attachment port. After the crossbeam is fabricated, cut off, and translated axially away from the beam builder machine, installation of the second port is performed in a manner similar to that for the first—but in opposite direction of motion. The function is complete when the installation device is rotated out of alignment with the beam.



### ACTIVITY 12.3

#### CONSTRUCTION SUPPORT EQUIPMENT

1. No. 2 construction station structural support elements
2. Attach port magazine and installation mechanisms
3. Beam builder
4. TV camera and lights
5. Controls and display systems for operation of installation device for attachment ports

#### TIMELINE

First Port: 4.12 minutes (interrupts beam fabrication 2.28 minutes)  
Second Port (after beam fabrication): 3.86 minutes  
Total time for port installation: 7.98 minutes (see Reference 5 for timeline details)

#### POWER/ENERGY

IVA: One person, continuously, during each installation sequence  
EVA: None

#### TECHNOLOGY DEVELOPMENT REQUIREMENTS

- Development of space-qualified installation and load testing devices for attachment ports.
- Resistance heating of intermediate filler material for welding of composite materials without active clamping.

PREPARED BY:

Satellite Systems Division  
Space Systems Group



Rockwell  
International

PAGE NO. 1 OF 1

CHECKED BY:

ACTIVITY 12.3

DATE:

INSTALL ATTACH PORTS (TO CROSSBEAM NO. 1)


MODEL NO. ETVP

DWG. NO.

ATTACHMENT 1

ATTACH PORT INSTALLATION  
DEVICE

BEAM BUILDER



PREPARED BY:	Satellite Systems Division Space Systems Group	PAGE NO. 1 OF 1
CHECKED BY:	Rockwell International	ACTIVITY 12.3
DATE:	INSTALLATION OF ATTACHMENT PORTS TO CROSS BEAMS	MODEL NO. ETVP
REF.	<div data-bbox="708 366 1010 447" data-label="Section-Header"> <p>ATTACHMENT 2</p> </div> <div data-bbox="434 497 1529 1991" data-label="Diagram"> </div> <div data-bbox="899 2042 968 2074" data-label="Text"> <p>B-98</p> </div>	




ACTIVITY 12.4

CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING TECHNOLOGY VERIFICATION PLATFORM (ETVP)

ACTIVITY



REFERENCE DATA

1. Space Construction Data Base
2. Drawing 42662-52, Number 2 Construction Station
3. Drawing 42662-56, Electric Cable-Laying Machine

DESCRIPTION OF ACTIVITY

At No. 2 Construction Station the electrical lines and connectors are automatically installed on the crossbeam as it is fabricated, as described in Attachment 1, and shown on Attachments 3 and 4.

CONSTRUCTION SUPPORT EQUIPMENT

1. Electrical line reel and installation machine
2. Controls and displays for electrical line installation

TIMELINE

Lay electrical lines at 1.08 m/sec (see Attachment 2)


POWER/ENERGY

Average power, 0.012 kW; peak power, 0.02 kW; energy 0.6 kJ  
(see Attachment 2)

CREW LOAD: None

TECHNOLOGY DEVELOPMENT REQUIREMENTS

Design and development of electrical cable-laying machine

PREPARED BY:	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:		ACTIVITY 12.4
DATE:	INSTALL ELECTRICAL LINES CROSSBEAM (NO. 1)	MODEL NO. ETVP
		DWG. NO.

ATTACHMENT 1

ELECTRICAL LINE REEL AND INSTALLATION MACHINE

The general configuration of a machine for dispensing and installing electrical lines and connectors onto the crossbeams is shown in Attachment 3. There are two drums—one for the power lines and one for the data lines. Each drum contains seven assembled cables, i.e., the full complement for the platform. The seven cables are loaded end to end in the continuous bandolier which takes the cables from the drum and presents them to the installation stations. The reason for loading the cables into a bandolier is to overcome the problems of feeding a discontinuous item such as seven unconnected cables. The bandolier is wound in a helix around the drum, one layer deep. It leaves the drum, passes around a fixed location pulley, and returns to rewind on the drum. The drums must move outward as they rotate to accommodate the passage of the helically wound bandoliers.

Each cable assembly consists of 20 m of line with a connector at each end and clips spaced at intervals to secure the line to the crossmembers of the crossbeam (Reference: Drawing 42662-56).

As the cable assembly on the bandolier moves from the drum toward the fixed location pulley, the front connector is stripped from the bandolier by the end connector installation station. The beam halts and the connector is mated with the unit preinstalled on the front end of the beam.

The beam continues to advance as it is manufactured by the beam builder. Each bay of the beam takes 80 seconds to build—40 seconds moving and 40 seconds stationary, while the crossmembers are welded onto the beam caps. The cable machine is positioned relative to the beam builder so that during the 40-second pause the clip installation station is opposite the crossmember on which a clip is due to be secured. The clips are part of the cable assembly and are secured to the crossmembers by Velcro.

The rear connector is installed by the end connector installation station in the same fashion as the front connector.

# ACTIVITY 12.4


## ATTACHMENT 2

Time, Power, and Energy Estimate for Installing Electrical Lines on Crossbeam No. 1


Task	Duration (Secs)	Peak Power (kW)	Avg Power (kW)	Energy (kJ)
1. Build short section of beam	5	.02	.02	.1
2. Add end attach port #1				
3. Advance beam				
4. Plug in the connectors at end attach port #1 and retract the arms	40	.01	.01	.4
5. Advance and build remainder of beam. Total beam build time = (14x80) + 40 = 1160 seconds Note: Line laying proceeds with beam advance. Line clips and intersection fittings are installed while beam is halted for crossmember joining				
6. Add end attach port #2				
7. Advance beam to connector installation station	5	.02	.02	.1
8. Plug in the connectors at end attach port #2 and retract the arms				
Additional Serial Time	50	.02**	.012*	.6

\*Average power =  $\frac{\text{energy summary}}{\text{total activity time}}$

\*\*Peak power and summary based upon peak power of individual activities, subjectively estimated, being performed simultaneously.

PREPARED BY:	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:		ACTIVITY 12.4
DATE:	INSTALL ELECTRICAL LINES ON CROSSBEAM	MODEL NO. ETVP
		DWG. NO.

ATTACHMENT 3



PREPARED BY:

Satellite Systems Division  
Space Systems Group



Rockwell  
International

PAGE NO. 1 OF 1

CHECKED BY:

ACTIVITY 12.4


DATE:

INSTALL ELECTRICAL LINES ON CROSSBEAM

MODEL NO. ETVP

DWG. NO.

ATTACHMENT 4




ACTIVITY 13.0

PRECEDING PAGE BLANK NOT FILMED

CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

ACTIVITY



REFERENCE DATA

1. Space Construction Data Base
2. Drawing 42662-50, Construction Fixture
3. Drawing 42662-55, EVA Work Station
4. Convair Division of General Dynamics, *Space Construction Automated Fabrication Experiment Definition Study (SCAFEDS), Part III*, Mid-Term Briefing, CASD-AS78-013, 13 December 1978 (describes beam-builder machine)
5. *Space Shuttle System Payload Accommodations Level II Program Definition and Requirements*, Volume XIV, JSC 07700, Revision F, August 17, 1979
6. *Performance Specification Manipulator Arm, Shuttle RMS*, SPAR-SG 366, Issue F, May 1978, Corrections through April 1979

DESCRIPTION OF ACTIVITY

The modified RMS grasps and transports a crossbeam from Work Station No. 2 to within "capture range" of the beam positioner at Work Station No. 1, releases the beam, and returns as shown in Attachments 1 through 4. The beam positioner receives the crossbeam for joining to the longitudinal beams. The RMS is under control of the IVA operator. However, during the last five minutes, an EVA astronaut provides verbal/visual feedback.

## ACTIVITY 13.0

### CONSTRUCTION SUPPORT EQUIPMENT

1. Beam-builder machine (Reference 4)
2. Modified orbiter RMS with upper arm roll joint and special end effector (Reference 5)
3. Tri-beam construction fixture (Reference 2)

### TIMELINE

Refer to Attachments 4 and 5. Time required: 33.4 minutes.

### POWER/ENERGY

Peak power, 2.25 kW; average power, 1.606 kW; energy, 3218 kJ  
(see Attachment 5)

### CREW LOAD


IVA: 1.0 man, 44 minutes  
EVA: 1.0 man, 5 minutes

### TECHNOLOGY DEVELOPMENT REQUIREMENTS

1. Roll joint for RMS upper arm ( $\pm 100$  degrees)
2. RMS end effector for grasping transverse beam
3. Beam positioner control and position sensing system


PREPARED BY:	Satellite Systems Division Space Systems Group	 Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:			ACTIVITY 13.0
DATE:	TRANSPORT CROSSBEAM TO CONSTRUCTION FIXTURE AND POSITION FOR JOINING		MODEL NO. ETVP
			DWG. NO.

ATTACHMENT 1




FORM 994-B-1 REV 12-78



PREPARED BY:	Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:		ACTIVITY 13.0
DATE:	TRANSPORT CROSSBEAM TO CONSTRUCTION FIXTURE AND POSITION FOR JOINING	MODEL NO. ETVP
		DWG. NO.

ATTACHMENT 2



B-108

PREPARED BY: C.H. FRIEZ

Space Systems Group



Rockwell  
International

PAGE NO. 1 OF 1

CHECKED BY:

ACTIVITY 13.0

DATE: 11-27-77

TRANSPORT CROSSBEAM TO CONSTRUCTION FIXTURE  
AND POSITION FOR JOINING

MODEL NO. ETVP



REF.

DWG. NO.

ATTACHMENT 3

RMS JOINT INITIAL CONDITIONS

1. SHOULDER YAW
2. SHOULDER PITCH
3. UPPER ARM ROLL
4. ELBOW PITCH
5. WRIST PITCH
6. WRIST YAW
7. WRIST ROLL



ATTACHMENT 4

ACTIVITY 13.0

TRANSPORT CROSSBEAM TO CONSTRUCTION FIXTURE AND POSITION FOR JOINING--SINGLE JOINT DRIVE MODE

INITIAL SETUP ANGLES TRANSPORT STEPS	JOINT 1	JOINT 2	JOINT 3	JOINT 4	JOINT 5	JOINT 6	JOINT 7
	$\alpha = 45^\circ$ YAW	$\beta = 40^\circ$ PITCH	$\gamma = 0^\circ$ ROLL	$\delta = 50^\circ$ PITCH	$\epsilon = 80^\circ$ PITCH	$\theta = 0^\circ$ YAW	$\lambda = 0^\circ$ ROLL
1		10°		50°			180°
2			90°				45°
3					30°	30°	
4	10°						
5				20°	10°		
6							
7		10°					
8							
9	10°						
10							
TOTALS	20°	20°	90°	70°	40°	30°	225°
JOINT RATES (DEGREES/MINUTE) *	13.74	13.74	13.74**	19.26	28.56	28.56	28.56
TIME (MINUTES)	1.46	1.46	6.55	3.63	1.40	1.05	7.88
$\Sigma$ TIME (MINUTES)	1.46	2.92	9.47	13.10	14.50	15.55	23.43

\*REF. 6, p. 3-39; \*\*ASSUMED VALUE FOR ADDITIONAL RMS JOINT

ATTACHMENT 5  
ACTIVITY 13.0  
TIME AND POWER SUMMARY

ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. PWR. (kW)	ENERGY (kJ)
1. MOVE RMS TO POSITION	-	-	-	-
2. GRASP COMPLETED BEAM WITH RMS, RELEASE BEAM FROM BEAM BUILDER	180	0.845 1.050†	0.845 0.525†	152.1 94.5
3. TRANSPORT BEAM WITH RMS FROM BEAM BUILDER TO ASSEMBLY FIXTURE BEAM POSITIONER "ACCEPTANCE" LOCATION	1404	0.845 1.050†	0.845 0.525†	1186.4 737.1
4. GRASP BEAM WITH BEAM POSITIONER; RELEASE RMS	120	0.845 1.050† 0.100††	0.845 0.525† 0.100††	101.4 63.0 12.0
5. RETURN RMS TO BEAM BUILDER LOCATION (USE 25% OF ITEM 3)	300	0.845 1.050†	0.845 0.525†	253.5 157.5
SIMULTANEOUS OPERATIONS (NON-ADDITIVE) LIGHTS, TV CAMERAS & HEATERS	(2004)	0.173 0.80	0.173 0.057	346.7 114.2
TOTALS	2004	2.248*	1.606**	3218.4
*PEAK POWER AND SUMMARY BASED UPON PEAK POWER OF INDIVIDUAL ACTIVITIES SUBJECTIVELY ESTIMATED BEING PERFORMED SIMULTANEOUSLY.				
**AVERAGE POWER = $\frac{\text{ENERGY SUMMARY}}{\text{TOTAL ACTIVITY TIME}}$				
†THEATER ††BEAM POSITIONER				

PRECEDING PAGE BLANK NOT FILMED

ACTIVITY 14.0

CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

ACTIVITY

14.0 Connect electr.  
lines from Crossbeam  
to Longitudinal Beam

15.0 Translate  
Struct. Assembly  
One Bay Length

REFERENCE DATA

1. Space Construction Data Base
2. Drwing 42662-45, Rockwell Tri-Beam Concept, ETVP
3. Drawing 42662-50, Construction Fixture
4. Drawing 42662-55, EVA Work Station

DESCRIPTION OF ACTIVITY (see Attachments 1, 2, and 3)

After the completion of a full bay with a long crossbeam, the electrical interface between the wiring cables on the longitudinal beam and crossbeam is accomplished by an EVA astronaut manually moving wire cable pigtails from stowed positions on the crossbeam and joining the cable connectors to mating connectors located on the longitudinal beam, as shown in Attachment 2.

CONSTRUCTION SUPPORT EQUIPMENT

1. Tri-beam construction fixture (Reference 3)
2. EVA work station (Reference 4)
3. Lighting
4. Self-powered electrical connectors

TIMELINE

14 minutes (see Attachment 5)

POWER/ENERGY (see Attachment 5)


Peak power, 0.5 kW; average power, 0.4 kW; energy, 336 kJ;  
includes 0.18 kW for lights on cherry picker.

CREW LOAD

One EVA astronaut continuously

DEVELOPMENT TECHNOLOGY REQUIREMENTS

Development of space-qualified, self-powered electrical connectors

PREPARED BY:	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:		ACTIVITY 14.0
DATE:	CONNECT ELECT. LINES FROM CROSSBEAM TO LONGITUDINAL BEAM	MODEL NO. ETVP
		DWG. NO.

ATTACHMENT 1

The activity begins after the completion of one bay with a long crossbeam, and is performed on alternate succeeding bays after both transverse beams and the long crossbeam have been assembled, and all six diagonal cords have been attached to the platform interfaces.

The EVA station is translated to position the astronaut adjacent to the leading surface of the crossbeam in the vicinity of the double crossmember. Here, the astronaut releases the secured ends of the Velcro straps and wraps them around the double crossmember, thus securing the cables at the pigtail breakout location. Next, the astronaut removes the four cable pigtails from their cable-run Velcro attachment and secures them to a holding device on the EVA station (or astronaut's pressure garment), as shown in Attachment 2, page 1.

The EVA station is repositioned so that the astronaut now faces the double crossmember on the inner face of the longitudinal beam. Again, the astronaut releases the attached straps and wraps them around the crossmember, securing the cable at the connector ends. The astronaut removes the secured pigtails one at a time and mates them with the appropriate connector attached to the longitudinal beam, as shown in Attachment 2, page 2. After all the electrical connections have been made, by joining the self-powered connectors (shown in Attachment 4), the astronaut reaches up to the mid-point of the pigtails where he releases a Velcro strap attached to one line. He then wraps the strap tightly around all four pigtails, as shown in Attachment 2, page 3.

The electrical power and data distribution concept is shown in Attachment 3.

PREPARED BY:

Satellite Systems Division  
Space Systems Group



Rockwell  
International

PAGE NO. 1 OF 3

CHECKED BY:

ACTIVITY 14.0

DATE:


CONNECT ELECTRICAL LINES FROM CROSSBEAM CABLES  
TO LONGITUDINAL CABLES

MODEL NO. ETVP

DWG. NO.

REF.

ATTACHMENT 2



DETACHING CROSSBEAM CABLE PIGTAILS PREPARATORY TO  
MAKING CONNECTIONS TO LONGITUDINAL BEAM CABLES.

B-115

PREPARED BY:

Satellite Systems Division  
Space Systems Group



Rockwell  
International

PAGE NO. 2 OF 3

CHECKED BY:

ACTIVITY 14.0

DATE:


CONNECT ELECTRICAL LINES FROM CROSSBEAM CABLES  
TO LONGITUDINAL CABLES

MODEL NO. ETVP

DWG. NO.

REF.

ATTACHMENT 2



ATTACHING ELECTRICAL CONNECTORS TO LONGITUDINAL BEAM  
CABLE INTERFACES



PREPARED BY:

Satellite Systems Division  
Space Systems Group



Rockwell  
International

PAGE NO. 3 OF 3

CHECKED BY:

ACTIVITY 14.0

DATE:


CONNECT ELECTRICAL LINES FROM CROSSBEAM CABLES  
TO LONGITUDINAL CABLES

MODEL NO. ETVP


DWG. NO.


REF.

ATTACHMENT 2




BANDING PIGTAILS WITH VELCRO STRAPS AND SECURING TO  
LONGITUDINAL BEAM

PREPARED BY:	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:		ACTIVITY 14.0
DATE:	CONNECT ELECTRICAL LINES FROM CROSSBEAM CABLES TO LONGITUDINAL CABLES	MODEL NO. ETVP
REF.	<div data-bbox="699 399 982 476" data-label="Section-Header"> <p>ATTACHMENT 3</p> </div> <div data-bbox="361 984 395 1683" data-label="Text"> <p>ELECTRICAL POWER AND DATA DISTRIBUTION CONCEPT</p> </div> <div data-bbox="444 554 1482 1956" data-label="Diagram"> <p>The diagram illustrates the electrical power and data distribution concept. It shows a wire breakout connected to a connector, which is then connected to a beam structure post. This setup is linked to an electrical line interchange. The interchange includes electrical power bus conductors (4 lines), house keeping experiment data hardline back-up, and T.S.P. 4 co-ax (51 lines).</p> </div>	

PREPARED BY:		Satellite Systems Division Space Systems Group	 Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:				ACTIVITY 14.0
DATE:		CONNECT ELECTRICAL LINES FROM CROSSBEAM CABLES TO LONGITUDINAL CABLES		MODEL NO. ETVP
REF.		DWG. NO.		ATTACHMENT 4


  

SELF-POWERED CONNECTOR CONCEPT



LONGITUDINAL RECEPTACLE: 2.5, 3, DATA, SOCKETS

CROSS-BEAM PLUG: 2.625, 4, PINS, PULL-IN PIN, .50, .375, TSP, COAX




PWR: 1.75, 3, SOCKETS

NO. 3 CONTACT: .50

PINS: .63, 5, 1.88

## TIME, POWER, AND ENERGY ESTIMATES

PREPARED BY:	Satellite Systems Division Space Systems Group		 <b>Rockwell International</b>		PAGE NO. 1 OF 1
CHECKED BY:					ACTIVITY 14.0
DATE:	CONNECT ELECTRICAL LINES FROM CROSSBEAM TO LONGITUDINAL BEAM				MODEL NO. ETVP
				DWG. NO.	

ATTACHMENT 5


ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
1. TRANSLATE EVA WORK STATION TO LONG CROSSBEAM	60	0.5	0.4	
2. RELEASE STRAP TIE AND WRAP AROUND DOUBLE CROSSMEMBER (FOUR PLACES)	120	0.5	0.4	
3. REMOVE FOUR PIGTAILS AND SECURE TO EVA STATION	120	0.5	0.4	
4. REPOSITION EVA STATION	60	0.5	0.4	
5. RELEASE STRAP TIES AND WRAP AROUND DOUBLE CROSSMEMBER	120	0.5	0.4	
6. REMOVE ONE PIGTAIL FROM EVA STATION AND MATE TO APPROPRIATE CONNECTOR ON LONGITUDINAL BEAM (FOUR TIMES)	240	0.5	0.4	
7. TRANSLATE TO MIDPOINT OF PIGTAILS	60	0.5	0.4	
8. RELEASE STRAP AND WRAP PIGTAILS TOGETHER	60	0.5	0.4	
SUMMARY	840 (14 MIN)	0.5	0.4	336

## ACTIVITY 15.0

### CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

ACTIVITY



REFERENCE DATA

1. Drawing 42662-50, Construction Fixture
2. Space Construction Data Base
3. Drawing 42662-45, Tri-Beam Platform Configuration

DESCRIPTION OF ACTIVITY

The entire platform structural assembly, as completed prior to this activity, is translated 12.9 meters with respect to the construction fixture by means of power-driven rollers which grip and position the platform. This action also pays out six cords for cross-bracing the structure.

CONSTRUCTION SUPPORT EQUIPMENT

Tribeam construction fixture—particularly supporting rollers and associated drive motors, controls, and sensors.

TIMELINE

2.16 meters/minute, 60 minutes for 12.9 meters

POWER/ENERGY


Construction fixture: varies only slightly according to mass of structure assembled. Average and peak power estimated at 0.12 kW; energy, 41 kJ (see Attachment 1)

CREW LOAD

IVA: Approximately 0.5 man continuously monitoring  
EVA: None

TECHNOLOGY DEVELOPMENT REQUIREMENTS

Development of construction fixture drive rollers, controls, and sensing system

PREPARED BY: R. Hart	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:		ACTIVITY 15.0
DATE: 12/5/79	TRANSLATE STRUCT. ASSEMBLY ONE BAY LENGTH	MODEL NO. ETVP
		DWG. NO.

ATTACHMENT 1

**ENERGY AND POWER CALCULATION**

Total weight of moving mass

3 longitudinals	3×266	=	798 lb
6 end caps	6×15	=	90
Wire, 2520 kg×2.2×70%		=	3880
			4768 lb

Weight of crossbeams  
and transverse beams = 252 lb

5020 lb

∴ Initial weight = 4768 lb; final weight = 5020 lb

Velocity = 2.16 m/min =  $2.16 \times \frac{3.28}{60} = 0.118$  ft/sec

Assume average weight of 4894 lb (difference is negligible)

Power =  $\frac{0.2}{103} \times \text{weight} \times \text{velocity} = \frac{0.2}{103} \times 4894 \times 118 = 0.115$  kW

Time to move one bay =  $\frac{12.9 \text{ m} \times 60}{2.16 \text{ m/min.}} = 358$  seconds  
(12.9 m)

Energy = 0.115×358 = 41.17 kJ

**SUMMARY**


Peak power	0.115 kW
Average power	0.115 kW
Time	358 seconds per bay
Energy	41.17 kJ per bay

## ACTIVITY 16.0

### CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

ACTIVITY



REFERENCE DATA

1. Drawing 42662-45, Rockwell Tri-Beam Concept, Engineering and Technology Verification Platform
2. Space Construction Data Base
3. Drawing 42662-50, Construction Fixture

DESCRIPTION OF ACTIVITY (see Attachment 1)

It is essential to monitor and check the geometric configuration of the tri-beam basic structure during its construction. Such checking will indicate deviations such as longitudinal warping, bending, or twisting from the theoretical geometry that may occur. The EVA astronaut will install an electro-optical device on the construction fixture in a position to sight along the platform longitudinal centerline. Targets will be incorporated into the platform structure in the plane of the bay as formed by the transverse and crossbeams. Real-time visual assessment and taking of status pictures will be accomplished via TV in the orbiter crew compartment.

CONSTRUCTION SUPPORT EQUIPMENT

1. Tri-beam construction fixture
2. Lighting
3. Platform alignment target and TV/optical alignment sighting system

TIMELINE


Viewing and recording of target pattern: 3 minutes per longitudinal bay

POWER/ENERGY: Negligible

CREW LOAD: IVA = 0.2 man, monitoring; EVA = none

TECHNOLOGY DEVELOPMENT REQUIREMENTS

1. Platform optical alignment checking system
2. Alignment targets and illumination system

PREPARED BY:	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 2
CHECKED BY:		Activity 16.0
DATE:		CHECK STRUCTURAL ALIGNMENT MODEL NO. ETVP DWG. NO.

ATTACHMENT 1

Platform Structural Alignment

Final platform structural alignment will be the net result of a great many interacting factors including:

- Consistency of heating and forming components
- Welding and joining of components
- Installation and tensioning of X-brace cords
- Drive forces of translation rollers in the construction fixture

The basic structural form of this platform is a triangular tube 136 m long. An effective way to evaluate structural alignment of such a structure is to view the inside of the three longitudinal members from one end along the longitudinal axis. The sets of transverse beams and crossbeams form natural cross-section stations that can individually be visually checked, indicate displacement of a particular station from the theoretical position, and can collectively show twisting or bending trends.


To facilitate visual observation of the displacements from nominal, targets will be incorporated into the intersection fittings that join the transverse beams and crossbeams to the longitudinal beams.

A view down the inside of the platform structure will appear somewhat like the graphic representation of Attachment 2. At any cross-section station there could be six targets appearing in an irregular hexagon. The perspective effect will make the six rows of targets appear to radiate outward from a theoretical vanishing point at the center of the longitudinal axis. In the nominal condition, in which there is perfect platform alignment, the six rows of targets will each appear to be straight and the target spacing will geometrically increase from the longitudinal axis outward. The outermost cross-section station is the one nearest the view point. Any twisting trend in the platform structure will cause the radiating pattern of targets to have a curved appearance. Displacement of a single cross-section station would cause an apparent "dog leg" or local bend in the radiating pattern targets. Fine lines scribed onto a target within the optics can provide comparisons to nominal case and also show permissible variations.

The sighting aperture is best located at some point on the longitudinal axis, which is also the main rotation axis for the beam positioner and astronaut cherry picker. The most advantageous point to place the viewing device is at the end of the rotation support structure upon which these mechanisms are mounted. This arrangement is shown in Attachment 3.

The recommended viewing devices is an electro-optical system that is controlled by the IVA operator and presents a visual display inside the orbiter, possibly on a closed-circuit TV screen. A significant advantage to this type of system is that a permanent record (a photo ) can be made of the successive viewings down the line of targets. In case of a contingency, a situation in which the misalignment of the platform structure has reached the point that it might no longer be within acceptable tolerance limits, the TV picture could be transmitted back to earth for evaluation and analysis.



PREPARED BY:	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 2 OF 2
CHECKED BY:		Activity 16.0
DATE:	CHECK STRUCTURAL ALIGNMENT	MODEL NO. ETVP
		DWG. NO.

ATTACH. 2 (Cont.)

The primary concern of this measurement activity is to establish that structural alignment of the platform from one end to the other will be satisfactory to prevent overstressing and failure as a column when thrust loads are applied to transfer the platform to geosynchronous orbit.

PREPARED BY: C. Fritz

Satellite Systems Division  
Space Systems Group



Rockwell  
International

PAGE NO. 1 OF 1

CHECKED BY:

Activity 16.0


DATE: 12-5-79

CHECK STRUCTURAL ALIGNMENT


MODEL NO. ETVP

DWG. NO.

ATTACHMENT 2



PATTERN OF MARKERS ON INTERSECTION FITTINGS AS VIEWED ALONG CENTERLINE OF TRI-BEAM PLATFORM.


PREPARED BY:	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:		Activity 16.0
DATE:	CHECK STRUCTURAL ALIGNMENT	MODEL NO. ETVP
		DWG. NO.

ATTACHMENT 3

CONSTRUCTION FIXTURE  
BEAM POSITIONER SUPPORT

TV/OPTICAL SIGHTING DEVICE

TRI-BEAM  
CENTERLINE




ACTIVITY 17.1

PRECEDING PAGE BLANK NOT FILMED

CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

ACTIVITY



REFERENCE DATA

1. Drawing 42662-50, Construction Fixture
2. Space Construction Data Base

DESCRIPTION OF ACTIVITY (see Attachments 1 and 3)

This activity primarily includes those operations necessary for the deployment and pre-separation checkout of the libration damping system. It will take place at completion of platform assembly, in parallel with the stowage of return cargo in the payload bay, and will be followed by the orbiter separation operations. Included is a short translation of the ETVP to clear the libration damping RCS pods from the end crossbeam.

CONSTRUCTION SUPPORT EQUIPMENT

1. Tri-beam construction fixture (Reference 1)
2. Lighting and TV system

TIMELINE (see Attachment 2)

Estimated 4 minutes for boom deployment, and 22.0 minutes for pre-separation electronic checkout. and 4 minutes for translation of the structure.

POWER/ENERGY


Peak power, 1.9 kW; average power, 0.6 kW; energy, 1100 kJ  
(see Attachment 2 for details)

CREW LOAD

IVA = 2.0 men continuously  
EVA = None

TECHNOLOGY DEVELOPMENT REQUIREMENTS


1. Tri-beam construction fixture libration damping system

PREPARED BY:	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:		ACTIVITY 17.1
DATE: 12-7-79	CONFIGURE CONSTRUCTION FIXTURE FOR UNTESTED OPERATION	MODEL NO. ETVP
		DWG. NO.

ATTACHMENT 1

**LIBRATION DAMPING SYSTEM CONFIGURATION**

The libration damping system will consist of: two cold gas RCS modules with 1/2-lb thrusters, each mounted on a foldable boom attached to the construction fixture; a battery module; a computer module, a TT&C module, a cryo sensor module; and two omni antennas. The entire system will be packaged and transported as a part of the main construction fixture. Sheet 3 of Drawing 42662-50, as revised, shows the general arrangement and indicates how the booms will unfold into operating position (as shown on Attachment 3). Power for boom deployment will be furnished by the orbiter.

PREPARED BY: ROEBUCK	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:		ACTIVITY 17.1
DATE: 12/7/79	RECONFIGURE CONSTRUCTION FIXTURE FOR UNTENDED OPERATIONS	MODEL NO. ETVF
		OWG. NO.

ATTACHMENT 2

DURATION, POWER, AND ENERGY ESTIMATES

ITEM	OPERATION	DURATION (min)	PK PWR (kW)	AVG PWR (kW)	ENERGY (kJ)
RCS PODS	DEPLOYMENT (TWO SIDES)	4	0.1	0.1	24
LIGHTING	ILLUM. POD DEPLOYMENT	4	0.6	0.6	144
CONS. FIXT.	TRANSLATE ETVF	4	0.1	0.1	24
RMS ARM	VIEWING SYSTEM PLATFORM	10	1.9	1.4	840
TV	OBSERVATION	30	0.07	0.05	90
SUMMARY		30	1.9**	0.6*	1098

\*AVERAGE POWER =  $\frac{\text{ENERGY SUMMATION}}{\text{ACTIVITY TIME SUMMATION}}$

\*\*PEAK POWER SUMMARY BASED UPON PEAK POWER OF INDIVIDUAL ACTIVITIES  
SUBSEQUENTLY ESTIMATED BEING PERFORMED SIMULTANEOUSLY.

Note: Control/Display power neglected.

PREPARED BY:

Satellite Systems Division  
Space Systems Group



Rockwell  
International

PAGE NO. 1 OF 1

CHECKED BY:


ACTIVITY 17.1

CONFIGURE CONSTRUCTION FIXTURE FOR  
UNENDED OPERATIONS

MODEL NO. ETVP

DWG. NO.

ATTACHMENT 3




ACTIVITY 17.2

CONSTRUCTION ACTIVITY DATA SHEET

PROJECT    ENGINEERING AND TECHNOLOGY EVALUATION PLATFORM (ETVP)

ACTIVITY



REFERENCE DATA

1. Space Construction Data Base
2. Drawing 42662-50, Construction Fixture
3. Drawing 42662-52, Construction Station No. 2
4. Drawing 42662-53, Orbiter Stowage, First Flight

DESCRIPTION OF ACTIVITY

The activity begins with the removal of equipment from Construction Fixture No. 1 and from Construction Station No. 2, and continues through the stowing of the equipment in the orbiter bay. *Note: Support tripod was stowed in Activity 8.1. (see Attachments 1, 2, and 3)*

CONSTRUCTION SUPPORT EQUIPMENT

RMS with TV and lights

POWER/ENERGY

Peak power, 2.4 kW; average power, 1.6 kW; energy, 10,040 kJ  
(see Attachment 1)

CREW LOAD

One man continuously, operating RMS 106.5 minutes

TECHNOLOGY DEVELOPMENT REQUIREMENTS

None



ATTACHMENT 1  
Time, Power, and Energy Estimation for Stowing Return Cargo, Activity No. 17.2 SHEET 1 OF 3


ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
1. EVA ASTRONAUT EGRESSES TO THE CONSTRUCTION FIXTURE, TRANSPORTS HIMSELF BY MMU TO CONSTRUCTION STATION NO. 2, RELEASES BRACING STRUT BETWEEN Y-FRAME AND REEL ASSEMBLY FRAMES AND STOWS IT IN PAYLOAD BAY ON EXISTING SUPPORT CRADLE (IN PARALLEL TIME FRAME WITH STEP 2).	(300)	NEGLIGIBLE	NEGLIGIBLE	NEGLIGIBLE
2. WITH THE RMS, GRASP THE BEAM BUILDER AT CONSTRUCTION STATION NO. 2	300	0.845 1.050	0.845 0.525	253.5 151.5
3. BY REMOTE CONTROL FROM THE CREW CABIN, RELEASE THE MECHANICAL LATCHES AND ELECTRICAL INTERFACE BETWEEN THE BEAM BUILDER AND THE Y-FRAME	30	0.02	0.02	0.6
4. USING THE RMS, REMOVE THE BEAM BUILDER, ROTATE IT THROUGH 180° AND REPLACE IT ON THE Y-FRAME	1200	0.845 1.050	0.845 0.525	1014. 630.
5. BY REMOTE CONTROL FROM THE CREW CABIN, SECURE THE MECHANICAL LATCHES BETWEEN THE BEAM BUILDER AND Y-FRAME	30	0.02	0.02	0.6
6. RELEASE THE RMS, MOVE THE RMS TO THE CABLE REEL ASSEMBLY AT CONSTRUCTION STATION NO. 2 AND GRASP IT (a)	300	0.845 1.050	0.845 0.525	253.5 157.5
7. BY REMOTE CONTROL FROM THE CREW CABIN, RELEASE THE LATCH POSITIONING THE CABLE REEL, FOLD THE CABLE REEL, AND RELATCH THE CABLE REEL (AS SHOWN IN ATTACHMENT 2). <i>Note: Can be done parallel in time with Step 2.</i>	30 30 30	0.02 0.02 0.02	0.02 0.02 0.02	0.6 0.6 0.6
8. BY REMOTE CONTROL FROM THE CREW CABIN, RELEASE THE MECH. LATCHES & ELEC. INTERFACE BETWEEN THE CABLE REEL ASSY AND ITS SUPPORTS.	30	0.02	0.02	0.6

ATTACHMENT 1  
Time, Power, and Energy Estimation for Stowing Return Cargo, Activity No. 17.2 SHEET 2 OF 3


ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
9. USING ONE RMS, MOVE THE CABLE REEL ASSY TO ITS STOWED LOCATION IN THE ORBITER BAY	1200	0.845	0.845	1014
10. BY REMOTE CONTROL FROM THE CREW CABIN, SECURE THE PAYLOAD RETENTION LATCHES	30	0.02	0.02	0.06
11. RELEASE THE RMS; MOVE THE RMS TO THE Y-FRAME AT CONSTR. STATION NO. 2 AND GRASP IT.	300	0.845 1.050	0.845 0.525	253.5 157.5
12. BY REMOTE CONTROL FROM THE CREW CABIN, RELEASE THE MECHANICAL LATCHES AND ELECTRICAL INTERFACE BETWEEN THE Y-FRAME AND ITS SUPPORT ON THE ORBITER LONGERONS.	30	0.02	0.02	0.6
13. USING THE RMS, MOVE THE Y-FRAME (WITH BEAM BUILDER ATTACHED) TO ITS STOWED LOCATION IN THE ORBITER BAY.	1200	0.845 1.050	0.845 0.525	1014. 630.
14. BY REMOTE CONTROL FROM THE CREW CABIN, SECURE THE PAYLOAD RETENTION LATCHES.	30	0.02	0.02	0.6
15. RELEASE THE RMS; MOVE THE RMS TO THE BRIDGE STRUCTURE ON CONSTRUCTION FIXTURE AND GRASP IT.	300	0.845 1.050	0.845 0.525	253.5 157.5
16. BY REMOTE CONTROL FROM THE CREW CABIN, RETRACT, STOW AND LATCH THE EVA WORK STATION ASSEMBLY TO THE BEAM POSITIONER. FUNCTION PERFORMED IN PARALLEL TIME TO 15.	(300)	0.22	0.1	30
17. BY REMOTE CONTROL FROM THE CREW CABIN, RELEASE THE MECHANICAL LATCHES WHICH FASTEN THE LEGS OF THE BRIDGE STRUCTURE TO THE MAIN YOKE FRAME OF THE CONSTRUCTION FIXTURE. THE ELECTRICAL CONNECTOR IS DISCONNECTED AS THE LATCHES ARE RELEASED. STORED ENERGY DEVICES POWER THE RETRACTION OF THE SUPPORT LEG ASSEMBLIES & THE 90° ROTATION OF THE LEG ASSYS RELATIVE TO THE BRIDGE BEAM ASSY, AS SHOWN IN ATTACH. 3.	30	0.02	0.02	0.6

ATTACHMENT 1  
Time, Power, and Energy Estimation for Stowing Return Cargo, Activity No. 17.2 SHEET 3 OF 3

ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
18. USING THE RMS, MOVE THE BRIDGE STRUCTURE TO ITS STOWED POSITION IN THE ORBITER BAY ON EXISTING SUPPORT CRADLE.	1200	0.845 1.050	0.845 0.525	1014. 630.
19. BY REMOTE CONTROL FROM THE CREW CABIN, SECURE THE PAYLOAD RETENTION LATCHES.	30	0.02	0.02	0.6
20. RELEASE THE RMS & MOVE IT AWAY FROM THE BRIDGE STRUCTURE.	50	0.845 1.050	0.845 0.525	50.7 31.5
21. TV, 34 W + 23 W AVERAGE HEATING (46 W PEAK); LIGHTS, 173 W; REQUIRED THROUGH STEPS 1 THROUGH 20.	(6390)	0.253	0.230	1469.7
22. STANDBY POWER FOR RMS HEATER DURING NON-TRANSPORT PERIODS (b)	(390)	1.050	0.525	204.8
SUMMARY	6390 (106.5 min) (1.775 hr)	(d) 2.388	(c) 1.57	10,040.3
<p><u>NOTES</u></p> <p>(a) DEVICE FOR INSTALLING INTERSECTION FITTINGS AND TELEOPERATOR PORTS IS ALSO ATTACHED TO CABLE REEL ASSEMBLY AND IS STOWED WITH IT AS ONE UNIT.</p> <p>(b) ASSUMED RMS HEATER IS THERMOSTATICALLY CONTROLLED WITH 50% DUTY CYCLE THROUGHOUT ACTIVITY.</p> <p>(c) AVERAGE POWER = <math>\frac{\text{TOTAL ENERGY}}{\text{TOTAL DURATION}}</math></p> <p>(d) PEAK POWER SUMMARY BASED UPON PEAK POWER OF INDIVIDUAL ACTIVITIES SUBJECTIVELY ESTIMATED BEING PERFORMED SIMULTANEOUSLY.</p>				

PREPARED BY:	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:		ACTIVITY 17.2
DATE:	STOW RETURN CARGO IN PAYLOAD BAY	MODEL NO. ETVP
		DWG. NO.

ATTACHMENT 2



PREPARED BY:

Satellite Systems Division  
Space Systems Group



Rockwell  
International

PAGE NO. 1 OF 1

ACTIVITY 17.2

CHECKED BY:


DATE:

STOW RETURN CARGO IN PAYLOAD BAY

MODEL NO. ETVP

DWG. NO.

ATTACHMENT 3




B-138

ACTIVITY 21.0

CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

ACTIVITY



REFERENCE DATA

1. Drawing 42662-45, Rockwell Tri-Beam Concept, ETVP
2. Space Construction Data Base
3. Manned Remote Work Station Development Article, Final Report, Executive Summary, Grumman Aerospace Corporation Report NSS-MR-RP008, March 1979.

DESCRIPTION OF ACTIVITY

This activity covers all operations necessary to prepare the construction system for construction operations. (see Attachment 1)

CONSTRUCTION SUPPORT EQUIPMENT

1. Tri-beam construction fixture system
2. Lighting and TV system
3. RMS with astronaut cherry picker

TIMELINE: 60 minutes (see Attachment 1)

POWER/ENERGY

Peak power, 2.771 kW; average power, 1.890 kW; energy, 6803 kJ  
(see Attachment 1)

CREW LOAD

IVA astronaut—60 minutes, continuous  
EVA astronaut—none

TECHNOLOGY DEVELOPMENT REQUIREMENTS

1. Tri-beam construction fixture system
2. RMS with astronaut cherry picker and end effectors

ATTACHMENT 1

PREPARE CONSTRUCTION SYSTEM FOR CONSTRUCTION OPERATIONS (ACTIVITY 21.0) SHEET 1 OF 2

ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
1. BRING RMS FROM ITS FINAL POSITION AT THE END OF DOCKING OPERATIONS INTO A POSITION AFFORDING AN ADVANTAGEOUS VIEW OF THE PRELIMINARY ELECTRIC CHECKOUT TO FOLLOW.	300	0.845 (a) 1.050 (b) 0.033 (k) 0.173 (j) 0.200 (f) 0.400 (g) <u>2.701</u>	0.845 (a) 0.525 (b) 0.023 (k) 0.173 (j) 0.200 (f) 0.400 (g) <u>2.166</u>	650
2. A PRELIMINARY ELECTRICAL CHECK OF THE CONSTRUCTION FIXTURE ELECTRICAL SYSTEM MUST BE PERFORMED TO CONFIRM THAT A SATISFACTORY ELECTRICAL CONNECTION WAS MADE AT DOCKING; THIS CHECK WILL INCLUDE CONSTRUCTION FIXTURE TV AND LIGHTING, BUT WILL NOT INCLUDE PLATFORM TRANSLATION DRIVE SYSTEM OR THE CONSTRUCTION FIXTURE ROTATION DRIVE.	600	1.050 (b) 0.033 (k) 0.033 (h) 0.173 (j) 0.200 (f) 0.400 (g) <u>1.889</u>	0.525 (b) 0.023 (k) 0.023 (h) 0.173 (j) 0.200 (f) 0.400 (g) <u>1.344</u>	806
3. TO REDUCE THE DANGER OF COLLISION BETWEEN THE RMS AND THE RCS BOOMS OF THE LIBRATION DAMPING SYSTEM WHICH EXTEND OUT FROM THE CONSTRUCTION FIXTURE, THESE BOOMS MUST BE RETRACTED INTO THE STOWED POSITION.	300	1.050 (b) 0.033 (k) 0.033 (h) 0.173 (j) 0.200 (f) 0.400 (g) <u>1.889</u>	0.525 (b) 0.023 (k) 0.023 (h) 0.173 (j) 0.200 (f) 0.400 (g) <u>1.344</u>	403
4. MANEUVER THE RMS INTO POSITION AND ATTACH THE CHERRY PICKER WHICH IS STOWED APPROXIMATELY IN THE CENTER OF THE ORBITER CARGO BAY; PROPER ATTACHMENT IS CONFIRMED BY A CHECKOUT OF CHERRY PICKER FUNCTIONS. AT COMPLETION OF CHECKOUT, THE CHERRY PICKER MUST BE PARKED AS NEAR AS PRACTICAL TO THE AIRLOCK DOOR AND ADJACENT TO HANDHOLDS WHICH WILL PERMIT THE EVA ASTRONAUT TO EGRESS AND CLIMB INTO POSITION ABOARD IT.	1800	0.845 (a) 1.050 (b) 0.070 (k) 0.033 (h) 0.173 (j) 0.200 (f) 0.400 (g) <u>2.771</u>	0.845 (a) 0.525 (b) 0.057 (k) 0.023 (h) 0.173 (j) 0.200 (f) 0.400 (g) <u>2.223</u>	4001

SHEET 2 OF 2

ATTACHMENT 1

ACTIVITY 21.0


ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
5. WHEN THE CHERRY PICKER IS READY TO RECEIVE HIM, THE EVA ASTRONAUT EGRESSES FROM THE AIRLOCK AND PROCEEDS VIA THE HANDHOLDS TO IT AND POSITIONS HIMSELF ABOARD; AN ON-BOARD FUNCTIONAL CHECK IS PERFORMED AND THEN THE CHERRY PICKER MANEUVERED INTO POSITION FOR THE NEXT ACTIVITY.	600	1.050 (b) 0.033 (h) 0.070 (c) 0.173 (j) 0.200 (f) 0.400 (g) 0.180 (i) <u>2.106</u>	0.525 (b) 0.023 (h) 0.070 (c) 0.173 (j) 0.200 (f) 0.400 (g) 0.180 (i) <u>1.571</u>	943
SUMMARY	3600 (60 MIN.)	2.771 (d)	1.890 (e)	6803
<p><u>NOTES</u></p> <p>(a) BASIC RMS</p> <p>(b) RMS HEATER</p> <p>(c) CHERRY PICKER</p> <p>(d) PEAK POWER SUMMARY BASED UPON PEAK POWER OF INDIVIDUAL ACTIVITIES, SUBJECTIVELY ESTIMATED, BEING PERFORMED SIMULTANEOUSLY.</p> <p>(e) AVERAGE POWER = <math>\frac{\text{ENERGY SUMMATION}}{\text{ACTIVITY TIME SUMMATION}}</math></p> <p>(f) ORBITER LIGHTS</p> <p>(g) CONSTRUCTION FIXTURE LIGHTS</p> <p>(h) CONSTRUCTION FIXTURE TV AND CAMERA</p> <p>(j) RMS LIGHTS</p> <p>(k) RMS TV AND HEATER</p> <p>(i) CHERRY PICKER LIGHTS</p>				



CONSTRUCTION ACTIVITY DATA SHEET 22.0

PROJECT      ENGINEERING & TECHNOLOGY VERIFICATION PLATFORM (ETVP)

ACTIVITY



REFERENCE DATA

1. Space Construction Data Base
2. Drawing 42662-45, Rockwell Tri-Beam Concept, ETVP
3. Drawing 42662-59, Forward Assembly

DESCRIPTION OF ACTIVITY

The activity consists of removing the folded forward support structure from the orbiter bay and installing it to the forward end of the tri-beam platform (see Attachment 4 for sequence and description of tasks).

CONSTRUCTION SUPPORT EQUIPMENT

RMS, Cherry Picker & Lighting

PRECEDING PAGE BLANK NOT FILMED

TIMELINE

77.5 minutes (see Attachment 4)

POWER/ENERGY


Peak power 2.2 kW; average power 1.6 kW; energy 7300 kJ (see Attachment 4)

CREW LOAD


One man continuous EVA

TECHNOLOGY DEVELOPMENT REQUIREMENTS

None

PREPARED BY: R. Hart		Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:			ACTIVITY 22.0
DATE: 21 Jan. 1980		INSTALLATION OF FORWARD SUPPORT STRUCTURE	MODEL NO. ETVP
REF.			DWG. NO.

ATTACHMENT 1




CONSTRUCTION  
FIXTURE

PLATFORM


FORWARD SUPPORT STRUCTURE  
IN FOLDED CONFIGURATION

B-144


PREPARED BY: R. Hart	Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:		ACTIVITY 22.0
DATE: 21 Jan. 1980	INSTALLATION OF FORWARD SUPPORT STRUCTURE	MODEL NO. ETVP
REF.		DWG. NO.

ATTACHMENT 2


DEPLOYED STRUCTURE




FINAL INSTALLED CONFIGURATION




B-145

PREPARED BY:	Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:		ACTIVITY 22.0
DATE:	INSTALLATION OF FORWARD SUPPORT STRUCTURE	MODEL NO. ETVP
REF.		DWG. NO.

ATTACHMENT 3



FORM 994-B-1 REV 12-78


PREPARED BY:	Space Systems Group  Rockwell International	PAGE NO. 1 OF 2
CHECKED BY:		ACTIVITY 22.0
DATE:	INSTALLATION OF THE FORWARD SUPPORT STRUCTURE	MODEL NO.
REF.		DWG. NO.

ATTACHMENT 4

Task Description	Duration (Sec.)	Peak Power (kW)	Avg. Power (kW)	Energy (kJ)
1. Move the EVA astronaut in the cherry picker to the folded forward support structure stowed in the orbiter bay and grasp it with the stabilizer arm of the cherry picker	600	.845(a) 1.050(b) .250(c)	.845(a) .525(b) .250(c)	507 315 150
2. By remote control from the orbiter crew cabin release the electro-mechanical latches which retain the forward support structure in its stowed location	30	.02(f) 1.050(b) .250(c)	.02 .525(b) .250(c)	6 16 8
3. Transport the folded forward support structure to the forward end of the platform Position the structure as shown on Attachment 1	1200	.845(a) 1.050(b) .250(c)	.845(a) .525(b) .250(c)	1014 630 300
4. Using the stabilizer arm, install the ball joint at the end of the forward support structure into the ball socket on the attach port of the platform longitudinal. The ball will automatically lock into the socket when it is inserted	300	.845(a) 1.050(b) .250(c)	.845(a) .525(b) .250(c)	253.5 157.5 75
5. Using the stabilizer arm, rotate the folded forward support structure about the installed ball joint so that the structure can be unfolded without collision.	120	.845(a) 1.050(b) .250(c)	.845(a) .525(b) .250(c)	101.4 63 30
6. Unclip the hook tool (see Attachment 3) from its stowed position on the cherry picker and use it to manually pull on the latch which secures the structure in its folded configuration. Restow the tool. The structure will unfold to its deployed configuration	300	1.050(b) .250(c)	.525(b) .250(c)	157.5 75

FORM 994-B-1 REV 12-78

PREPARED BY:	 <b>Rockwell International</b> Space Systems Group	PAGE NO. 2 OF 2																																																						
CHECKED BY:		ACTIVITY 22.0																																																						
DATE:	<b>INSTALLATION OF THE FORWARD SUPPORT STRUCTURE</b>	MODEL NO. ETVP																																																						
REF.	<div style="text-align: center; margin-bottom: 10px;">ATTACHMENT 4</div> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 45%;">Task Description</th> <th style="width: 10%;">Duration (Sec.)</th> <th style="width: 10%;">Peak Power (kW)</th> <th style="width: 10%;">Avg. Power (kW)</th> <th style="width: 15%;">Energy (kJ)</th> </tr> </thead> <tbody> <tr> <td rowspan="3">7. Wait until the deployed structure is quiescent and release it from the grasp of the cherry picker. Move the cherry picker to the grasp point near the second ball joint and grasp the structure with the stabilizer</td> <td rowspan="3" style="text-align: center;">600</td> <td style="text-align: center;">.845(a)</td> <td style="text-align: center;">.845(a)</td> <td style="text-align: center;">507</td> </tr> <tr> <td style="text-align: center;">1.050(b)</td> <td style="text-align: center;">.525(b)</td> <td style="text-align: center;">315</td> </tr> <tr> <td style="text-align: center;">.250(c)</td> <td style="text-align: center;">.250(c)</td> <td style="text-align: center;">150</td> </tr> <tr> <td rowspan="3">8. Install the second ball joint in similar fashion to Step 4 (see Attachment 2)</td> <td rowspan="3" style="text-align: center;">300</td> <td style="text-align: center;">.845(a)</td> <td style="text-align: center;">.845(a)</td> <td style="text-align: center;">253.5</td> </tr> <tr> <td style="text-align: center;">1.050(b)</td> <td style="text-align: center;">.525(b)</td> <td style="text-align: center;">157.5</td> </tr> <tr> <td style="text-align: center;">.250(c)</td> <td style="text-align: center;">.250(c)</td> <td style="text-align: center;">75</td> </tr> <tr> <td rowspan="3">9. Install the third ball joint in similar fashion to Steps 7 and 4 (see Attachment 2)</td> <td rowspan="3" style="text-align: center;">900</td> <td style="text-align: center;">.845(a)</td> <td style="text-align: center;">.845</td> <td style="text-align: center;">760.5</td> </tr> <tr> <td style="text-align: center;">1.050(b)</td> <td style="text-align: center;">.525</td> <td style="text-align: center;">472.5</td> </tr> <tr> <td style="text-align: center;">.250(c)</td> <td style="text-align: center;">.250</td> <td style="text-align: center;">225</td> </tr> <tr> <td rowspan="3">10. Release the stabilizer arm and move the cherry picker away from the structure</td> <td rowspan="3" style="text-align: center;">300</td> <td style="text-align: center;">.845(a)</td> <td style="text-align: center;">.845</td> <td style="text-align: center;">253.5</td> </tr> <tr> <td style="text-align: center;">1.050(b)</td> <td style="text-align: center;">.525</td> <td style="text-align: center;">157.5</td> </tr> <tr> <td style="text-align: center;">.250(c)</td> <td style="text-align: center;">.250</td> <td style="text-align: center;">75</td> </tr> <tr> <td style="text-align: center;">SUMMARY</td> <td style="text-align: center;">4650</td> <td style="text-align: center;">2.165(d)</td> <td style="text-align: center;">1.56(e)</td> <td style="text-align: center;">7260.9</td> </tr> </tbody> </table> <div style="margin-top: 10px;"> <p><b>NOTES:</b></p> <ul style="list-style-type: none"> <li>(a) Basic RMS</li> <li>(b) RMS Heater</li> <li>(c) Cherry Picker</li> <li>(d) Peak power summary based upon peak power of individual activities, subjectively estimated, being performed simultaneously</li> <li>(e) Average Power = <math>\frac{\text{Energy Summation}}{\text{Activity Time Summation}}</math></li> </ul> </div>		Task Description	Duration (Sec.)	Peak Power (kW)	Avg. Power (kW)	Energy (kJ)	7. Wait until the deployed structure is quiescent and release it from the grasp of the cherry picker. Move the cherry picker to the grasp point near the second ball joint and grasp the structure with the stabilizer	600	.845(a)	.845(a)	507	1.050(b)	.525(b)	315	.250(c)	.250(c)	150	8. Install the second ball joint in similar fashion to Step 4 (see Attachment 2)	300	.845(a)	.845(a)	253.5	1.050(b)	.525(b)	157.5	.250(c)	.250(c)	75	9. Install the third ball joint in similar fashion to Steps 7 and 4 (see Attachment 2)	900	.845(a)	.845	760.5	1.050(b)	.525	472.5	.250(c)	.250	225	10. Release the stabilizer arm and move the cherry picker away from the structure	300	.845(a)	.845	253.5	1.050(b)	.525	157.5	.250(c)	.250	75	SUMMARY	4650	2.165(d)	1.56(e)	7260.9
Task Description	Duration (Sec.)	Peak Power (kW)	Avg. Power (kW)	Energy (kJ)																																																				
7. Wait until the deployed structure is quiescent and release it from the grasp of the cherry picker. Move the cherry picker to the grasp point near the second ball joint and grasp the structure with the stabilizer	600	.845(a)	.845(a)	507																																																				
		1.050(b)	.525(b)	315																																																				
		.250(c)	.250(c)	150																																																				
8. Install the second ball joint in similar fashion to Step 4 (see Attachment 2)	300	.845(a)	.845(a)	253.5																																																				
		1.050(b)	.525(b)	157.5																																																				
		.250(c)	.250(c)	75																																																				
9. Install the third ball joint in similar fashion to Steps 7 and 4 (see Attachment 2)	900	.845(a)	.845	760.5																																																				
		1.050(b)	.525	472.5																																																				
		.250(c)	.250	225																																																				
10. Release the stabilizer arm and move the cherry picker away from the structure	300	.845(a)	.845	253.5																																																				
		1.050(b)	.525	157.5																																																				
		.250(c)	.250	75																																																				
SUMMARY	4650	2.165(d)	1.56(e)	7260.9																																																				


FORM 994-B-1 REV 12-78

ACTIVITY 23.0

CONSTRUCTION ACTIVITY DATA SHEET

PROJECT Engineering and Technology Verification Platform (ETVP)

ACTIVITY



REFERENCE DATA

1. Space Construction Data Base
2. Drawing 42662-45, Rockwell Tri-Beam Concept, ETVP
3. Drawing 42662-59, Forward Assembly
4. Drawing 42662-57, Control Module Assembly

DESCRIPTION OF ACTIVITY

The activity consists of removing the forward assembly from the orbiter cargo bay with the RMS/cherry picker combined system and installing it on the forward support structure. Specific steps in the operation are delineated in Attachment 1. Attachments 2 through 7 illustrate details relating to the physical attachment process.

TIMELINE: 80 minutes, 30 seconds (see Attachment 1)

POWER/ENERGY

Peak power, 2.1 kW; average power, 1.6 kW; energy, 7800 kJ  
(see Attachment 1)

CREW LOAD: EVA—One man continuously

TECHNOLOGY DEVELOPMENT REQUIREMENTS

None

## ACTIVITY 23.0

## ATTACHMENT 1

SHEET 1 OF 2

## TIME, POWER, AND ENERGY ESTIMATION FOR INSTALLATION OF THE FORWARD BAY

ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
1. MOVE THE EVA ASTRONAUT IN THE CHERRY PICKER TO THE FWD ASSY STOWED IN THE ORBITER BAY & GRASP IT WITH THE CHERRY PICKER STABILIZER ARM.	600	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	507 315 150
2. BY REMOTE CONTROL FROM THE CREW CABIN, RELEASE THE ELECTROMECHANICAL LATCHES WHICH RETAIN THE FORWARD ASSEMBLY IN ITS STOWED LOCATION.	30	0.02 (f) 1.050 (b) 0.250 (c)	0.02 (f) 0.525 (b) 0.250 (c)	6 16 8
3. TRANSPORT THE FORWARD ASSEMBLY TO NEAR ITS INSTALLED LOCATION ON THE FWD SUPPORT STRUCTURE	1200	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	1014 630 300
4. UNCLIP THE HOOK TOOL FROM ITS STOWED LOCATION ON THE CHERRY PICKER & USE IT TO MANUALLY ACTIVATE THE 2ND POSITION CONTROL OF THE CABLE TRAY; THE TRAY WILL AUTOMATICALLY DEPLOY AS SHOWN IN (2) ON ATTACHMENT 5. RESTOW THE TOOL.	300	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	253.5 157.5 75
5. USE THE STABILIZER ARM TO INSTALL THE 1ST BALL SOCKET OF THE CM TO THE BALL JOINT OF THE SUPPORT STRUCTURE; THE BALL WILL AUTOMATICALLY LOCK IN THE SOCKET WHEN IT IS INSERTED.	300	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	253.5 157.5 75
6. WAIT UNTIL THE FWD ASSY IS QUIESCENT, THEN RELEASE THE STABIL. ARM; MOVE CHERRY PICKER TO NEAR THE 2ND BALL SOCKET AND GRASP THE CM.	600	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	507 315 150
7. INSTALL THE 2ND & 3RD BALL JOINTS IN SIMILAR FASHION TO STEPS 5, 6, 5.	1200	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	1014 630 300
8. UNCLIP HOOK TOOL FROM ITS STOWED POSITION ON THE CHERRY PICKER; USE IT TO MANUALLY ACTIVATE THE 3RD POSITION CONTROL OF THE CABLE TRAY. THE TRAY WILL AUTOMATICALLY MOVE TO POSITION (3), AS SHOWN ON ATTACHMENT 5.	300	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 1.050 (b) 0.250 (c)	253.5 157.5 75



ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
9. USE THE HOOK TOOL TO MANUALLY ACTIVATE THE 4TH POSITION CONTROL OF THE CABLE TRAY; RESTOW THE TOOL. THE TRAY WILL AUTOMATICALLY MOVE TO POSITION (4), AS SHOWN ON ATTACHMENT 5.	300	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 1.050 (b) 0.250 (c)	253.5 157.5 75
SUMMARY	4830 (80 MINUTES, 30 SECONDS)	2.145 (d)	1.616 (e)	7806

## NOTES

(a) BASIC RMS

(b) RMS HEATER

(c) CHERRY PICKER

(d) PEAK POWER SUMMARY BASED UPON PEAK POWER OF INDIVIDUAL ACTIVITIES, SUBJECTIVELY ESTIMATED, BEING PERFORMED SIMULTANEOUSLY.


(e) AVERAGE POWER =  $\frac{\text{ENERGY SUMMATION}}{\text{ACTIVITY TIME SUMMATION}}$ 

(f) LATCH

PREPARED BY:	Satellite Systems Division Space Systems Group	Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:	INSTALL FORWARD ASSEMBLY TO SUPPORT STRUCTURE		ACTIVITY 23.0
DATE:			MODEL NO. ETVP
			DWG. NO.

ATTACHMENT 2

STOWED CONFIGURATION OF FWD ASSY IN  
ORBITER CARGO BAY



B-152

PREPARED BY:

Satellite Systems Division  
Space Systems Group



Rockwell  
International

PAGE NO. 1 OF 1

CHECKED BY:

ACTIVITY 23.0


DATE:


INSTALL FORWARD ASSEMBLY TO SUPPORT STRUCTURE

MODEL NO. ETVP



DWG. NO.

ATTACHMENT 3




PREPARED BY:	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:		ACTIVITY 23.0
DATE:	INSTALL FORWARD ASSEMBLY TO SUPPORT STRUCTURE	MODEL NO. ETVP
		DWG. NO.


ATTACHMENT 4



FORM 994-B-1 REV 12-78


PREPARED BY:	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:		ACTIVITY 23.0
DATE:	INSTALL FORWARD ASSEMBLY TO SUPPORT STRUCTURE	MODEL NO. ETVP
		DWG. NO.

ATTACHMENT 5




FORM 994-B-1 REV 12-78

B-155


PREPARED BY:	Satellite Systems Division Space Systems Group	 <b>Rockwell International</b>	PAGE NO. 1 OF 1
CHECKED BY:			ACTIVITY 23.0
DATE:	INSTALL FORWARD ASSEMBLY TO SUPPORT STRUCTURE		MODEL NO. ETVP
REF.			DWG. NO.

ATTACHMENT 6




THE FOUR POSITIONS OF THE CABLE TRAY

- (1) STOWED
- (2) DEPLOYED FOR CONTROL MODULE INSTALLATION TO SUPPORT TRUSS
- (3) INTERMEDIATE POSITION
- (4) STRAIGHTENED POSITION FOR LATCHING

PREPARED BY:	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:		ACTIVITY 23.0
DATE:	INSTALL FORWARD ASSEMBLY TO SUPPORT STRUCTURE	MODEL NO. ETVP
REF.		DWG. NO.

ATTACHMENT 7




ACTIVITY 24.0

CONSTRUCTION ACTIVITY DATA SHEET

PROJECT Engineering and Technology Verification Platform (ETVP)

ACTIVITY



REFERENCE DATA

1. Drawing 42662-45, Rockwell Tri-Beam Concept, ETVP
2. Space Construction Data Base
3. Drawing 42662-59, Forward Assembly and Installation
4. Drawing 42662-57, Control Module Assembly

DESCRIPTION OF ACTIVITY

After the cable tray is manually locked in place, there will be seven connectors that will be individually engaged by the EVA astronaut, as discussed in Attachment 1.

CONSTRUCTION SUPPORT EQUIPMENT

PRECEDING PAGE BLANK NOT FILMED

1. Tri-beam construction fixture system
2. Lighting and TV system
3. RMS with astronaut cherry picker

TIMELINE: 41 minutes (see Attachment 2)

POWER/ENERGY

Peak power (occurring during Tasks 1 and 4), 2.145 kW; average power, 1.187 kW; energy, 2921 kJ —see Attachment 2.


CREW LOAD

EVA astronaut: 41 minutes, continuously  
IVA astronaut: 20 minutes, monitoring

TECHNOLOGY DEVELOPMENT REQUIREMENTS

1. Electrical connector for EVA astronaut manual operations
2. Cherry picker



PREPARED BY:	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:		ACTIVITY 24.0
DATE:	CONNECT FORWARD ASSEMBLY TO MAIN ELECTRICAL BUSES	MODEL NO. ETVP
		DWG. NO.

ATTACHMENT I

DISCUSSION OF ACTIVITY

At the end of the preceding activity (23.0—Installation of Forward Assembly to Support Structure), the cable tray has been brought into final position, but not yet locked to the structure. The first task to be accomplished by the EVA astronaut in this activity will be to manually latch the cable tray in place. Once the cable tray is latched, the cable tiedowns can be released, which will make the cables with their connectors available for engagement to the mating connectors on the main bus wiring.

## TIME, POWER, AND ENERGY ESTIMATION FOR CONNECTING FORWARD ASSEMBLY TO MAIN ELECTRICAL BUSES


ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
1. MANEUVER CHERRY PICKER, WITH EVA ASTRONAUT, TO A POSITION WITHIN REACH OF CABLE TRAY LATCH.	300	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	253.5 157.5 75.0
2. MANUALLY LATCH CABLE TRAY IN PLACE, MECHANICALLY ATTACHING IT TO THE FORWARD SUPPORT STRUCTURE, AS ILLUSTRATED IN STEP 4, SHEET 1 OF DRAWING NO. 42662-59.	300	1.050 (b) 0.250 (c)	0.525 (b) 0.250 (c)	157.5 75.0
3. THE CABLE PIGTAIL ENDS, TERMINATED WITH ELECTRICAL CONNECTORS, WILL BE TRANSPORTED CONTAINED BY QUICK-RELEASE TIEDOWNS. THIS TASK REMOVES THOSE TIEDOWNS, MAKING THE PIGTAILS AVAILABLE FOR CONNECTION TO THE MAIN ELECTRICAL BUSES.	60	1.05 (b) 0.250 (c)	0.525 (b) 0.250 (c)	31.5 15.0
4. THE MAIN TASK OF THIS ACTIVITY IS TO ENGAGE THE ELECTRICAL CONNECTORS LEADING FROM THE FORWARD ASSEMBLY TO THE MAIN DISTRIBUTION SYSTEM ON THE PLATFORM. AT COMPLETION OF ELECTRICAL CONNECTIONS, THE CHERRY PICKER IS RETRACTED TO A POSITION CLEAR OF PLATFORM TRANSLATION.	900 1800 1800	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	760.5 945.0 450.0
SUMMARY	2460 (41 MIN.)	2.145 (d)	1.187 (e)	2921
NOTES (a) BASIC RMS (b) RMS HEATER (c) CHERRY PICKER (d) PEAK POWER SUMMARY BASED UPON PEAK POWER OF INDIVIDUAL ACTIVITIES, SUBJECTIVELY ESTIMATED, BEING PERFORMED SIMULTANEOUSLY. (e) AVERAGE POWER = $\frac{\text{ENERGY SUMMATION}}{\text{ACTIVITY TIME SUMMATION}}$				

## ACTIVITY 25.0

### CONSTRUCTION ACTIVITY DATA SHEET

PROJECT    ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

ACTIVITY



REFERENCE DATA

1. Drawing 42662-45, Rockwell Tri-Beam Concept, ETVP
2. Space Construction Data Base
3. Drawing 42662-71, Bracing Strut Installation via Cherry Picker

DESCRIPTION OF ACTIVITY

On both sides of the platform there will be installed 12 bracing struts, two struts bracing each of the six long crossbeams. This bracing is required to react the orbit transfer loads of the installed payloads. Between the installation of the pair of bracing struts at each crossbeam, the platform must be translated far enough to bring the next crossbeam within reach of the RMS/cherry picker. Attachments 1 and 4 delineate the specific steps in the activity.

CONSTRUCTION SUPPORT EQUIPMENT

1. Tri-beam construction fixture system
2. Lighting and TV system
3. RMS with astronaut cherry picker
4. Bracing strut stowage canister

TIMELINE: 10 hours, 58 minutes (see Attachment 2)

POWER/ENERGY

Peak power, 2.992 kW; average power, 2.236 kW; energy, 88,260 kJ  
(see Attachment 2)


CREW LOAD

EVA astronaut—10 hours, 58 minutes (continuous)  
IVA astronaut—10 hours, 58 minutes (monitoring and support activities)

TECHNOLOGY DEVELOPMENT REQUIREMENTS

1. Tri-beam construction fixture system
2. RMS with astronaut cherry picker
3. Bracing strut stowage canister

PRECEDING PAGE BLANK NOT FILMED

PREPARED BY:	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:		ACTIVITY 25.0
DATE:	INSTALL BRACING STRUTS ON PORT SIDE OF PLATFORM	MODEL NO. ETVP
		DWG. NO.

ATTACHMENT 1

Activity 25.0 includes a total of 78 identified tasks which may be grouped into six sets of 13 basic tasks—one set being required for the installation of the pair of bracing struts on each end of each of the crossbeams. With the exception of small differences in the first task of each set (due to a slight variation in the distance that the platform must be translated to bring a crossbeam within reach of the RMS/cherry picker), the duration, power requirements, etc., of each set of 13 basic tasks are the same.

Attachment 3 presents a detail breakdown and summary of the construction support equipment utilization and total payload power requirements for a typical set of 13 basic tasks. The peak power, average power, and energy summaries for each task are used as entries on Attachment 2. Attachment 3 shows some commonalities of the various tasks—for example, if the RMS is active the peak power requirement will be 2.992 kW and the average power requirement, 2.454 kW. This is the case for Tasks 2, 3, 4, 5, 7, 8, 9, 10, 11, and 13. Excepting the first task, if the RMS is inactive, the peak power requirement will be 2.147 kW and the average power requirement will be 1.609 kW. This is the case for Tasks 6 and 12. For the first task, the peak power requirement is 2.262 kW and the average power requirement is 1.724 kW. This differs from Tasks 6 and 12 only in that the construction fixture drive rolls are active for translation of the platform.

ACTIVITY 25.0 ATTACHMENT 2 SHEET 1 OF 3  
TIME, POWER, AND ENERGY ESTIMATION FOR INSTALLING BRACING STRUTS ON PORT SIDE OF PLATFORM

ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
1. TRANSLATE PLATFORM INTO POSITION	240	2.262	1.724	413.76
2. GRASP STRUT A	300	2.992	2.454	736.20
3. TRANSPORT STRUT A TO PLATFORM	1080	2.992	2.454	2650.32
4. ENGAGE FIRST BALL JOINT	240	2.992	2.454	588.96
5. RELEASE AND POSITION CHERRY PICKER	480	2.992	2.454	1177.92
6. ADJUST AND ENGAGE SECOND BALL JOINT	600	2.147	1.609	965.40
7. RMS RETURN TO POSITION	300	2.992	2.454	736.20
8. GRASP STRUT B	300	2.992	2.454	736.20
9. TRANSPORT STRUT B TO PLATFORM	1080	2.992	2.454	2650.32
10. ENGAGE FIRST BALL JOINT	240	2.992	2.454	588.96
11. RELEASE AND POSITION CHERRY PICKER	480	2.992	2.454	1177.92
12. ADJUST AND ENGAGE SECOND BALL JOINT	600	2.147	1.609	965.40
13. RMS RETURN TO POSITION	300	2.992	2.454	736.20
14. TRANSLATE PLATFORM INTO POSITION	360	2.262	1.724	620.64
15. GRASP STRUT A	300	2.992	2.454	736.20
16. TRANSPORT STRUT A TO PLATFORM	1080	2.992	2.454	2650.32
17. ENGAGE FIRST BALL JOINT	240	2.992	2.454	588.96
18. RELEASE AND POSITION CHERRY PICKER	480	2.992	2.454	1177.92
19. ADJUST AND ENGAGE SECOND BALL JOINT	600	2.147	1.609	965.40
20. RMS RETURN TO POSITION	300	2.992	2.454	736.20
21. GRASP STRUT B	300	2.992	2.454	736.20
22. TRANSPORT STRUT B TO PLATFORM	1080	2.992	2.454	2650.32
23. ENGAGE FIRST BALL JOINT	240	2.992	2.454	588.96
24. RELEASE AND POSITION CHERRY PICKER	480	2.992	2.454	1177.92
25. ADJUST AND ENGAGE SECOND BALL JOINT	600	2.147	1.609	965.40
26. RMS RETURN TO POSITION	300	2.992	2.454	736.20
27. TRANSLATE PLATFORM INTO POSITION	720	2.262	1.724	1241.28
28. GRASP STRUT A	300	2.992	2.454	736.20
29. TRANSPORT STRUT A TO PLATFORM	1080	2.992	2.454	2650.32
30. ENGAGE FIRST BALL JOINT	240	2.992	2.454	588.96
31. RELEASE AND POSITION CHERRY PICKER	480	2.992	2.454	1177.92
32. ADJUST AND ENGAGE SECOND BALL JOINT	600	2.147	1.609	965.40
33. RMS RETURN TO POSITION	300	2.992	2.454	736.20

## ACTIVITY 25.0

## ATTACHMENT 1

## SHEET 2 OF 3

Satellite Systems Division  
Space Systems GroupRockwell  
International

ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
34. GRASP STRUT B	300	2.992	2.454	736.20
35. TRANSPORT STRUT B TO PLATFORM	1080	2.992	2.454	2650.32
36. ENGAGE FIRST BALL JOINT	240	2.992	2.454	588.96
37. RELEASE AND POSITION CHERRY PICKER	480	2.992	2.454	1177.92
38. ADJUST AND ENGAGE SECOND BALL JOINT	600	2.147	1.609	965.40
39. RMS RETURN TO POSITION	300	2.992	2.454	736.20
40. TRANSLATE PLATFORM INTO POSITION	720	2.262	1.724	1241.28
41. GRASP STRUT A	300	2.992	2.454	736.20
42. TRANSPORT STRUT A TO PLATFORM	1080	2.992	2.454	2650.32
43. ENGAGE FIRST BALL JOINT	240	2.992	2.454	588.96
44. RELEASE AND POSITION CHERRY PICKER	480	2.992	2.454	1177.92
45. ADJUST AND ENGAGE SECOND BALL JOINT	600	2.147	1.609	965.40
46. RMS RETURN TO POSITION	300	2.992	2.454	736.20
47. GRASP STRUT B	300	2.992	2.454	736.20
48. TRANSPORT STRUT B TO PLATFORM	1080	2.992	2.454	2650.32
49. ENGAGE FIRST BALL JOINT	240	2.992	2.454	588.96
50. RELEASE AND POSITION CHERRY PICKER	480	2.992	2.454	1177.92
51. ADJUST AND ENGAGE SECOND BALL JOINT	500	2.147	1.609	965.40
52. RMS RETURN TO POSITION	300	2.992	2.454	736.20
53. TRANSLATE PLATFORM INTO POSITION	720	2.262	1.724	1241.28
54. GRASP STRUT A	300	2.992	2.454	736.20
55. TRANSPORT STRUT A TO PLATFORM	1080	2.992	2.454	2650.32
56. ENGAGE FIRST BALL JOINT	240	2.992	2.454	588.96
57. RELEASE AND POSITION CHERRY PICKER	480	2.992	2.454	1177.92
58. ADJUST AND ENGAGE SECOND BALL JOINT	600	2.147	1.609	965.40
59. RMS RETURN TO POSITION	300	2.992	2.454	736.20
60. GRASP STRUT B	300	2.992	2.454	736.20
61. TRANSPORT STRUT B TO PLATFORM	1080	2.992	2.454	2650.32
62. ENGAGE FIRST BALL JOINT	240	2.992	2.454	588.96
63. RELEASE AND POSITION CHERRY PICKER	480	2.992	2.454	1177.92
64. ADJUST AND ENGAGE SECOND BALL JOINT	600	2.147	1.609	965.40
65. RMS RETURN TO POSITION	300	2.992	2.454	736.20
66. TRANSLATE PLATFORM INTO POSITION	720	2.262	1.724	1241.28

ATTACHMENT 2

SHEET 3 OF 3


ACTIVITY 25.0

ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
67. GRASP STRUT A	300	2.992	2.454	736.20
68. TRANSPORT STRUT A TO PLATFORM	1080	2.992	2.454	2650.32
69. ENGAGE FIRST BALL JOINT	240	2.992	2.454	588.96
70. RELEASE AND POSITION CHERRY PICKER	480	2.992	2.454	1177.92
71. ADJUST AND ENGAGE SECOND BALL JOINT	600	2.147	1.609	965.40
72. RMS RETURN TO POSITION	300	2.992	2.454	736.20
73. GRASP STRUT B	300	2.992	2.454	736.20
74. TRANSPORT STRUT B TO PLATFORM	1080	2.992	2.454	2650.32
75. ENGAGE FIRST BALL JOINT	240	2.992	2.454	588.96
76. RELEASE AND POSITION CHERRY PICKER	480	2.992	2.454	1177.92
77. ADJUST AND ENGAGE SECOND BALL JOINT	600	2.147	1.609	965.40
78. RMS RETURN TO POSITION	300	2.992	2.454	736.20
SUMMARY	39,480 SEC 10:58 HR	2.992 (a)	2.236 (b)	88,260 kJ 24.5 kWh
<p>NOTES</p> <p>(a) PEAK POWER SUMMARY BASED UPON PEAK POWER OF INDIVIDUAL ACTIVITIES, SUBJECTIVELY ESTIMATED, BEING PERFORMED SIMULTANEOUSLY.</p> <p>(b) AVERAGE POWER = <math>\frac{\text{ENERGY SUMMATION}}{\text{ACTIVITY TIME SUMMATION}}</math></p>				

ATTACHMENT 3  
SUMMARY OF POWER & ENERGY REQUIREMENTS BY TASK & EQUIPMENT FOR TYPICAL SET OF 13 TASKS IN ACTIVITY 25.0

	TASKS												
	1	2	3	4	5	6	7	8	9	10	11	12	13
PEAK POWER													
RMS OPERATION	-	0.845			0.845	-	0.845				0.845	-	0.845
RMS HEATER	1.050												1.050
RMS TV/HEATER	-	-	-	-	-	-	-	-	-	-	-	-	-
CONSTR. FIX. TV/HEATER	0.047												0.047
CONSTR. FIXTURE DRIVE	0.115	-	-	-	-	-	-	-	-	-	-	-	-
CONSTR. FIX. ROTATOR	-	-	-	-	-	-	-	-	-	-	-	-	-
CHERRY PICKER OPERATION	0.070												0.070
MISCELLANEOUS	-	-	-	-	-	-	-	-	-	-	-	-	-
RMS LIGHTS	-	-	-	-	-	-	-	-	-	-	-	-	-
ORBITER LIGHTS	0.200												0.200
CONSTR. FIX. LIGHTS	0.600												0.600
CHERRY PICKER LIGHTS	0.180												0.180
TOTAL PEAK POWER	2.262	2.992	2.992	2.992	2.992	2.147	2.992	2.992	2.992	2.992	2.992	2.147	2.992
AVERAGE POWER													
RMS OPERATION	-	0.845			0.845	-	0.845				0.845	-	0.845
RMS HEATER	0.525												0.525
RMS TV/HEATER	-	-	-	-	-	-	-	-	-	-	-	-	-
CONSTR. FIX. TV/HEATER	0.034												0.034
CONSTR. FIXTURE DRIVE	0.115	-	-	-	-	-	-	-	-	-	-	-	-
CONSTR. FIX. ROTATOR	-	-	-	-	-	-	-	-	-	-	-	-	-
CHERRY PICKER OPERATION	0.070												0.070
MISCELLANEOUS	-	-	-	-	-	-	-	-	-	-	-	-	-
RMS LIGHTS	-	-	-	-	-	-	-	-	-	-	-	-	-
ORBITER LIGHTS	0.200												0.200
CONSTR. FIX. LIGHTS	0.600												0.600
CHERRY PICKER LIGHTS	0.180												0.180
TOTAL AVG PWR (kW)	1.724	2.454	2.454	2.454	2.454	1.609	2.454	2.454	2.454	2.454	2.454	2.454	2.454
TOTAL ENERGY (kWh)	0.115	0.205	0.736	0.164	0.327	0.268	0.205	0.205	0.736	0.164	0.327	0.268	0.205




PREPARED BY:	Satellite Systems Division Space Systems Group	 Rockwell International	PAGE NO. 1 OF 8
CHECKED BY:			ACTIVITY 25.0
DATE:	INSTALL BRACING STRUTS ON PORT SIDE OF PLATFORM		MODEL NO. ETVP
			OWG. NO.

ATTACHMENT 4

PROCEDURES FOR INSTALLING BRACING STRUTS

Initially, the bracing strut storage canister will be rotated, by remote control from the orbiter crew compartment, to its deployed position as shown in Figure 1. The orbiter is then docked to the construction fixture. The RMS will grasp the cherry picker which will be boarded by an EVA astronaut as shown in Figure 2. Removal of the bracing struts and installation on the platform is accomplished in four phases, as described below.

1. Step A—Strut removal from storage canister and attachment of leading end to attach port at end of long crossbeam (see Figure 3).
  - Translate platform until fixture is at midpoint between first long crossbeam and short crossbeam.
  - Move RMS across payload bay, aligning cherry picker into position above the canister.
  - The cherry picker attaches to one end of a strut in the canister via the end effector at end of the stabilizer arm (see Figure 4).
  - The strut is removed clear where the RMS wrist rotates the strut into the approximate assembly plane.
  - The RMS is rotated, positioning the wrist directly below the long crossbeam.
  - The RMS wrist joint is rotated, moving strut "up" toward platform in the  $Y_0$  plane.
  - The cherry picker makes the final alignment and inserts the leading end of strut into the attachment housing.
2. Step B—Assembly of trailing end of strut to attachment at the short crossbeam extremity.
  - RMS releases leading end of strut and moves clear. The upper and lower arms of the RMS are driven so they are in a straight line.
  - The rotary joint in the upper arm of the (modified) RMS is rotated  $180^\circ$ , allowing elbow to be rotated in the opposite direction (see Figure 2).
  - The RMS is translated to position the cherry picker alongside the end of the short crossbeam as shown in Figure 5.
  - With cherry picker in position alongside the strut, the astronaut removes the strut length adjustment device and corrects the strut length as required for assembly, as shown in Figure 6.

PREPARED BY:	Satellite Systems Division Space Systems Group	 Rockwell International	PAGE NO. 2 OF 8
CHECKED BY:			ACTIVITY 25.0
DATE:	INSTALL BRACING STRUTS ON PORT SIDE OF PLATFORM		MODEL NO. ETVP
			DWG. NO.

ATTACHMENT 4

- With the strut length corrected (if necessary), the device is restowed on the cherry picker and the ball end inserted into the attachment housing.

*NOTE: The strut assembly described in Steps A and B is repeated an additional five times, as shown in Figure 7, and each assembly sequence is doubled, adding a second strut to the attach ports as shown in Figure 8.*

3. Step C—Assembly sequence for second (or opposing) strut.

Translate the platform until the second long crossbeam is in line with the centerline of the orbiter.

The RMS picks up one end of strut following the sequence described in Step A.

4. Step D—Final attachment sequence for second strut.

- The RMS releases strut and moves clear.
- The RMS is translated in position with the cherry picker alongside the end of the short crossbeam as shown in Figure 9.
- The remaining assembly sequence is as described in Step B.

*NOTE: The strut assembly described in Steps C and D is repeated an additional five times, as shown in Figure 7, and each assembly sequence is doubled, adding a second strut to the attach ports as shown in Figure 10.*

PREPARED BY:	Satellite Systems Division Space Systems Group	Rockwell International	PAGE NO. 3 OF 8
CHECKED BY:			ACTIVITY 25.0
DATE:	INSTALL BRACING STRUTS ON PORT SIDE OF PLATFORM		MODEL NO. ETVP
			DWG. NO.

ATTACHMENT 4

ORIGINAL PAGE IS  
OF POOR QUALITY





FIG. 1




RMS/CHERRY PICKER ASSEMBLY

FIG. 2

FORM 386-B-1 REV 12-78

PREPARED BY:	Satellite Systems Division Space Systems Group	Rockwell International	PAGE NO. 4 OF 8
CHECKED BY:			ACTIVITY 25.0
DATE:	INSTALL BRACING STRUTS ON PORT SIDE OF PLATFORM		MODEL NO. ETVP
			DWG. NO.


ATTACHMENT 4



STRUT REMOVAL TO 1<sup>ST</sup> ATTACHMENT PROCEEDURE.

STRUT (LEADING END) ASSEMBLY ACCOMPLISHED  
VIA CHERRY PICKER

FIG. 3



END EFFECTOR (STABILIZER) DETAIL

FIG. 4

PREPARED BY:	Satellite Systems Division Space Systems Group	Rockwell International	PAGE NO. 5 OF 8
CHECKED BY:	INSTALL BRACING STRUTS ON PORT SIDE OF PLATFORM		ACTIVITY 25.0
DATE:			MODEL NO. ETVP
			DWG. NO.

ATTACHMENT 4






FIG. 5



STRUT (TRAILING END) ASSEMBLY PROCEEDURE  
VIA ASTRONAUT

FIG. 6

PREPARED BY:	Satellite Systems Division Space Systems Group	 <b>Rockwell International</b>	PAGE NO. 6 OF 8
CHECKED BY:			ACTIVITY 25.0
DATE:	INSTALL BRACING STRUTS ON PORT SIDE OF PLATFORM		MODEL NO. ETVP
			DWG. NO.

ATTACHMENT 4




FIG. 7




FIG. 8

PREPARED BY:

Satellite Systems Division  
Space Systems Group



Rockwell  
International

PAGE NO. 7 OF 8

CHECKED BY:

ACTIVITY 25.0

DATE:

INSTALL BRACING STRUTS ON PORT SIDE OF  
PLATFORM

MODEL NO. ETVP

DWG. NO.

ATTACHMENT 4





FIG. 9

PREPARED BY:	Satellite Systems Division Space Systems Group	Rockwell International	PAGE NO. 8 OF 8
CHECKED BY:	INSTALL BRACING STRUTS ON PORT SIDE OF PLATFORM		ACTIVITY 25.0
DATE:			MODEL NO. ETVP
			DWG. NO.

## ATTACHMENT 4



RELATIONSHIP OF ORBITER TO PLATFORM FOR STRUT ATTACHMENT AS DEPICTED

NOTE: • PLATFORM IS TRANSLATED THRU CONSTRUCTION FIXTURE & ALL STRUTS (A) THRU (C) — ARE ASSEMBLED ON SIDE OF PLATFORM CLOSEST TO AFT END OF ORBITER :

• ORBITER IS ROTATED & PROCEDURE REPEATED .

FIG. 10




## ACTIVITY 26.0

### CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

#### ACTIVITY



#### REFERENCE DATA

1. Drawing 42662-45, Rockwell Tri-Beam Concept, ETVP
2. Space Construction Data Base

#### DESCRIPTION OF ACTIVITY

The platform is rotated 180 degrees about the axis of the berthing port on the construction fixture to bring the desired work areas within range of the RMS. A rotation mechanism has been included in the construction fixture mounting arrangement to accommodate this requirement.

#### CONSTRUCTION SUPPORT EQUIPMENT

1. Tri-beam construction fixture system
2. Lighting and TV system

#### TIMELINE

Rotation time = 60 minutes, based on an angular velocity of  
3 degrees/minute

#### POWER/ENERGY

Peak power = average power = 0.1 kW for rotation; energy = 360 kJ

#### CREW LOAD

IVA astronaut—30 minutes, intermittantly  
EVA astronaut—not required

#### TECHNOLOGY DEVELOPMENT REQUIREMENTS


Tri-beam construction fixture rotation system

## ACTIVITY 27.0

### CONSTRUCTION ACTIVITY DATA SHEET

PROJECT Engineering and Technology Verification Platform (ETVP)

#### ACTIVITY



#### REFERENCE DATA

1. Space Construction Data Base
2. Drawing 42662-45, Rockwell Tri-Beam Concept, ETVP
3. Drawing 42662-60, Interorbital Thrust Structure

#### DESCRIPTION OF ACTIVITY

This activity consists of removing three struts from the strut canister and installing them to join together the aft ends of the platform longitudinal beams, then removing the collapsed thrust structure (see Attachment 3) from the orbiter cargo bay, and installing and deploying it at the aft end of the platform. Specific steps in the installation operations are delineated in Attachment 1. Attachments 2, 3, and 4 illustrate the general features.

#### CONSTRUCTION SUPPORT EQUIPMENT

RMS, cherry picker, lighting, and hook tool

#### TIMELINE

4 hours, 56 minutes, 30 seconds (see Attachment 1)

#### POWER/ENERGY

Peak power, 2.145 kW; average power, 1.384 kW, energy, 24,613 kJ  
(see Attachment 1)

#### CREW LOAD

EVA—One man, continuously

#### TECHNOLOGY DEVELOPMENT REQUIREMENTS

None

PRECEDING PAGE BLANK NOT FILMED

## ACTIVITY 27.0

## ATTACHMENT 1

SHEET 1 OF 5

## TIME, POWER, AND ENERGY ESTIMATION FOR INSTALLATION OF THE INTERORBITAL ENGINE THRUST STRUCTURE

ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
1. MOVE THE EVA ASTRONAUT IN THE CHERRY PICKER ON THE RMS TO THE STRUT CONTAINER.	300	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	253.5 157.5 75
2. GRASP STRUT NO. 10 WITH THE CHERRY PICKER STABILIZER AND REMOVE IT FROM THE CONTAINER.		0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	253.5 157.5 75
3. MOVE THE CHERRY PICKER TO THE AFT END OF THE PLATFORM AT THE APEX LONGITUDINAL.	300	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	253.5 157.5 75
4. USING THE STABILIZER, INSTALL THE BALL END OF THE STRUT INTO THE BALL SOCKET OF THE ATTACH PORT ON THE APEX LONGITUDINAL. THE BALL WILL AUTOMATICALLY LOCK INTO THE SOCKET WHEN IT IS INSERTED.	300	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	253.5 157.5 75
5. RELEASE THE STABILIZER FROM THE STRUT, MOVE THE CHERRY PICKER TO THE OTHER END OF THE STRUT & GRASP IT WITH THE STABILIZER.	300	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	253.5 157.5 75
6. USING THE STABILIZER, INSTALL THE BALL END OF THE STRUT INTO THE BALL SOCKET OF THE ATTACH PORT OF THE LONGITUDINAL. THE BALL WILL AUTOMATICALLY LOCK INTO THE SOCKET WHEN IT IS INSERTED. RELEASE THE STABILIZER.	300	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	253.5 157.5 75
7. INSTALL STRUT NO. 11 USING A PROCEDURE SIMILAR TO STEPS 1-6.	1800	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	1521 945 450
8. INSTALL STRUT NO. 12 USING A PROCEDURE SIMILAR TO STEPS 1-6.	1800	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	1521 945 450

SEE NOTES ON SHEET 5 OF 5



SHEET 2 OF 5

ATTACHMENT 1

ACTIVITY 27.0

ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
9. MOVE THE EVA ASTRONAUT IN THE CHERRY PICKER ON THE RMS TO THE STOWED THRUST STRUCTURE IN THE ORBITER BAY. USE THE CHERRY PICKER STABILIZER TO GRASP THE THRUST STRUCTURE AT CENTRAL FRAME NO. 8.	600	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	507 315 150
10. BY REMOTE CONTROL FROM THE CREW CABIN, RELEASE THE MECHANICAL LATCHES WHICH SECURE THE THRUST STRUCTURE TO ITS CRADLE.	30	0.02 (f) 1.050 (b) 0.250 (c)	0.02 (f) 0.525 (b) 0.250 (c)	6 16 8
11. USING THE RMS, TRANSPORT THE THRUST STRUCTURE TO THE VICINITY OF ITS INSTALLED LOCATION AT THE AFT END OF THE APEX LONGITUDINAL OF THE PLATFORM.	600	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	507 315 150
12. INSTALL THE BALL JOINT AT THE END OF CENTRAL FRAME NO. 8 (THRUST STRUCTURE) INTO THE SOCKET ON THE END ATTACH PORT AT THE AFT END OF THE APEX LONGITUDINAL. THE BALL WILL AUTOMATICALLY LOCK INTO THE SOCKET WHEN IT IS INSERTED.	300	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 1.050 (b) 0.250 (c)	233.5 157.5 75
13. USE THE CHERRY PICKER STABILIZER TO ROTATE THE THRUST STRUCTURE (STILL IN ITS UNDEPLOYED CONFIGURATION) ABOUT THE APEX BALL JOINT TO AN ATTITUDE SUCH THAT CENTRAL FRAME NO. 7 CAN BE DEPLOYED WITHOUT DANGER OF COLLISION.	120	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	101.4 63 30
14. UNCLIP THE HOOK TOOL FROM ITS STOWED POSITION ON THE CHERRY PICKER AND USE IT TO MANUALLY PULL ON THE LANYARD WHICH RELEASES THE LATCH SECURING CENTRAL FRAME NO. 7. THIS FRAME WILL NOW SLOWLY DEPLOY, POWERED BY SPRINGS AND RATE CONTROLLED BY A DAMPER, UNTIL IT REACHES ITS DESIGNATED ANGLE RELATIVE TO THE REMAINDER OF THE THRUST STRUCTURE. RESTOW THE HOOK TOOL.	300	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	253.5 157.5 75

SHEET 3 OF 5

ATTACHMENT 1

ACTIVITY 27.0

ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
15. WAIT UNTIL THE QUASI-DEPLOYED STRUCTURE IS QUIESCENT AND RELEASE THE CHERRY PICKER STABILIZER FROM CENTRAL FRAME NO. 8. MOVE THE CHERRY PICKER TOWARD THE BALL JOINT AT THE END OF CENTRAL FRAME NO. 7, AND ATTACH THE STABILIZER TO THE GRASP POINT LOCATED NEAR THAT BALL JOINT.	600	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	507 315 150
16. INSTALL THE BALL JOINT AT THE END OF CENTRAL FRAME NO. 7 (THRUST STRUCTURE) INTO THE SOCKET ON THE END ATTACH PORT AT THE AFT END OF THE LONGITUDINAL. THE BALL WILL AUTOMATICALLY LOCK INTO THE SOCKET WHEN IT IS INSERTED.	300	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	253.5 157.5 75
17. INSTALL AND DEPLOY CENTRAL FRAME NO. 9 IN SIMILAR FASHION TO SETPS 13, 14, 15, AND 16. AT THE CONCLUSION OF STEP 17, THE CHERRY PICKER REMAINS ANCHORED TO CENTRAL FRAME NO. 9, CLOSE TO THE BALL JOINT.	1320	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	1115.4 693 330
18. UNCLIP THE HOOK TOOL FROM ITS STOWED POSITION ON THE CHERRY PICKER AND USE IT TO MANUALLY PULL ON THE LANYARD WHICH RELEASES THE LATCH SECURING THE NO. 2 OUTBOARD ENGINE TRUSS TO CENTRAL FRAME NO. 9. THE OUTBOARD ENGINE TRUSS WILL NOW SLOWLY DEPLOY, POWERED BY SPRINGS AND RATE CONTROLLED BY A DAMPER, UNTIL IT REACHES ITS DESIGNATED ANGLE RELATIVE TO THE REMAINDER OF THE THRUST STRUCTURE. RESTOW THE HOOK TOOL.	300	1.050 (b) 0.250 (c)	0.525 (b) 0.250 (c)	157.5 75
19. RELEASE THE CHERRY PICKER STABILIZER. MOVE THE CHERRY PICKER TO THE OPPOSITE END OF CENTRAL FRAME NO. 9. USE THE STABILIZER TO ANCHOR THE CHERRY PICKER TO CENTRAL FRAME NO. 9 SO THAT THE BALL SOCKET OF STRUT NO. 6 IS WITHIN REACH OF THE ASTRONAUT.	600	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	507 315 150

SHEET 4 OF 5

ATTACHMENT 1

ACTIVITY 27.0

ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
20. UNCLIP THE HOOK TOOL FROM ITS STOWED POSITION ON THE CHERRY PICKER AND USE IT TO MANUALLY PULL ON THE LANYARD WHICH RELEASES THE LATCH SECURING STRUT NO. 6 TO THE NO. 2 OUTBOARD ENGINE TRUSS. RELEASE THE LANYARD, THEN HOOK INTO THE STRUT RINGS (AS SHOWN IN ATTACHMENT 3). REEL IN THE HOOK AND BRING THE FREE END OF THE STRUT WITHIN REACH OF THE ASTRONAUT. UNFASTEN THE HOOK TOOL FROM THE STRUT RING. STOW THE HOOK TOOL.	400	1.050 (b) 0.250 (c)	0.525 (b) 0.250 (c)	210 100
21. MANUALLY INSTALL THE FREE END OF STRUT NO. 6 INTO THE BALL SOCKET ON THE CENTER ENGINE ATTACH PORT. ADJUST THE STRUT LENGTH AS REQUIRED BY MANUALLY TURNING THE ADJUSTING SCREW.	120	1.050 (b) 0.250 (c)	0.525 (b) 0.250 (c)	63 30
22. RELEASE THE CHERRY PICKER STABILIZER. MOVE THE CHERRY PICKER TO THE END ATTACH PORT OF THE NO. 2 OUTBOARD ENGINE. USE THE STABILIZER TO ANCHOR IT THERE SO THAT THE BALL SOCKET OF STRUT NO. 2 IS WITHIN REACH OF THE ASTRONAUT.	600	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	507 315 150
23. INSTALL NO. 2 STRUT SIMILAR TO STEPS 20 AND 21.	520	1.050 (b) 0.250 (c)	0.525 (b) 0.250 (c)	273 130
24. INSTALL NO. 5 STRUT SIMILAR TO STEPS 22, 20, AND 21. AT THE CONCLUSION OF STEP 24, THE CHERRY PICKER IS LOCATED AT THE END ATTACH PORT OF NO. 2 OUTBOARD ENGINE.	600	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	507 315 150
	520	1.050 (b) 0.250 (c)	0.525 (b) 0.250 (c)	273 130
25. MOVE THE CHERRY PICKER TO CENTRAL FRAME NO. 9 AND ANCHOR IT.	600	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	507 315 150

SHEET 5 OF 5

ATTACHMENT 1

ACTIVITY 27.0

ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
26. REPEAT STEPS 18 THROUGH 24 TO INSTALL NO. 1 OUTBOARD ENGINE AND NO. 3, 1, & 4 STRUTS. AT THE CONCLUSION OF STEP 26, THE CHERRY PICKER IS LOCATED AT THE END ATTACH PORT OF NO. 1 OUTBOARD ENGINE.	3660	2.145	1.190	4357.5
27. RELEASE THE CHERRY PICKER STABILIZER AND MOVE THE CHERRY PICKER AWAY FROM THE THRUST STRUCTURE.	300	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	253.5 157.5 75
SUMMARY	17,790 (4 HOURS, 56 MINUTES, 30 SEC)	2.145 (d)	1.384 (e)	24,613.2
<p>NOTES</p> <p>(a) BASIC RMS</p> <p>(b) RMS HEATER</p> <p>(c) CHERRY PICKER</p> <p>(d) PEAK POWER SUMMARY BASED UPON PEAK POWER OF INDIVIDUAL ACTIVITIES, SUBJECTIVELY ESTIMATED, BEING PERFORMED SIMULTANEOUSLY.</p> <p>(e) AVERAGE POWER = <math>\frac{\text{ENERGY SUMMATION}}{\text{ACTIVITY TIME SUMMATION}}</math></p> <p>(f) LATCH</p>				

PREPARED BY:

Satellite Systems Division  
Space Systems Group



Rockwell  
International

PAGE NO. 1 OF 1

CHECKED BY:

ACTIVITY 27.0

DATE:



INSTALL THRUST STRUCTURE

MODEL NO. ETVP

DWG. NO.

REF.

ATTACHMENT 2



INSTALLING THE THRUST STRUCTURE



PREPARED BY:

Satellite Systems Division  
Space Systems Group



Rockwell  
International

PAGE NO. 1 OF 1

CHECKED BY:

ACTIVITY 27.0

DATE:


INSTALL THRUST STRUCTURE

MODEL NO. ETVP

DWG. NO.


REF.

ATTACHMENT 3



STOWED THRUST STRUCTURE


B-186

PREPARED BY:		Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:			ACTIVITY 27.0
DATE:		INSTALL THRUST STRUCTURE	MODEL NO. ETVP
REF.			DWG. NO.

ATTACHMENT 4

ORIGINAL PAGE IS  
OF POOR QUALITY

BRAKE CONTROL



HAND CRANKED "STEEN" DEVICE

TETHER & HOOK

HOOK TOOL


STRUT WITH STRUT RING

## Activity 28.0

### CONSTRUCTION ACTIVITY DATA SHEET

PROJECT Engineering and Technology Verification Platform (ETVP)

#### ACTIVITY



#### REFERENCE DATA

1. Space Construction Data Base
2. Drawing 42662-45, Rockwell Tri-Beam Concept, ETVP
3. Drawing 42662-73, Special Lines and Antenna Installation, Aft End

#### DESCRIPTION OF ACTIVITY

The activity consists of removing the wiring package from the bracing strut container and then installing it at the aft end of the platform. Specific steps in the activity are delineated in Attachment 1. Attachments 2 and 3 illustrate details relating to the wiring installation.

#### CONSTRUCTION SUPPORT EQUIPMENT

RMS, cherry picker, and lighting

TIMELINE: 49 minutes (see Attachment 1)

#### POWER/ENERGY

Peak power, 2.145 kW; average power, 1.292 kW; energy, 3800 kJ (see Attachment 1)

#### CREW LOAD

EVA: One man continuously

#### TECHNOLOGY DEVELOPMENT REQUIREMENTS

None

PRECEDING PAGE BLANK NOT FILMED

# ACTIVITY 28.0

## ATTACHMENT 1

SHEET 1 OF 2

TIME, POWER, AND ENERGY ESTIMATION FOR INSTALLATION OF WIRING AT THE AFT END OF THE PLATFORM

ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
1. MOVE THE EVA ASTRONAUT IN THE CHERRY PICKER ON THE RMS TO THE WIRING PACKAGE WHICH IS STOWED IN THE BRACING STRUT CONTAINER. GRASP THE PACKAGE WITH THE CHERRY PICKER STABILIZER.	600	0.345 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	507 315 150
2. USING THE RMS, TRANSPORT THE WIRING PACKAGE TO THE REAR END OF THE PLATFORM. LOCATE THE CHERRY PICKER SO THAT THE BEAM CROSSMEMBER TO WHICH THE WIRING IS TO BE INSTALLED IS WITHIN REACH OF THE ASTRONAUT.	600	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	507 315 150
3. ROTATE THE STABILIZER HOLDING THE WIRING PACKAGE SO THAT THE WIRING PACKAGE IS WITHIN REACH OF THE ASTRONAUT.	120	0.250 (c) 1.050 (b)	0.250 (c) 0.525 (b)	30 63
4. MANUALLY REMOVE THE WIRING PACKAGE FROM THE STABILIZER AND SECURE IT TO THE BEAM CROSSMEMBER WITH THE ATTACHED STRAPS. THE FAR END OF THE WIRING PACKAGE WILL BE LOCATED ON (BUT NOT ATTACHED TO) THE CROSSMEMBER ON THE APEX BEAM.	300	1.050 (b) 0.250 (c)	0.525 (b) 0.250 (c)	157.5 75
5. MANUALLY CONNECT THE PIGTAILED CONNECTOR OF THE WIRING PACKAGE TO THE EXISTING CONNECTOR ON THE PLATFORM LONGITUDINAL BEAM.	300	1.050 (b) 0.250 (c)	0.525 (b) 0.250 (c)	157.5 75
6. MOVE THE CHERRY PICKER TO THE APEX BEAM, AND LOCATE IT IN A CONVENIENT POSITION FOR INSTALLING THE WIRING PACKAGE.	600	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.120 (c)	507 315 150
7. MANUALLY INSTALL THE WIRING PACKAGE TO THE CROSSMEMBER OF THE APEX BEAM USING THE ATTACHED STRAPS.	120	1.050 (b) 0.250 (c)	0.525 (b) 0.250 (c)	157.5 75
8. MANUALLY CONNECT THE PIGTAILED CONNECTOR OF THE WIRING PACKAGE TO THE EXISTING CONNECTOR WHICH IS PART OF THE ELECTRICAL HARNESS OF THE APEX BEAM END ATTACH PORT.	120	1.050 (b) 0.250 (c)	0.525 (b) 0.250 (c)	63 30






SHEET 2 OF 2


ATTACHMENT 1


ACTIVITY 28.0

ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
SUMMARY	2940 (49 MIN.)	2.145 (d)	1.292 (e)	3799.5
<p><u>NOTES</u></p> <p>(a) BASIC RMS</p> <p>(b) RMS HEATER</p> <p>(c) CHERRY PICKER</p> <p>(d) PEAK POWER SUMMARY BASED UPON PEAK POWER OF INDIVIDUAL ACTIVITIES, SUBJECTIVELY ESTIMATED, BEING PERFORMED SIMULTANEOUSLY.</p> <p>(e) AVERAGE POWER = <math>\frac{\text{ENERGY SUMMATION}}{\text{ACTIVITY TIME SUMMATION}}</math></p>				


PREPARED BY:	Satellite Systems Division Space Systems Group	 Rockwell International	PAGE NO. 1 OF 2
CHECKED BY:			ACTIVITY 28.0
DATE:	INSTALL WIRING AT AFT END OF PLATFORM		MODEL NO. ETVP
REF.			DWG. NO.

ATTACHMENT 2



PREPARED BY:	Satellite Systems Division Space Systems Group	 Rockwell International	PAGE NO. 2 OF 2
CHECKED BY:			ACTIVITY 28.0
DATE:	INSTALL WIRING AT AFT END OF PLATFORM		MODEL NO. ETVP
REF.			DWG. NO.

ATTACHMENT 2



ORIGINAL PAGE IS  
OF POOR QUALITY

PREPARED BY:

Space Systems Group



Rockwell  
International

PAGE NO. 1 OF 1

CHECKED BY:

ACTIVITY 28.0

DATE:

INSTALL WIRING AT AFT END OF PLATFORM

MODEL NO. ETVP

DWG. NO.

REF.

ATTACHMENT 3




DIAGRAM OF ELECTRICAL  
CONNECTIONS

B-194




## ACTIVITY 29.0

### CONSTRUCTION ACTIVITY DATA SHEET

PROJECT Engineering and Technology Verification Platform (ETVP)

#### ACTIVITY



#### REFERENCE DATA

1. Space Construction Data Base
2. Drawing 42662-45, Rockwell Tri-Beam Concept, ETVP
3. Drawing 42662-73, Special Lines and Antenna Installation, Aft End

#### DESCRIPTION OF ACTIVITY

The activity consists of removing the antenna from the orbiter cargo bay, installing and connecting it, and then electrically connecting the wiring on the thrust structure to the platform wiring. Specific steps in this activity process are delineated in Attachment 1. Attachments 2 and 3 illustrate major component features.

#### CONSTRUCTION SUPPORT EQUIPMENT

RMS, cherry picker, and lighting

#### TIMELINE

42 minutes (see Attachment 1)

#### POWER/ENERGY (see Attachment 1)

Average power, 1.473 kW; peak power, 2.145 kW; total energy, 3711 kJ

#### CREW LOAD

One man continuously—EVA

#### TECHNOLOGY DEVELOPMENT REQUIREMENTS

None

ATTACHMENT 1  
TIME, POWER, AND ENERGY ESTIMATION FOR INSTALLATION OF TT&C ANTENNA AND FOR ELECTRICALLY  
CONNECTING THE THRUST STRUCTURE (29.0)

SHEET 1 OF 2

ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
1. MOVE THE CHERRY PICKER TO THE LOCATION OF THE KU-BAND ANTENNA STOWED IN THE ORBITER BAY; GRASP THE ANTENNA WITH THE STABILIZER ARM OF THE CHERRY PICKER.	600	0.845 (a) 1.050 (b) 0.500 (c)	0.845 (a) 0.525 (b) 0.250 (c)	507 315 150
2. BY REMOTE CONTROL FROM THE ORBITER CREW CABIN, RELEASE THE ELECTROMECHANICAL LATCH(ES) WHICH RETAIN THE ANTENNA IN ITS STOWED LOCATION.	30	0.02 (f) 1.050 (b) 0.250 (c)	0.02 (f) 0.525 (b) 0.250 (c)	6 16 8
3. TRANSPORT THE ANTENNA TO ITS INSTALLED LOCATION AT THE AFT END OF THE APEX LONGITUDINAL BEAM.	30	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	507 315 150
4. USING THE STABILIZER ARM, INSTALL THE ANTENNA TO ITS INTERFACE; THE SECURING LATCH WILL AUTOMATICALLY LOCK THE ANTENNA WHEN IT IS CORRECTLY CLOSED.	600	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	507 315 150
5. MANUALLY CONNECT THE PIGTAILED CONNECTOR (PART OF THE ANTENNA HARNESS) TO THE HARNESS OF THE APEX BEAM END ATTACH PORT.	120	1.050 (b) 0.250 (c)	0.525 (b) 0.250 (c)	63 30
6. MANUALLY UNFASTEN THE VELCRO STRAP WHICH SECURES THE PIGTAILED CONNECTOR ON CENTRAL FRAM NO. 8; THIS IS PART OF THE ELECTRICAL HARNESS OF THE INTERORBITAL ENGINE THRUST STRUCTURE.	120	1.050 (b) 0.250 (c)	0.525 (b) 0.250 (c)	63 30
7. MANUALLY CONNECT THE PIGTAILED CONNECTOR (FROM STEP 9) TO THE HARNESS OF THE APEX BEAM END ATTACH PORT.	120	1.050 (b) 0.250 (c)	0.525 (b) 0.250 (c)	63 30
8. MOVE CHERRY PICKER AWAY FROM THE AFT END OF THE PLATFORM.	300	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	253.5 157.5 75
SUMMARY	2520 (42 MIN.)	2.145 (d)	1.473 (e)	3711

SEE NOTES ON SHEET 2

ACTIVITY 29.0

ATTACHMENT 1

SHEET 2 OF

NOTES

(a) BASIC RMS


(b) RMS HEATER

(c) CHERRY PICKER


(d) PEAK POWER SUMMARY BASED UPON PEAK POWER OF INDIVIDUAL ACTIVITIES, SUBJECTIVELY ESTIMATED, BEING PERFORMED SIMULTANEOUSLY.

(e) AVERAGE POWER =  $\frac{\text{ENERGY SUMMATION}}{\text{ACTIVITY TIME SUMMATION}}$

(f) LATCH

PREPARED BY:	Satellite Systems Division Space Systems Group	 <b>Rockwell International</b>	PAGE NO. 1 OF 1
CHECKED BY:			ACTIVITY 29.0
DATE:	INSTALL & CONNECT TT&C ANTENNA & CONNECT THRUST STRUCTURE WIRING TO PLATFORM WIRING		MODEL NO. ETVF
			DWG. NO.

ATTACHMENT 2



TT&C ANTENNA

PREPARED BY:

Satellite Systems Division  
Space Systems Group



Rockwell  
International

PAGE NO. 1 OF 1

CHECKED BY:

ACTIVITY 29.0

DATE:

INSTALL & CONNECT TT&C ANTENNA; CONNECT THRUST  
STRUCTURE WIRING TO PLATFORM WIRING

MODEL NO. ETVP

DWG. NO.

ATTACHMENT 3





DIAGRAM OF ELECTRICAL CONNECTIONS

## ACTIVITY 30.0

### CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

ACTIVITY



REFERENCE DATA

1. Drawing 42662-45, Tri-Beam Concept, Rockwell Tri-Beam Concept, ETVP
2. Space Construction Data Base
3. Drawing 42662-71, Bracing Strut Installation via Cherry Picker

DESCRIPTION OF ACTIVITY

This activity is the same as Activity 25.0, except that the bracing struts will be installed on the opposite side of the platform.

CONSTRUCTION SUPPORT EQUIPMENT

1. Tri-beam construction fixture system
2. Lighting and TV system
3. RMS with astronaut cherry picker
4. Bracing strut stowage canister

TIMELINE: 10 hours, 58 minutes (see Attachment 2, Activity 25.0)

POWER/ENERGY (see Attachment 2, Activity 25.0)

Peak power, 2.992 kW—occurs during most of the task; average power, 2.236 kW; energy, 88,260 kJ

CREW LOAD

EVA astronaut—10 hours, 58 minutes (continuous)

IVA astronaut—10 hours, 58 minutes (monitoring and support activities)

TECHNOLOGY DEVELOPMENT REQUIREMENTS

1. Tri-beam construction fixture system
2. RMS with astronaut cherry picker
3. Bracing strut stowage canister


PRECEDING PAGE BLANK NOT FILMED

Activity 31.0

CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

ACTIVITY



NOTE: THIS ACTIVITY IS IDENTICAL TO  
26.0. SEE THAT ACTIVITY DATA  
PACKAGE FOR DETAILS.


PRECEDING PAGE BLANK NOT FILMED

## ACTIVITY 32.0

### CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

ACTIVITY



REFERENCE DATA

1. Engineering and Technology Verification Platform (ETVP) Definition
2. Drawing 42662-45, Rockwell Tri-Beam Concept, ETVP
3. Drawing 42662-67, Shuttle Bay Packaging, Ground Flight Platform
4. Drawing 42662-74, Solar Array Assembly
5. Space Construction Data Base

DESCRIPTION OF ACTIVITY

By means of the cherry picker, an electrical cable from a spring-loaded reel in the orbiter bay is connected to a receptacle on the control module. This cable is used also for ground checkout of the ETVP systems and it is wired accordingly. The solar array system is unfolded and rotated, but not extended. The continuity of all of the connections made in space is verified; also, the latches and motorized electrical connectors located at the crossbeam ends and at the thrust structure ports are functionally checked. Subsequent to this verification of the electrical distribution system, the electrical cable from the control module (CM) to the orbiter is disconnected and stowed on the spring-loaded reel in the payload bay. Attachment 1 delineates the steps in the operation; Attachments 2 and 3 illustrate the operations.

TIMELINE: 1 hour, 55 minutes, 30 seconds (see Attachment 1)

POWER/ENERGY

Peak power, 2.145 kW; average power, 1.148 kW; energy, 7958 kJ  
(see Attachment 1)

CREW LOAD

One man (EVA), continuous, RMS/cherry picker

One man (IVA), one hour, 7-1/2 minutes, 50% time—monitoring, checkout

TECHNOLOGY DEVELOPMENT REQUIREMENTS

None

**PRECEDING PAGE BLANK NOT FILMED**



## ACTIVITY 32.0

## ATTACHMENT 1

SHEET 1 OF 3

## TIME, POWER, AND ENERGY ESTIMATION FOR ELECTRICAL DISTRIBUTION CHECK

ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
1. MOVE THE EVA ASTRONAUT ON THE RMS/CHERRY PICKER TO THE CHECKOUT CABLE REEL IN THE PAYLOAD BAY.	600	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	507 315 150
2. GRASP THE CONNECTOR END OF THE CABLE WITH THE STABILIZER ARM OF THE CHERRY PICKER.	300	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	253.5 157.5 75
3. MOVE THE EVA ASTRONAUT ON THE RMS/CHERRY PICKER TO THE CONTROL MOD. THE CABLE WILL PAY OUT FROM THE SPRING-LOADED REEL WITH SUFFICIENT TENSION TO KEEP THE CABLE UNDER CONTROL.	600	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	507 315 150
4. MATE THE CONNECTOR AT THE END OF THE CABLE TO THE RECEPTACLE IN THE CONTROL MOD. THE CONNECTOR/RECEPTACLE WILL LATCH AUTOMATICALLY WHEN IT IS MATED.	300	1.050 (b) 0.250 (c)	0.525 (b) 0.250 (c)	157.5 75
5. THE RMS/CHERRY PICKER REMAINS AT THIS LOCATION WHILE THE CHECKOUT IS PERFORMED (STEPS 6 THROUGH 16). <u>Note:</u> The control module can now be commanded from the orbiter crew cabin. All checkout operations are initiated from this location.	(4050)	1.050 (b) 0.250 (c)	0.525 (b) 0.250 (c)	2126.3 1012.5
6. RELEASE THE LATCHES (2) WHICH TIE DOWN THE SOLAR PANELS IN THEIR STOWED POSITION.	30	0.04 (f)	0.4 (f)	1.2
7. ROTATE ONE SOLAR PANEL ASSY (HALF WING) 180°, STARBOARD SIDE.	180	0.10 (g)	0.10 (g)	18.0
8. REPEAT STEP 7 FOR PORT SIDE.	180	0.10 (g)	0.10 (g)	18.0
9. UNFOLD WING HINGE 90°, STARBOARD SIDE.	90	0.10 (g)	0.10 (g)	9.0
10. REPEAT STEP 9 FOR PORT SIDE.	90	0.10 (g)	0.10 (g)	9.0
11. EXTEND TELESCOPING MAST FOR STARBOARD SIDE.	90	0.10 (g)	0.10 (g)	9.0
12. REPEAT STEP 11 FOR PORT SIDE.	90	0.10 (g)	0.10 (g)	9.0

0.85

Satellite Systems Division  
Space Systems GroupRockwell  
International

SEE NOTES ON SHEET 3.

SHEET 2 OF 3

ATTACHMENT 1

ACTIVITY 32.0


ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
13. ROTATE THE ROTARY JOINT BETWEEN THE CM AND THE SOLAR ARRAY ASSEMBLY: 5 MIN. @ LEO RATE, 1 REV/93 MIN; 5 MIN. @ GEO RATE, 1 REV/24 HOURS; 6 MIN @ 1/2 REV/SEC, 360 DEGREES. ALSO, NOD THE SOLAR ARRAYS THROUGH $\pm 40^\circ$ CONCURRENT WITH STEPS 14 AND 15.	(1320)	0.20 (g)	0.20 (g)	264
14. VERIFY CONTINUITY OF THE ELECTRICAL DISTRIBUTION SYSTEM TO EACH OF THE 15 ATTACH PORTS.	900	0.1 (g)	0.1 (g)	90
15. FUNCTION, OPEN/CLOSE EACH OF THE THREE LATCHES AT EACH OF THE 15 ATTACH PORTS.	1200	0.06 (f)	0.06 (f)	72
16. FUNCTION, EXTEND/RETRACT THE MOTORIZED ELECTRICAL CONNECTORS AT EACH OF THE 15 ATTACH PORTS.	1200	0.05 (g)	0.05 (g)	60
17. THE EVA ASTRONAUT ON THE RMS/CHERRY PICKER MANUALLY UNLATCHES THE CABLE BETWEEN THE ORBITER BAY & THE CONTROL MODULE BY USING THE HOOK TOOL WHICH IS STOWED ON THE CHERRY PICKER.	180	1.050 (b) 0.250 (c)	0.525 (b) 0.250 (c)	94.5 45
18. MOVE THE EVA ASTRONAUT ON THE RMS/CHERRY PICKER TO THE CABLE REEL IN THE BAY. THE SPRING ON THE CABLE REEL WILL RESTOW THE CABLE.	600	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	507 315 150
19. RELEASE THE CONNECTOR END OF THE CABLE FROM THE GRASP OF THE CHERRY PICKER STABILIZER & MOVE THE RMS/CHERRY PICKER AWAY FROM THE BAY.	300	0.845 (a) 1.050 (b) 0.250 (c)	0.845 (a) 0.525 (b) 0.250 (c)	253.5 157.5 75
SUMMARY	6930 (1 HOUR, 55 MINUTES, 30 SECONDS)	2.145 (d)	1.142 (e)	7913

SHEET 3 OF 3

ATTACHMENT 1


ACTIVITY 32.0


ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
<p><u>NOTES</u></p> <p>(a) BASIC RMS</p> <p>(b) RMS HEATER</p> <p>(c) CHERRY PICKER</p> <p>(d) PEAK POWER SUMMARY BASED UPON PEAK POWER OF INDIVIDUAL ACTIVITIES, SUBJECTIVELY ESTIMATED, BEING PERFORMED SIMULTANEOUSLY.</p> <p>(e) AVERAGE POWER = <math>\frac{\text{ENERGY SUMMATION}}{\text{ACTIVITY TIME SUMMATION}}</math></p> <p>(f) LATCHES</p> <p>(g) PLATFORM MECHANISMS AND CIRCUITS</p>				

PREPARED BY:	Satellite Systems Division Space Systems Group	 <b>Rockwell International</b>	PAGE NO. 1 OF 1
CHECKED BY:			ACTIVITY 32.0
DATE:	DISTRIBUTION SYSTEM CHECK AND PARTIAL FUNCTIONAL CHECK		MODEL NO. ETVP
			DWG. NO.



ATTACHMENT 2

ORIGINAL PAGE IS  
OF POOR QUALITY




PREPARED BY:	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:		ACTIVITY 32.0
DATE:	DISTRIBUTION SYSTEM CHECK AND PARTIAL FUNCTIONAL CHECK	MODEL NO. ETVP
		DWG. NO.


ATTACHMENT 3



SOLAR PANELS  
NOT EXTENDED  
FOR ACTIVITY 32.0



TELESCOPING ARMS




UNFOLDING OF  
SOLAR ARRAY ARMS

ACTIVITY 33.0

CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

ACTIVITY



REFERENCE DATA

1. Drawing 42662-45, Rockwell Tri-Beam Concept, ETVP
2. Space Construction Data Base
3. Figure 8, p. A-15, Manned Remote Work Station Development Article: Final Report—Volume I, Book 1, Flight Article Requirements; and Appendix A, Mission Requirements. Report NSS-MR-RP008, Grumman Aerospace Corporation, March 1, 1979

DESCRIPTION OF ACTIVITY

The cherry picker is not required for the remainder of this mission. Therefore, at this time, it is returned to the orbiter storage location where the EVA operator dismounts to a foot support device and folds the cherry picker for stowage. By control from the crew cabin, the RMS then stows it in the orbiter cargo bay, ready for the return flight, while the EVA operator ingresses through the airlock to the crew cabin.

CONSTRUCTION SUPPORT EQUIPMENT

1. Tri-beam construction fixture system
2. Light and TV system
3. RMS with astronaut cherry picker and end effectors

TIMELINE

20 minutes

POWER/ENERGY

Peak power, 2.992 kW; average power, 2.454 kW; energy, 2945 kJ

CREW LOAD

IVA—20 minutes, continuous; EVA—20 minutes, continuous

TECHNOLOGY DEVELOPMENT REQUIREMENTS


RMS astronaut cherry picker and end effector system

ACTIVITY 34.0

CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

ACTIVITY



REFERENCE DATA

1. Drawing 42662-45, Rockwell Tri-Beam Concept, ETVP
2. Space Construction Data Base

DESCRIPTION OF ACTIVITY

By remote control from the crew cabin, the two IMU's are prepared for installation on the control module (CM) and the platform crossbeam attach ports for determining relative alignment. See Attachments 1, 2, and 3 for details.

TIMELINE

8 hours (see Attachment 1)

POWER/ENERGY

Virtually none; the IMU's are battery powered after initial spinup of gyros by orbiter power.


CREW LOAD

One man, IVA

TECHNOLOGY DEVELOPMENT REQUIREMENTS

Develop the subsystem boxes which contain the three-axis IMU's, recording equipment, time base, and batteries.

PRECEDING PAGE BLANK NOT FILMED

PREPARED BY:	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:		ACTIVITY 34.0
DATE:	PREPARE ALIGNMENT MEASUREMENT INSTRUMENTATION	MODEL NO. ETVP
		DWG. NO.

ATTACHMENT 1


From overall operational considerations, the requirement exists to be able to point the payloads (such as antennas) to specific target areas. The ability to point to a desired target area involves several factors. The pointing of the basic tri-beam platform is accomplished by the precision attitude reference package which incorporates star trackers and gyros. The payloads are mounted on the ends of the crossbeams by the previously discussed male and female attach port systems. Therefore, it is necessary to determine the relative alignment between the precision attitude reference package on the control module and each crossbeam attach port. The attachment of each payload to its female attach port can be adjusted and aligned on the ground before carrying to orbit and subsequent berthing to the tri-beam platform. This technique will provide a known alignment relationship between the payload and the precision attitude reference package.

Determination of the relative alignment, in three orthogonal axes, between the precision attitude reference package and each crossbeam attach port is accomplished by the use of two inertial measurement units (IMU's). One IMU is attached to the control module, and the other IMU is sequentially attached to each crossbeam attach port. The relative alignment is measured between each attach port and the control module and recorded to provide the data base for ground adjustment of the payload female attach port system.


The two IMU's are platform-mounted on a cradle for transport to orbit as part of the second flight payload. Attachment 2 illustrates the arrangement of the IMU's on the mounting platform. A deployable cover will be provided, if required, for environmental reasons. Prior to removal of the IMU's from the platform, power is supplied and the internal gyros are spun up.

The timeline requirements are based on the premise that the alignment measurement period should be preceded by a calibration period for both IMU's, while on the stable platform. This calibration time should be of equal duration to that required for the total alignment measurement period, which is approximately six hours. An additional hour is allocated for spinup of the IMU gyros, so that this activity starts seven hours prior to Activity 35.0. In addition, a post-measurement calibration period of one hour is provided (also considered part of Activity 34.0) following the actual measurements, thus making a total of eight hours. All of this activity time is conducted in parallel with other construction activity, and thus adds nothing to elapsed time on orbit.




PREPARED BY:	Satellite Systems Division Space Systems Group	 Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:			ACTIVITY 34.0
DATE:	PREPARE ALIGNMENT MEASUREMENT INSTRUMENTATION		MODEL NO. ETVP
			DWG. NO.

ATTACHMENT 2



FORM 994-B-1 REV 12-78

PREPARED BY:	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:		ETVP
DATE:	PREPARE ALIGNMENT MEASUREMENT INSTRUMENTATION	MODEL NO. 34.0
		DWG. NO.

ATTACHMENT 3

	Weight (lb)
Sensor unit	26
Electronics control unit	22
Recorder or memory with timeline	5
Silver-zinc battery	35
Total	88 lb (40 kg)

Weight of sensor and electronic control is based on Bendix permanent magnet rate integrating gyroscope (64 PM RIG). Power required = 75 W @ 28 VDC.

Time required for IMU alignment operation is approx. 6 hours (per Activity Sheets 34.0, 35.0, 36.0, 37.0 and 38.0).

A silver-zinc battery for 1400 watt-hours would require a volume and weight as indicated:

$$7 \text{ hours} \times 100 \text{ watts} \times \text{factor of } 2 = 1400 \text{ watt-hours.}$$


Physical size of IMU is driven by size of mounting interfaces with RMS end effector and attach port/teleoperator berthing interfaces. Assume 23" W x 23" D x 11" H.

## ACTIVITY 35.0

### CONSTRUCTION ACTIVITY DATA SHEET

PROJECT    ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

#### ACTIVITY



#### REFERENCE DATA

1. Drawing 42662-45, Rockwell Tri-Beam Concept, ETVP
2. Space Construction Data Base

#### DESCRIPTION OF ACTIVITY

The cover of the baseline mounting fixture in the orbiter bay is opened, IMU No. 2 is grasped by the RMS, and then the latches securing the IMU are released by remote control. IMU No. 2 is transported by the RMS to the control module (CM) and installed on the teleoperator docking port located there. Latches on the teleoperator docking port are remotely activated by means of the TTC antenna to secure IMU No. 2.

TIMELINE:    32 minutes (see Attachment 1)

#### POWER/ENERGY

Peak power, 2.121 kW; average power, 1.701 kW; energy, 3266 kJ  
(see Attachment 1)

#### CREW LOAD

IVA—One man continuously, operating the RMS

#### TECHNOLOGY DEVELOPMENT REQUIREMENTS

None

# ACTIVITY 35.0

## ATTACHMENT 1

### TIME, POWER, AND ENERGY ESTIMATION FOR INSTALLING ALIGNMENT IMU ON CONTROL MODULE


ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
1. BY REMOTE CONTROL FROM THE CREW CABIN, OPEN THE COVER OF THE BASELINE MOUNTING FIXTURE IN THE ORBITER BAY.	60	0.02	0.02	12
2. MOVE THE RMS TO THE BASELINE MOUNTING FIXTURE AND GRASP IMU NO. 2 ASSEMBLY.	600	0.845(a) 1.050(b)	0.845 0.525	507 315
3. BY REMOTE CONTROL FROM THE CREW CABIN, RELEASE THE LATCHES WHICH SECURE IMU NO. 2 ASSEMBLY.	30	0.02	0.02	6
4. USE THE RMS TO TRANSPORT IMU NO. 2 ASSEMBLY TO THE CONTROL MODULE AND POSITION IT AT THE TELEOPERATOR DOCKING PORT.	600	0.845(a) 1.050(b)	0.845 0.525	507 315
5. INSTALL THE IMU NO. 2 ASSEMBLY ONTO THE TELEOPERATOR DOCKING PORT.	300	0.845(a) 1.050(b)	0.845 0.525	253.5 157.5
6. BY REMOTE CONTROL FROM THE CREW CABIN AND VIA THE TT&C ANTENNA, ACTIVATE THE LATCHES ON THE TELEOPERATOR DOCKING PORT TO SECURE THE IMU NO. 2 ASSY.	30	0.02	0.02	6
7. RELEASE THE RMS & MOVE IT AWAY FROM THE CONTROL MODULE.	300	0.845(a) 1.050(b)	0.845 0.525	253.5 157.5
RMS LIGHTING TV & HEATER	SUBTOTAL	1.915	1.297	2490
	1920 (32 MIN.)			
	1920	0.173	0.173	332
	1920	0.033	0.023	44
NOTES (a) BASIC RMS; (b) RMS HEATER; (c) PEAK POWER SUMMARY BASED UPON PEAK POWER OF INDIVIDUAL ACTIVITIES, SUBJECTIVELY ESTIMATED, BEING PERFORMED SIMULTANEOUSLY; (d) AVERAGE POWER = $\frac{\text{ENERGY SUMMATION}}{\text{ACTIVITY TIME SUMMATION}}$	SUMMARY	2.121(c)	1.701(d)	3266

## ACTIVITY 36.0

### CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

#### ACTIVITY



#### REFERENCE DATA

1. Drawing 42662-45, Rockwell Tri-Beam Concept, ETVP
2. Space Construction Data Base

#### DESCRIPTION OF ACTIVITY

An RMS grasps the IMU No. 2 assembly, remotely actuated latches release the IMU from its structural mounting in the orbiter cargo bay, and the RMS then translates it to a mounting position on the control module (CM). In a similar manner, IMU No. 1 is removed from the cargo bay and sequentially installed on the port side ends of the long crossbeam attach ports. A record is made of the data from both IMU's to provide the information for determining the relative alignment between each attach port and the CM. Attachment 1 delineates the steps in the operation. Attachments 2 and 3 illustrate the general features.

#### TIMELINE

2 hours, 18 minutes, 45 seconds (see Attachment 1) (see Section 5.3)

#### POWER/ENERGY

Peak power, 2.2 kW; average power, 1.3 kW; energy, 10,900 kJ  
(see Attachment 1) (see Section 5.3)

#### CREW LOAD

IVA—one man continuously, operating the RMS

#### TECHNOLOGY DEVELOPMENT REQUIREMENTS

None

# ACTIVITY 36.0

ATTACHMENT 1  
TIME, POWER, AND ENERGY ESTIMATION FOR PERFORMING ALIGNMENT OF ATTACH PORTS ON PORT SIDE OF ETVP

SHEET 1 OF 2

Satellite Systems Division  
Space Systems Group



Rockwell  
International


ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
1. MOVE THE RMS TO THE BASELINE MOUNTING FIXTURE AND GRASP IMU NO. 1 ASSEMBLY.	600	0.845 (a) 1.050 (b)	0.845 (a) 0.525 (b)	507 315
2. BY REMOTE CONTROL FROM THE CREW CABIN, RELEASE THE LATCHES WHICH SECURE IMU NO. 1 ASSEMBLY.	30	0.02 (e) 1.050 (b)	0.02 (e) 0.525 (b)	0.6 16
3. USE THE RMS TO TRANSPORT IMU NO. 1 ASSEMBLY FROM THE BASELINE MOUNTING FIXTURE TO THE END OF THE FIRST CROSSBEAM ON THE PORT SIDE OF THE ETVP.	600	0.845 (a) 1.050 (b)	0.845 (a) 0.525 (b)	507 315
4. INSTALL IMU NO. 1 ASSEMBLY ONTO THE ATTACH PORT.	300	0.845 (a) 1.050 (b)	0.845 (a) 0.525 (b)	253.5 157.5
5. BY REMOTE CONTROL FROM THE CREW CABIN, AND VIA THE TTC ANTENNA, CLOSE THE LATCHES ON THE ATTACH PORT AND SECURE IMU NO. 1 ASSEMBLY.	30	0.02 (e) 1.050 (b)	0.02 (e) 0.525 (b)	0.6 16
6. RELEASE THE RMS & BACK IT AWAY A SHORT DISTANCE FROM THE IMU NO. 1 ASSEMBLY (TO ELIMINATE DISTORTION ON THE CROSSBEAM DURING ALIGNMENT MEASUREMENT).	120	0.845 (a) 1.050 (b)	0.845 (a) 0.525 (b)	101.4 63
7. GRASP IMU NO. 1 ASSEMBLY WITH THE RMS.	120	0.845 (a) 1.050 (b)	0.845 (a) 0.525 (b)	101.4 63
8. RELEASE THE ATTACH PORT LATCHES.	30	0.02 (e) 1.050 (b)	0.02 (e) 0.525 (b)	0.6 16
9. BACK THE RMS AND IMU NO. 1 ASSEMBLY A SAFE DISTANCE AWAY FROM THE ETVP.	120	0.845 (a) 1.050 (b)	0.845 (a) 0.525 (b)	101.4 63
10. TRANSLATE THE ETVP THROUGH THE CONSTRUCTION FIXTURE A DISTANCE OF APPROXIMATELY 20 m @ 2.16 m/MIN, SO THAT THE NEXT CROSSBEAM IS LOCATED CONVENIENT TO THE RMS.	555	0.10 (f) 1.050 (b)	0.10 (f) 0.525 (b)	55.5 291
11 REPEAT STEPS 4,5,6,7,8,9, AND 10 FOUR TIMES.	5100 (4x1275)	1.915	1.007	5135.6 (4x1283.6)

SHEET 2 OF 2


ATTACHMENT 1

ACTIVITY 36.0


ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
12. REPEAT STEPS 4 THROUGH 9 ONE TIME.	720	1.915	1.302	937.4
SUBTOTAL	8325 (2 HR, 18 MIN, 45 SEC)	1.915 (c)	1.084 (d)	9022.8
RMS LIGHTING TV & HEATER (WRIST & ELBOW)	8325 8325	0.173 0.070	0.173 0.057	1440.2 474.5
SUMMARY	8325	2.158 (c)	1.314 (d)	10,937.5
<p>NOTES</p> <p>(a) BASIC RMS</p> <p>(b) RMS HEATER</p> <p>(c) PEAK POWER SUMMARY BASED UPON PEAK POWER OF INDIVIDUAL ACTIVITIES, SUBJECTIVELY ESTIMATED, BEING PERFORMED SIMULTANEOUSLY.</p> <p>(d) AVERAGE POWER = <math>\frac{\text{ENERGY SUMMATION}}{\text{ACTIVITY TIME SUMMATION}}</math></p> <p>(e) LATCH</p>				

PREPARED BY:	Satellite Systems Division Space Systems Group	 Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:			ACTIVITY 36.0
DATE:	MEASURE ALIGNMENT OF ATTACH PORTS ON PORT SIDE OF PLATFORM		MODEL NO. ETVP DWG. NO.


ATTACHMENT 2





PREPARED BY:	Satellite Systems Division Space Systems Group  <b>Rockwell International</b>	PAGE NO. 1 OF 1
CHECKED BY:		ACTIVITY 36.0
DATE:		MODEL NO. ETVP
MEASURE ALIGNMENT OF ATTACH PORTS ON PORT SIDE OF PLATFORM		DWG. NO.

ATTACHMENT 3




INSTALLATION SEQUENCE OF IMU's  
 POSITIONS 1 THROUGH 7 COVERED ON THIS  
 ACTIVITY

## ACTIVITY 37.0

### CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

#### ACTIVITY



#### REFERENCE DATA

1. Drawing 42662-45, Rockwell Tri-Beam Concept, ETVP
2. Space Construction Data Base

#### DESCRIPTION OF ACTIVITY

The activity consists of installing and removing the IMU No. 1 assembly to each of the three attach ports for the inter-orbital propulsion stages and then to the six attach ports along the starboard side of the ETVP. Attachment 1 delineates the operational steps; Attachment 2 illustrates IMU No. 1 attachment to a crossbeam. Attachment 3 shows platform positions.

#### TIMELINE

3 hours, 8 minutes, 15 seconds (see Attachment 1) (see Section 5.3)

#### POWER/ENERGY

Peak power, 2.2 kW; average power, 1.2 kW; energy, 14,100 kJ  
(see Attachment 1) (see Section 5.3)

#### CREW LOAD

One man (IVA) continuously, operating RMS.

#### TECHNOLOGY DEVELOPMENT REQUIREMENTS

None

PRECEDING PAGE BLANK NOT FILMED

## ACTIVITY 37.0

## ATTACHMENT 1

SHEET 1 OF 2

TIME, POWER, AND ENERGY ESTIMATION FOR PERFORMING ALIGNMENT OF ATTACH PORTS ON THRUST STRUCTURE AND ALONG STARBOARD SIDE OF ETVP

ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
1. USE THE RMS TO TRANSPORT THE IMU NO. 1 ASSEMBLY TO THE FIRST ATTACH PORT OF THE THRUST STRUCTURE AND INSTALL IT.	900	0.845 (a) 1.050 (b)	0.845 (a) 0.525 (b)	760.5 472.5
2. BY REMOTE CONTROL FROM THE CREW CABIN AND VIA THE TTC ANTENNA, CLOSE THE LATCHES ON THE ATTACH PORT AND SECURE THE IMU NO. 1 ASSEMBLY.	30	0.02 (f) 1.050 (b)	0.02 (f) 0.525 (b)	0.6 16
3. RELEASE THE RMS AND BACK IT AWAY A SHORT DISTANCE FROM THE IMU NO. 1 ASSEMBLY (TO ELIMINATE DISTORTION ON THE IMU DURING ALIGNMENT MEASUREMENT)	120	0.845 (a) 1.050 (b)	0.845 (a) 0.525 (b)	101.4 63
4. GRASP THE IMU NO. 1 ASSEMBLY WITH THE RMS.	120	0.845 (a) 1.050 (b)	0.845 (a) 0.525 (b)	101.4 63
5. RELEASE THE ATTACH PORT LATCHES	30	0.02 (f) 1.050 (b)	0.02 (f) 0.525 (b)	0.6 16
6. REPEAT STEPS 1,2,3,4, AND 5 THREE TIMES. THIS COMPLETES THE ALIGNMENT MEASUREMENT OF THE THRUST STRUCTURE AND THE FIRST STARBOARD CROSSBEAM.	3600 (3 x 1200)	1.915	1.329	4785 (3 x 1595)
7. BACK THE RMS AND IMU NO. 1 ASSEMBLY A SAFE DISTANCE AWAY FROM THE ETVP.	120	0.845 (a) 1.050 (b)	0.845 (a) 0.525 (b)	101.4 63
8. TRANSLATE THE ETVP THROUGH THE CONSTRUCTION FIXTURE A DISTANCE OF APPROXIMATELY 20 m @ 2.16 m/MIN. SO THAT THE SECOND CROSSBEAM IS CONVENIENT TO THE RMS.	555	0.10 (g)	0.10 (g)	55.5
9. INSTALL THE IMU NO. 1 ASSY ONTO THE ATTACH PORT.	300	0.845 (a) 1.050 (b)	0.845 (a) 0.525 (b)	253.5 157.5
10. REPEAT STEPS 2,3,4,5,7,8, & 9 FOUR TIMES	5100 (4 x 1275)	1.915	0.779	3971.6 (4 x 992.9)

SEE NOTES ON SHEET 2.




SHEET 2 OF 2


ATTACHMENT I


ACTIVITY 37.0

ACTIVITY		DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
11. REPEAT STEPS 2,3,4,5, & 7 ONE TIME		420	1.915	1.253	526.4
SUBTOTAL		11,295 (3 HOURS, 8 MINUTES, 15 SECONDS)	1.915 (d)	1.079 (e)	11,508.9
RMS LIGHTING TV & HEATER		11,295	0.173	0.173	1954
		11,295	0.70	0.57	643.8
SUMMARY		11,295	2.158	1.249	14,106.7
<p>NOTES</p> <p>(a) BASIC RMS</p> <p>(b) RMS HEATER</p> <p>(c) CHERRY PICKER</p> <p>(d) PEAK POWER SUMMARY BASED UPON PEAK POWER OF INDIVIDUAL ACTIVITIES, SUBJECTIVELY ESTIMATED, BEING PERFORMED SIMULTANEOUSLY.</p> <p>(e) AVERAGE POWER = <math>\frac{\text{ENERGY SUMMATION}}{\text{ACTIVITY TIME SUMMATION}}</math></p> <p>(f) LATCH</p> <p>(g) CONSTRUCTION FIXTURE ROLLER DRIVES</p>					


PREPARED BY:	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:		ACTIVITY 37.0
DATE:		MODEL NO. ETVP DWG. NO.
DETERMINE ALIGNMENT OF ATTACH PORTS ON THRUST STRUCTURE AND ALONG STARBOARD SIDE		

ATTACHMENT 2



PREPARED BY:	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:		ACTIVITY 37.0
DATE:	MEASURE ALIGNMENT OF ATTACH PORTS ON THRUST STRUCTURE & ALONG STARBOARD SIDE	MODEL NO. ETVP
		DWG. NO.

ATTACHMENT 3




## ACTIVITY 38.1

### CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

#### ACTIVITY



#### REFERENCE DATA

1. Drawing 42662-45, Rockwell Tri-Beam Concept, ETVP Verification Platform
2. Space Construction Data Base

#### DESCRIPTION OF ACTIVITY

The activity consists of returning IMU No. 1 assembly (which is on the RMS) to the baseline mounting fixture and latching it in place, then rotating the construction fixture (and platform assembly) 180 degrees to permit the RMS to retrieve IMU No. 2 from the teleoperator docking port of the control module, and stow it in the baseline mounting fixture, where it is latched in position. The cover (if used) of the baseline mounting fixture is then closed. See Attachment 1 for delineation of steps in the operation.

#### TIMELINE

One hour, 49 minutes, 30 seconds (see Attachment 1)

#### POWER/ENERGY

Peak power, 2.2 kW; average power, 1.0 kW; energy, 6900 kJ  
(see Attachment 1)

#### CREW LOAD

One man continuously (IVA), operating RMS

#### TECHNOLOGY DEVELOPMENT REQUIREMENTS

None

PRECEDING PAGE BLANK NOT FILMED

TIME, POWER, AND ENERGY ESTIMATION FOR ROTATING CONSTR. FIXTURE &amp; RETURNING ALIGNMENT IMU's TO ORB. BAY

ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
THE RMS HAS JUST REMOVED THE IMU NO. 1 ASSEMBLY FROM THE ATTACH PORT OF THE LAST CROSSBEAM AND THE ALIGNMENT MEASUREMENT IS COMPLETE.				
1. TRANSPORT IMU NO. 1 ASSY TO THE BASELINE MOUNTING FIXTURE IN THE ORBITER BAY AND INSTALL IT.	900	0.845 (a) 1.050 (b)	0.845 (a) 0.525 (b)	760.5 472.5
2. BY REMOTE CONTROL FROM THE CREW CABIN, CLOSE THE LATCHES WHICH SECURE THE IMU NO. 1 ASSEMBLY IN THE BASELINE MOUNTING FIXTURE.	30	0.02 (f) 1.050 (b)	0.02 (f) 0.525 (b)	12 16
3. BY REMOTE CONTROL FROM CREW CABIN, ROTATE THE CONSTRUCTION FIXTURE 180° ABOUT THE BERTHING PORT AXIS TO PERMIT RMS REACH TO THE CONTROL MODULE.	3600	0.10 (g) 1.050 (b)	0.10 (g) 0.525 (b)	360 1890
4. RELEASE THE RMS AND MOVE IT TO THE VICINITY OF IMU NO. 2 WHICH IS INSTALLED ON THE TELEOPERATOR DOCKING PORT ON THE CONTROL MODULE (CM).	600	0.845 (a) 1.050 (b)	0.845 (a) 0.525 (b)	507 315
5. USE THE RMS TO GRASP IMU NO. 2 ASSEMBLY	300	0.845 (a) 1.050 (b)	0.845 (a) 0.525 (b)	253.5 157.5
6. BY REMOTE CONTROL FROM THE CREW CABIN & VIA THE TTC ANTENNA, RELEASE THE LATCHES WHICH SECURE THE IMU NO. 2 ASSEMBLY TO THE TELEOPERATOR DOCKING PORT ON THE CM.	30	0.02 (f) 1.050 (b)	0.02 (f) 0.525 (b)	0.6 16
7. USE THE RMS TO TRANSPORT THE IMU NO. 2 ASSEMBLY TO THE BASELINE MOUNTING FIXTURE IN THE ORBITER BAY AND INSTALL IT.	900	0.845 (a) 1.050 (b)	0.845 (a) 0.525 (b)	760.5 472.5
8. BY REMOTE CONTROL FROM THE CREW CABIN, CLOSE THE LATCHES WHICH SECURE IMU NO. 2 ASSEMBLY IN THE BASELINE MOUNTING FIXTURE.	30	0.02 (f) 1.050 (b)	0.02 (f) 0.525 (b)	0.6 16
9. RELEASE THE RMS AND MOVE IT AWAY FROM THE BASELINE MOUNTING FIXTURE	120	0.845 (a) 1.050 (b)	0.845 (a) 0.525 (b)	101.4 63



SHEET 2 OF 2

ATTACHMENT 1

ACTIVITY 38.1


ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
9. BY REMOTE CONTROL FROM THE CREW CABIN, CLOSE THE COVER ON THE BASELINE MOUNTING FIXTURE.	60	0.02 (f) 1.050 (b)	0.02 (f) 0.525 (b)	0.6 '31
SUBTOTAL	6570	1.915	1.332	6206.2
RMS LIGHTING TV & HEATER	2970 2970	0.173 0.070	0.137 0.057	513.8 169.3
SUMMARY	6570 (109 MIN., 30 SEC)	2.158 (d)	1.049 (e)	6889.3
<p>NOTES</p> <p>(a) BASIC RMS</p> <p>(b) RMS HEATER</p> <p>(-) --</p> <p>(d) PEAK POWER SUMMARY BASED UPON PEAK POWER OF INDIVIDUAL ACTIVITIES, SUBJECTIVELY ESTIMATED, BEING PERFORMED SIMULTANEOUSLY.</p> <p>(e) AVERAGE POWER = <math>\frac{\text{ENERGY SUMMATION}}{\text{ACTIVITY TIME SUMMATION}}</math></p> <p>(f) LATCH</p> <p>(g) CONSTRUCTION FIXTURE ROTATOR</p>				

## ACTIVITY 38.2

### CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

#### ACTIVITY



#### REFERENCE DATA

1. Drawing 42662-50, Construction Fixture
2. Space Construction Data Base

#### DESCRIPTION OF ACTIVITY

This activity primarily includes those operations necessary for the deployment and pre-separation checkout of the libration damping system. It will take place at completion of platform assembly, in parallel with the stowage of return cargo in the payload bay, and will be followed by the orbiter separation operations (see Attachments 1 and 3).

#### CONSTRUCTION SUPPORT EQUIPMENT

1. Tri-beam construction fixture
2. Lighting and TV system

#### TIMELINE

Estimated 20 minutes for boom deployment, and 28.0 minutes for pre-separation electronic checkout (see Attachment 2).

#### POWER/ENERGY

Peak power, 2.1 kW; average power, 0.8 kW; energy, 1500 kJ  
(see Attachment 2)


#### CREW LOAD

EVA: 2.0 men continuously  
EVA: None

#### TECHNOLOGY DEVELOPMENT REQUIREMENTS

Tri-beam construction fixture libration damping system

PRECEDING PAGE BLANK NOT FILMED

PREPARED BY:	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:		ACTIVITY 38.2
DATE:	CONFIGURE PLATFORM FOR UNTENDED OPERATIONS	MODEL NO. ETVP
		DWG. NO.

ATTACHMENT 1

LIBRATION DAMPING SYSTEM CONFIGURATION

The libration damping system will consist of: two cold gas RCS modules with 1/2-lb thrusters, each mounted on a foldable boom attached to the construction fixture; a battery module; a computer module; a TT&C module; a cryo sensor module; and two omni antennas. The entire system will be packaged and transported as a part of the main construction fixture. Sheet 3 of Drawing 42662-50, as revised, shows the general arrangement and indicates how the booms will unfold into operating position (as shown on Attachment 3). Power for boom deployment will be furnished by the orbiter.

RETURN CARGO STOWAGE

The cherry picker, alignment measurement equipment, and checkout equipment have all been stowed previously following usage. The cross-brace strut canister cannot be rotated to its stowed position until separation of the orbiter from the construction fixture.

ACTIVITY 38.2

ATTACHMENT 2  
TIME, POWER, AND ENERGY ESTIMATION FOR CONFIGURING PLATFORM FOR UNATTENDED OPERATIONS (38.2)

ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
1. POSITION RMS FOR VIEWING OF LIBRATION DAMPING RCS APPENDAGE DEPLOYMENT.	120	0.845 (a) 1.050 (b) 0.243 (c)	0.845 (a) 0.525 (b) 0.230 (c)	101.4 63.0 27.6
2. DEPLOY RCS APPENDAGE BY USE OF MOTOR DRIVES IN CONSTRUCTION FIXTURE.	240	0.1 (f) 0.466 (g) 1.050 (b) 0.243 (c)	0.1 (f) 0.466 (g) 0.525 (b) 0.230 (c)	24.0 107.0 126.0 55.2
3. MOVE RMS TO GRAPPLE CONSTRUCTION FIXTURE IN PREPARATION FOR SEPARATION (CONCURRENTLY WITH FOLLOWING TASK).	120	0.845 (d) 0.243 (c)	0.845 (a) 0.230 (c)	101.4 27.6
4. PERFORM ELECTRONIC CHECKOUT OF THE TT&C, POWER DISTRIBUTION, AND RCS CONTROL SYSTEM IN PREPARATION FOR UNATTENDED OPERATIONS.	1320	(NEGLECTIBLE) 1.050 (b)	(NEGLECTIBLE) 0.525 (b)	10.0 693.0
5. TRANSLATE ETVP APPROX. 8 METERS TO CLEAR LIBRATION DAMPER RCS PLUMES FROM CROSSBEAMS	240	0.1 (h) 1.050 (b) 0.233 (i)	0.1 (h) 0.525 (b) 0.223 (i)	24.0 126.0 26.8
SUMMARY	1800	2.138 (d)	0.841 (e)	1513.0
<p>NOTES</p> <p>(a) BASIC RMS; (b) RMS HEATER; (c) RMS WRIST LIGHT, WRIST AND ELBOW TV CAMERAS, AND HEATERS; (d) PEAK POWER SUMMARY BASED UPON PEAK POWER OF INDIVIDUAL ACTIVITIES, SUBJECTIVELY ESTIMATED, BEING PERFORMED SIMULTANEOUSLY.</p> <p>(e) AVERAGE POWER = <math>\frac{\text{ENERGY SUMMATION}}{\text{ACTIVITY TIME SUMMATION}}</math></p> <p>(f) LIBRATION DAMPER EXTENSION DRIVES; (g) ONE 200-W LAMP AND TV CAMERA ON EACH SIDE OF CONSTRUCTION FIXTURE YOKE; (h) CONSTRUCTION FIXTURE ROLLER DRIVES; (i) CONSTR. FIXTURE LAMP &amp; TV AT BASE OF YOKE.</p>				

PREPARED BY:

Satellite Systems Division  
Space Systems Group



Rockwell  
International

PAGE NO. 1 OF 1

CHECKED BY:

ACTIVITY 38.2


DATE:

CONFIGURE CONSTRUCTION FIXTURE FOR UNTENDED OPNS

MODEL NO. ETVP

DWG. NO.

ATTACHMENT 3




B-238

## ACTIVITY 41.0

### CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

#### ACTIVITY



#### REFERENCE DATA

1. Drawing 42662-45, Rockwell Tri-Beam Concept, ETVP
2. Space Construction Data Base
3. Manned Remote Work Station Development Article Final Report—Executive Summary, Grumman Aerospace Corporation, Report NSS-MR-RP008, March 1979

#### DESCRIPTION OF ACTIVITY

Included in this activity are all those operations necessary to prepare the construction system for construction operations. Attachment 1 delineates the steps in the operations.

#### CONSTRUCTION SUPPORT EQUIPMENT

1. Tri-beam construction fixture system
2. Lighting and TV system
3. RMS with astronaut cherry picker

#### TIMELINE

60 minutes (see Attachment 1)

#### POWER/ENERGY

Peak power, 2.771 kW; average power, 1.890 kW; energy, 6803 kJ  
(see Attachment 1)

#### CREW LOAD

IVA astronaut—60 minutes, continuous  
EVA astronaut—None

#### TECHNOLOGY DEVELOPMENT REQUIREMENTS

1. Tri-beam construction fixture system
2. RMS with astronaut cherry picker and end effectors

SHEET 1 OF 2

ATTACHMENT 1

TIME, POWER AND ENERGY ESTIMATION FOR PREPARING CONSTRUCTION SYSTEM FOR CONSTRUCTION OPERATIONS (ACTIVITY 41.0)

ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
1. BRING RMS FROM ITS FINAL POSITION AT THE END OF DOCKING OPERATIONS INTO A POSITION AFFORDING AN ADVANTAGEOUS VIEW OF THE PRELIMINARY ELECTRICAL CHECKOUT TO FOLLOW.	300	0.845 (a) 1.050 (b) 0.033 (k) 0.173 (j) 0.200 (f) 0.400 (g)	0.845 (a) 0.525 (b) 0.023 (k) 0.173 (j) 0.200 (f) 0.400 (g)	
2. A PRELIMINARY ELECTRICAL CHECK OF THE CONSTRUCTION FIXTURE ELECTRICAL SYSTEM MUST BE PERFORMED TO CONFIRM THAT A SATISFACTORY ELECTRICAL CONNECTION WAS MADE AT DOCKING. THIS CHECK WILL INCLUDE CONSTRUCTION FIXTURE TV AND LIGHTING, BUT WILL NOT INCLUDE PLATFORM TRANSLATION DRIVE SYSTEM OR THE CONSTRUCTION FIXTURE ROTATION DRIVE.	600	2.701 1.050 (b) 0.033 (k) 0.033 (h) 0.173 (j) 0.200 (f) 0.400 (g)	2.166 0.525 (b) 0.023 (k) 0.023 (h) 0.173 (j) 0.200 (f) 0.400 (g)	650
3. TO REDUCE THE DANGER OF COLLISION BETWEEN THE RMS AND THE RCS BOOMS OF THE LIBRATION DAMPING SYSTEM, WHICH EXTEND OUT FROM THE CONSTRUCTION FIXTURE, THESE BOOMS MUST BE RETRACTED INTO THE STOWED POSITION.	300	1.889 1.050 (b) 0.033 (k) 0.033 (h) 0.173 (j) 0.200 (f) 0.400 (g)	1.344 0.525 (b) 0.023 (k) 0.023 (h) 0.173 (j) 0.200 (f) 0.400 (g)	806
4. MANEUVER THE RMS INTO POSITION AND ATTACH THE CHERRY PICKER WHICH IS STOWED APPROXIMATELY IN THE CENTER OF THE ORBITER CARGO BAY; PROPER ATTACHMENT IS CONFIRMED BY A CHECKOUT OF CHERRY PICKER FUNCTIONS. AT COMPLETION OF CHECKOUT, THE CHERRY PICKER MUST BE PARKED AS NEAR AS PRACTICAL TO THE AIRLOCK DOOR AND ADJACENT TO HANDHOLDS WHICH WILL PERMIT THE EVA ASTRONAUT TO EGRESS AND CLIMB INTO POSITION ABOARD IT.	1800	1.889 0.845 (a) 1.050 (b) 0.070 (k) 0.033 (h) 0.173 (j) 0.200 (f) 0.400 (g)	1.344 0.845 (a) 0.525 (b) 0.057 (k) 0.023 (h) 0.173 (j) 0.200 (f) 0.400 (g)	403
		2.771	2.223	4001

## ACTIVITY 41.0

ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
5. WHEN THE CHERRY PICKER IS READY TO RECEIVE HIM, THE EVA ASTRONAUT EGRESSES FROM THE AIRLOCK AND PROCEEDS VIA THE HANDHOLDS TO IT AND POSITIONS HIMSELF ABOARD. AN ON-BOARD FUNCTIONAL CHECK IS PERFORMED AND THEN THE CHERRY PICKER IS MANEUVERED INTO POSITION FOR NEXT ACTIVITY.	600	1.050 (b) 0.033 (h) 0.070 (c) 0.173 (j) 0.200 (f) 0.400 (g) 0.180 (i) 2.106	0.525 (b) 0.023 (h) 0.070 (c) 0.173 (j) 0.200 (f) 0.400 (g) 0.180 (i) 1.571	943
SUMMARY	3600 (60 MINUTES)	2.771 (d)	1.890 (e)	6803 1.890 kWh
NOTES (a) BASIC RMS (b) RMS HEATER (c) CHERRY PICKER (d) PEAK POWER SUMMARY BASED UPON PEAK POWER OF INDIVIDUAL ACTIVITIES, SUBJECTIVELY ESTIMATED, BEING PERFORMED SIMULTANEOUSLY (e) AVERAGE POWER = $\frac{\text{ENERGY SUMMATION}}{\text{ACTIVITY TIME SUMMATION}}$ (f) ORBITER LIGHTS (g) CONSTRUCTION FIXTURE LIGHTS (h) CONSTRUCTION FIXTURE TV & CAMERA (j) RMS LIGHTS (k) RMS TV & HEATER (i) CHERRY PICKER LIGHTS				






ACTIVITY 42.0

CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM

ACTIVITY



REFERENCE DATA

1. Drawing 42662-45, Rockwell Tri-Beam Concept, ETVP
2. Space Construction Data Base

DESCRIPTION OF ACTIVITY

This activity includes those operations necessary to install the two RCS pods on opposite ends of a crossbeam at one end or the other of the platform. Since there is one RCS pod bearing crossbeam at each end of the platform, this activity must be accomplished twice during the mission to install a total of four RCS pods. Attachment 1 delineates the steps in the activity, timelines, power and energy requirements. Attachment 2 provides a detail discussion of the operations.

CONSTRUCTION SUPPORT EQUIPMENT

1. Tri-Beam Construction Fixture System
2. Lighting and TV System
3. RMS with Astronaut Cherry Picker

TIMELINE: 87 minutes (see Attachment 1)

POWER/ENERGY:

Peak power, 2.992 kW; average power, 2.313 kW; total energy, 12,075 kJ  
(see Attachment 1)

CREW LOAD


IVA—Astronaut, 87 minutes support  
EVA—Astronaut, 87 minutes continuous

TECHNOLOGY DEVELOPMENT REQUIREMENTS: (1) tri-beam construction fixture system;  
(2) RMS with astronaut cherry picker.

ATTACHMENT 1

TIME, POWER, AND ENERGY SUMMATION FOR ACTIVITY 42.0--INSTALL RCS PODS

ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
1. POSITION PLATFORM	120	0.845 (a) 1.050 (b) 0.250 (c) 0.400 (f) 0.047 (h)	0.845 (a) 0.525 (b) 0.250 (c) 0.400 (f) 0.034 (h)	101.4 63.0 30.0 48.0 4.1 <u>294.5</u>
2. GRASP RCS MODULE NO. 1	300	SAME	SAME	736.3
3. TRANSPORT MODULE TO PLATFORM	1320	SAME	SAME	3239.5
4. ATTACH MODULE TO CROSSBEAM	480	SAME	SAME	1178.0
5. RETURN CHERRY PICKER	300	SAME	SAME	736.3
6. GRASP RCS MODULE NO. 2	300	SAME	SAME	736.3
7. TRANSPORT MODULE TO PLATFORM	1620	SAME	SAME	3975.8
8. ATTACH MODULE TO CROSSBEAM	480	SAME	SAME	1178.0
9. RETURN CHERRY PICKER	300	SAME	SAME	736.3
SUMMARY	5220	2.992 (d)	2.313 (e)	12,074.7
<p>(a) BASIC RMS (b) RMS HEATER (c) CHERRY PICKER (d) PEAK POWER SUMMARY BASED UPON PEAK POWER OF INDIVIDUAL ACTIVITIES, SUBJECTIVELY ESTIMATED, BEING PERFORMED SIMULTANEOUSLY.</p> <p>(e) AVERAGE POWER = <math>\frac{\text{ENERGY SUMMATION}}{\text{ACTIVITY TIME SUMMATION}}</math></p> <p>(f) ORBITER LIGHTS (g) CONSTRUCTION FIXTURE LIGHTS (h) CONSTRUCTION FIXTURE TV AND CAMERA</p>				

PREPARED BY:	Satellite Systems Division Space Systems Group		Rockwell International	PAGE NO. 1	OF 1
CHECKED BY:				ACTIVITY 42.0	
DATE:	INSTALL RCS PODS			MODEL NO. ETVP	
				DWG. NO.	


## ATTACHMENT 2

The process of installing the RCS module begins with the cherry picker attached to the end of the RMS and manned by an astronaut. The four RCS modules are contained in a revolving cradle which positions each module ready for pick-up. After the RMS/cherry picker has locked on to a module, the support trunnions are withdrawn via remote control from the orbiter cabin. The platform is translated through the construction fixture until the first long crossbeam is positioned 8.5 m outboard from the centerline of the orbiter and construction fixture as shown in Attachment 3.


Translating and aligning the RCS module for attachment involves several distinct operations. The lower arm of the RMS is raised approximately 30 degrees so that the upper and lower arm sections are in line. The joint in the upper arm of the modified RMS is rotated 180° in one direction. Concurrently, the wrist joint is rotated 180° in the opposite direction. This dual action has resulted in an orientation of the RMS which permits movement of the RCS module to the end of the crossbeam attach port. Attachment 4 illustrates these operations. The RCS module female attach port is berthed and locked to the male attach port on the end of the crossbeam. Mechanized connectors are then remotely actuated to complete the electrical connections across the berthed interface. Installation of the second RCS module is basically the same as just described, except that the RMS is translated to the opposite end of the first crossbeam, No. 1.

Subsequently, the tri-beam platform is translated its full length through the construction fixture, rotated 180° around the end of the platform to the position shown in Attachment 5. From this position, RCS modules No. 3 and 4 are installed.

With all four RCS modules installed, the orbiter is rotated back 180° and the platform translated its full length, which places the orbiter back at the forward end of the platform adjacent to the control module, ready for the system checkout activity.

PREPARED BY:	Satellite Systems Division Space Systems Group	 <b>Rockwell International</b>	PAGE NO. 1 OF 1
CHECKED BY:			ACTIVITY 42.0
DATE:	INSTALL RCS PODS		MODEL NO. ETVP
			DWG. NO.

ATTACHMENT 3



FORM 994-B-1 REV 12-78

PREPARED BY:

Satellite Systems Division  
Space Systems Group



Rockwell  
International

PAGE NO. 1 OF 1

CHECKED BY:

ACTIVITY 42.0


DATE:

INSTALL RCS PODS

MODEL NO. ETVP

DWG. NO.


ATTACHMENT 4



B-247

PREPARED BY:	Satellite Systems Division Space Systems Group	Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:			ACTIVITY 42.0
DATE:	INSTALL RCS PODS		MODEL NO. ETVP
			DWG. NO.

ATTACHMENT 5



RELATIONSHIP OF ORBITER TO PLATFORM FOR RCS MODULE ATTACHMENT

NOTE: ITEMS 1 & 2 REQUIRED FOR ASSEMBLY OF RCS MODULES N°3 & N°4.


ITEMS 3 & 4 RETURNS ORBITER BACK TO THE SYSTEMS MODULE END FOR THE NEXT (CHECK-OUT) PROCEDURE.

ACTIVITY 43.0

CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

ACTIVITY



REFERENCE DATA

1. Drawing 42662-45, Rockwell Tri-Beam Concept, ETVP
2. Space Construction Data Base
3. Drawing 42662-50, Tri-Beam Construction Fixture

DESCRIPTION OF ACTIVITY

The platform is translated through the construction fixture rollers to the opposite end in order to bring the next RCS pod mounting point within reach of the RMS/cherry picker.

CONSTRUCTION SUPPORT EQUIPMENT

Tri-beam construction fixture

TIMELINE

63 minutes, 136 meters @ 2.16 meters/minute

POWER/ENERGY

Peak power, 2.067 kW; average power, 1.180 kW; energy, 6160 kJ

CREW LOAD

IVA—Approximately 0.5, continuously monitoring  
EVA—None

TECHNOLOGY DEVELOPMENT REQUIREMENTS


Construction fixture roller drive and control system

ACTIVITY 44.0

CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING AND TECHNOLOGY VERIFICATION PLATFORM (ETVP)

ACTIVITY



REFERENCE DATA

1. Drawing 42662-45, Rockwell Tri-Beam Concept, ETVP
2. Space Construction Data Base

DESCRIPTION OF ACTIVITY

At this point, it will be necessary to rotate the platform 180 degrees to bring the desired work areas within range of the RMS. A rotation mechanism has been included in the construction fixture mounting arrangement to accommodate this requirement.

CONSTRUCTION SUPPORT EQUIPMENT

1. Tri-beam construction fixture system
2. Lighting and TV system

TIMELINE

Rotation time = 60 minutes, based on an angular velocity of 3 degrees/minute

POWER/ENERGY

Peak power, 2.067 kW; average power, 1.629 kW; energy 5865 kJ

CREW LOAD

IVA astronaut— 60 minutes, continuous  
EVA astronaut— 60 minutes, monitoring

TECHNOLOGY DEVELOPMENT REQUIREMENTS

Tri-beam construction fixture system

PRECEDING PAGE BLANK NOT FILMED




ACTIVITY 45.0

CONSTRUCTION ACTIVITY DATA SHEET

PROJECT ENGINEERING TECHNOLOGY AND VERIFICATION PLATFORM (ETVP)

ACTIVITY



REFERENCE DATA

1. Engineering and Technology Verification Platform (ETVP) Definition
2. Drawing 42662-45, Rockwell Tri-Beam Concept, ETVP
3. Drawing 42662-67, Shuttle Bay Packaging, Ground Flight Platform
4. Drawing 42662-74, Solar Array Assembly

DESCRIPTION OF ACTIVITY

The data/power umbilical will be withdrawn from the payload bay and connected to the platform's control module, using the EVA crewman in the RMS/cherry picker (see Attachment 1). The control module will be powered up and put through a self-test series of checks (see Attachment 4). For safe deployment of the solar array, the platform will be translated outboard to clear the wing surface. The solar array will be fully deployed and checked through the rotary joint. The array will then be retracted and the platform translated inboard so that the umbilical may be disconnected. Final activation, prior to orbiter separation, will be accomplished by translating the platform, deploying the solar array, and retesting the system—with verification over the RF link to the cabin.

CONSTRUCTION SUPPORT EQUIPMENT

RMS, cherry picker, power/data buffer unit (with umbilical)

TIMELINE: 7 hours (see Attachment 4)


POWER/ENERGY

Peak power, 5.277 kW; average power, 2.371 kW; energy, 54,495 kJ  
(see Attachment 4)


CREW LOAD


IVA—one crew, monitoring  
EVA—one crew, continuously

TECHNOLOGY DEVELOPMENT REQUIREMENTS: Development of software that is associated with checkout equipment and operations.

PREPARED BY:	Satellite Systems Division Space Systems Group	 <b>Rockwell International</b>	PAGE NO. 1 OF 1
CHECKED BY:			ACTIVITY 45.0
DATE:	ACTIVATE AND CHECK OUT PLATFORM SYSTEM		MODEL NO. ETVP
			OWG. NO.

ATTACHMENT 1



PREPARED BY:	Satellite Systems Division Space Systems Group	 Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:	ACTIVATE AND CHECKOUT PLATFORM SYSTEM		ACTIVITY 45.0
DATE:			MODEL NO. ETVF
			DWG. NO.

ATTACHMENT 2


CHECKOUT CONCEPT


The checkout concept for the platform is schematically represented in Attachment 3.

The platform's systems are controlled and monitored within the TT&C subsystem by the command and data (C&D) processor. The subsystem includes a platform self-test element (primarily in the form of software) which, upon command, automatically steps the platform's subsystem through sets of test operations and verifies the performance to the line/spare-replaceable-unit (LRU) level. Performance deviations outside spec limits are reported over the RF or umbilical link to the orbiter or to ground/mission control.

A test module element is included to verify the integrity of the self-test. This element emulates a performance model of the platform's systems—including performance deviations at the LRU level. The self-test procedure begins with a report of the measured performance of the test model.

Attachment 3 also shows the interface between the platform's checkout elements and the orbiter. The orbiter provides a power/data buffer unit (including the umbilical) which serves two functions: (1) provides external (orbiter) power at platform voltage (220 V) for systems operations and checkout; and (2) provides signal conditioning for compatibility between platform hardware and data bus streams and orbiter controls and displays in the aft cabin. In addition to the umbilical link, an RF link to the orbiter is provided for summary reports of the platform's status when the umbilical is not used.

PREPARED BY:	Satellite Systems Division Space Systems Group  Rockwell International	PAGE NO. 1 OF 1
CHECKED BY:		ACTIVITY 45.0
DATE:	ACTIVATE AND CHECK OUT PLATFORM SYSTEM	MODEL NO. ETVP DWG. NO.



FORM 586-U-1 REV 12-78

ACTIVITY 45.0 ATTACHMENT 4  
TIME, POWER, AND ENERGY SUMMATION FOR ACTIVATING AND CHECKING OUT PLATFORM SYSTEM (SHEET 1 OF 3)

ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
1. MANEUVER THE EVA CREWMAN/CHERRY PICKER/RMS INTO POSITION TO GRASP THE UMBILICAL CONNECTOR	600	0.845 (a) 1.05 (b) 0.25 (c)	0.845 (a) 0.525 (b) 0.25 (c)	507 315 150
2. GRASP THE CONNECTOR WITH THE MANIPULATOR/STABILIZER ARM OF THE CHERRY PICKER	120	0.845 (a) 1.05 (b) 0.25 (c)	0.845 (a) 0.525 (b) 0.25 (c)	101 63 30
3. MANEUVER THE CHERRY PICKER INTO POSITION TO CONNECT THE UMBILICAL WITH THE CHECKOUT PORT OF THE CONTROL MODULE. THE UMBILICAL WILL PAY OUT (UNDER TENSION) FROM A REEL WITHIN THE POWER/DATA BUFFER UNIT LOCATED IN THE PAYLOAD BAY.	600	0.845 (a) 1.05 (b) 0.25 (c)	0.845 (a) 0.525 (b) 0.25 (c)	508 315 150
4. INSERT THE CONNECTOR INTO THE CONTROL MODULE PORT AND ACTIVATE THE LATCHES WHICH WILL SECURE ALL MECHANICAL AND ELECTRICAL INTERFACES; VERIFY THE CONNECTIONS.  <i>NOTE: At this point, control of the operations is transferred to the aft cabin control station. The EVA astronaut remains aboard the cherry picker to observe, record, communicate, and take such local action as may be required.</i>	300	0.845 (a) 1.05 (b) 0.25 (c)	0.845 (a) 0.525 (b) 0.25 (c)	250 160 80
5. APPLY EXTERNAL (ORBITER) POWER TO THE CONTROL MODULE MAIN BUS TO BRING ALL PLATFORM SYSTEMS UP TO OPERATING CONDITIONS (E.G., TEMPERATURE, SPEED, ETC.). HARDWIRED (RED-LINES, SAFETY) FUNCTIONS ARE MONITORED FROM THE AFT CABIN.	7200	3 (f) 1.050 (b) 0.25 (c)	3 (f) 0.525 (b) 0.25 (c)	21,600 3,780 1,800
6. ACTIVATE THE PLATFORM'S SELF-TEST SYSTEM TO STEP THROUGH THE CHECKOUT SEQUENCE; SUMMARY VERIFICATION DATA ARE TRANSMITTED OVER THE UMBILICAL TO THE AFT CABIN.	3600	3 (f) 1.050 (b) 0.25 (c)	3 (f) 0.525 (b) 0.25 (c)	10,800 1,890 900

ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
7. WITH ALL SYSTEMS CHECKOUT COMPLETE (ON EXTERNAL POWER), MANEUVER THE CREWMAN/CHERRY PICKER TO A POSITION WHERE THE PLATFORM CAN BE FREELY TRANSLATED THROUGH THE FIXTURE.	300	0.845 (a) 1.05 (b) 0.25 (c)	0.845 0.525 0.25	254 158 75
8. TRANSLATE THE PLATFORM TO PLACE THE EXTENDED SOLAR ARRAY BEYOND THE PORT WING TIP—TO PRECLUDE THE POSSIBILITY OF COLLISION IN THE EVENT OF FAILURE IN THE ARRAY DRIVE SYSTEM. THE UMBILICAL, WHICH REMAINS ATTACHED, IS EXTENDED FROM THE PAYLOAD BAY.	240	1.05 (b) 0.25 (c)	0.525 (b) 0.25 (c)	126 60
9. EXTEND THE SOLAR ARRAY TO ITS FULLY DEPLOYED POSITION.	900	1.0 (f) 1.050 (b) 0.25 (c)	1.0 (f) 0.525 (b) 0.25 (c)	900 473 225
10. CHECK THE SOLAR ARRAY/ROTARY JOINT FOR POWER OUTPUT AND DRIVE SYSTEM PERFORMANCE	900	1.0 (f) 1.050 (b) 0.25 (c)	1.0 (f) 0.525 (b) 0.25 (c)	900 473 225
11. SWITCH PLATFORM SYSTEMS TO INTERNAL POWER TO CHECK POWER SWITCHING AND CONTINUITY.	120	NEGLIGIBLE 1.050 (b) 0.25 (c)	NEGLIGIBLE 0.525 (b) 0.25 (c)	63 30
12. SWITCH POWER TO EXTERNAL AND RETRACT SOLAR ARRAY PANELS; CHECK RETRACTION PROCESS	1020	1.0 1.050 (b) 0.250 (c)	1.0 0.525 (b) 0.250 (c)	1020 536 255
13. TRANSLATE THE PLATFORM BACK TO ORIGINAL POSITION WHERE CHERRY PICKER CAN PERFORM UMBILICAL DISCONNECT.	240	0.1 1.05 (b) 0.25 (c)	0.1 0.525 (b) 0.25 (c)	24 126 60
14. MANEUVER THE CHERRY PICKER INTO POSITION, DISCONNECT THE UMBILICALS AND RESTOW THE UMBILICAL INTO THE POWER/DATA BUFFER UNIT	300	0.845 (a) 1.05 (b) 0.25 (c)	0.845 (a) 0.525 (b) 0.25 (c)	254 158 75
15. TRANSLATE THE PLATFORM (REPEAT 8)	240	0.1 1.050 (b) 0.25 (c)	0.1 0.525 (b) 0.25 (c)	24 126 60

ATTACHMENT 4

ACTIVITY 45.0

SHEET 3 OF 3

ACTIVITY	DURATION (sec)	PEAK POWER (kW)	AVG. POWER (kW)	ENERGY (kJ)
16. USING THE RF COMMAND LINK AND INTERNAL (BATTERY) POWER, REDEPLOY THE SOLAR ARRAY (REPEAT 10).	900	NEGLIGIBLE 1.050 (b) 0.250 (c)	NEGLIGIBLE 0.525 (b) 0.250 (c)	473 225
17. REPEAT SELF-TEST PROCEDURE (ITEM 6) FOR CHECK OF INTEGRATED OPERATIONS AND RF LINK.	3600	0.1 1.050 (b) 0.25 (c)	0.1 0.525 (b) 0.25 (c)	360 158 900
18. MANEUVER THE CHERRY PICKER TO ITS STOWED POSITION IN THE BAY.	600	0.845 (a) 1.05 (b) 0.25 (c)	0.845 (a) 0.525 (b) 0.25 (c)	507 315 150
19. STOW/SECURE THE CHERRY PICKER	600	0.845 (a) 1.050 (b)	0.845 (a) 0.525	507 315
20. RE-ENTER THE EVA CREWMAN INTO THE AIRLOCK/CABIN	600	1.050 (b)	0.525	507
SUMMARY	22,980	5.277 (d)	2.371 (e)	54,495
<p>NOTES: (a) BASIC RMS (b) RMS HEATER (c) CHERRY PICKER (d) PEAK POWER SUMMARY BASED UPON PEAK POWER OF INDIVIDUAL ACTIVITIES, SUBJECTIVELY ESTIMATED, BEING PERFORMED SIMULTANEOUSLY</p> <p>(e) AVERAGE POWER = <math>\frac{\text{ENERGY SUMMATION}}{\text{ACTIVITY TIME SUMMATION}}</math> (f) ORBITER-FURNISHED CHECKOUT POWER</p>				

APPENDIX C  
MASS PROPERTIES STATEMENTS

Detail lists of cargo manifest items for each of the three construction missions are included in this appendix. The tables are arranged in order of the mission occurrence.

**PRECEDING PAGE BLANK NOT FILMED**





WEIGHT AND BALANCE, ORBITER CARGO—ETVP MISSION NO. 1

ITEM	WEIGHT (LB)	X <sub>CG</sub> (IN)	Y <sub>CG</sub> (IN)	Z <sub>CG</sub> (IN)	W <sub>X</sub>	W <sub>Y</sub>	W <sub>Z</sub>
PLATFORM ITEMS (SATELLITE)	(11,498)	1130.1	-0.3	356.3	(12,994,214)	(-3960)	(4,096,558)
BEAM MATERIAL (ON BEAM BUILDER)	2,761	1240.9	0	422.0			
CONVERTERS/REGULATORS/SWITCH GEARS	741	1102.9	0	332.0			
INTERSECT. FITTINGS (66)	198	1236.9	-20.0	360.0			
ATTACH PORTS (28) + TELEOP. PORTS (12)	6,468	1102.9	0	332.0			
CONDUCTOR	558	955.9	0	368.0			
CORD ASSY	75	935.9	0	400.0			
ELECTRICAL INSTALLATION	697	1103.0	0	332.0			
CONSTRUCTION ITEMS	(12,052)	956.5	1.3	428.5	(11,527,342)	(15,740)	(5,091,506)
CONSTRUCTION FIXTURE INSTAL.	(5,814)	787.5	3.4	424.1	(4,578,877)	(19,740)	(2,465,682)
MAIN BEAMS	1,680	742.0	0	428.0			
BASE BEAM	526	634.0	0	428.0			
JACK ARMS	273	674.0	0	428.0			
BRIDGE BEAMS (2)	350	842.0	0	428.0			
LONGITUDINAL BEAM ROLLER SUPT. (4)	450	854.0	50.0	435.0			
BRIDGE BEAM (1)	250	842.0	0	430.0			
BEAM BUILDER SWING ARM (1)	150	750.0	0	428.0			
SPOOL BRACKETS	75	930.0	0	396.0			
MISC. ARMS, LATCHES, ETC.	396	862.0	0	405.0			
AFT TRUNNION & MOUNT	200	896.0	0	414.0			
CORD REELS (6)	59	930.0	0	440.0			
CABLE REEL (3)	220	942.0	0	370.0			
RCS BOOMS	154	902.0	0	428.0			
SOLAR ARRAY DEPLOYMENT SYST.	22	902.0	0	428.0			
FIXTURE DEPLOYMENT SYST.	132	634.0	0	428.0			
RCS BOOM DEPLOYMENT	22	902.0	0	428.0			
TT&C MODULE	41	682.0	-46.0	428.0			
RCS, COLD GAS SYSTEM	395	882.0	0	428.0			
SOLAR ARRAY, 70 FT <sup>6</sup> (6.5 M <sup>2</sup> )	100	902.0	0	428.0			
BATTERIES (2)	20	682.0	46.0	428.0			
WIRE HARNESS	110	742.0	0	428.0			
ATT. REF. UNIT (GYRO SENSOR PKG)	37	682.0	-46.0	428.0			
COMPUTER MODULE	2	682.0	-46.0	428.0			
EVA WORK STATION	150	731.5	0	428.0			
BEAM BUILDER	(5,738)	1111.2	0	427.7	6,376,215	0	2,454,224
STRUCTURE	1,828	1118.9	0	424.0			
CAP FORMING	1,246	1239.0	0	424.0			
CROSS MEMBER SECT.	875	1033.0	0	432.0			
CORD SECTION	703	1033.0	0	432.0			
WELDING	57	1033.0	0	432.0			
CUTOFF	150	1033.0	0	432.0			

WEIGHT AND BALANCE, ORBITER CARGO—ETVP MISSION NO. 1

ITEM	WEIGHT (LB)	X <sub>0</sub> (IN)	Y <sub>0</sub> (IN)	Z <sub>0</sub> (IN)	ω <sub>x</sub>	ω <sub>y</sub>	ω <sub>z</sub>
BEAM BUILDER (CONT.)	595	1073.0	0	432.0			
AVIONICS/CONTROLS	15	1073.0	0	432.0			
COOLING	20	1073.0	0	432.0			
THERMAL SHROUD	249	1073.0	0	430.0			
LATCH/DEPLOYMENT	( 200)	1224.9	-20.0	360.0	244,980	-4000	72,000
INTERCONNECT FITTING CANISTER	( 300)	1090.9	0	332.0	327,270	0	99,600
SUPPORT FOR ATTACH PORTS							
AIRBORNE SUPPORT EQUIPMENT	(11,957)	900.7	7.1	361.8	10,769,898	84,738	4,325,713
BERTHING PLATFORM	1,200	681.9	0	364.0			
FWD CRADLE PALLET	575	681.6	0	360.0			
PALLET-CTR (STRUTS & RETURN ITEMS)	920	862.0	0	360.0			
STATION NO. 2 CRADLE	500	1072.9	0	360.0			
PALLET, AFT	1,455	1228.0	0	360.0			
AFT SUPT., BEAM MACHINE	350	1279.0	5.0	400.0			
LONG. BRIDGE FTG. STA. 659.9 (2)	172	659.9	0	404.0			
LONG. ATTACH FTG. " (2)	62	659.9	0	410.0			
LONG. BRIDGE FTG. STA. 703.2 (2)	188	703.2	0	404.0			
LONG. ATTACH FTG. " (2)	62	703.2	0	410.0			
KEEL BRIDGE FTG. STA. 659.93 (1)	59	659.9	0	308.0			
KEEL ATTACH FTG. " (1)	15	659.9	0	308.0			
LONG. BRIDGE FTG. STA. 817.27 (2)	216	817.3	0	404.0			
LONG. ATTACH FTG. " (2)	62	817.3	0	410.0			
LONG. BRIDGE FTG. STA. 884.13 (2)	216	884.1	0	404.0			
LONG. ATTACH FTG. " (2)	62	884.1	0	410.0			
KEEL BRIDGE FTG. " (1)	116	884.1	0	308.0			
KEEL ATTACH FTG. " (1)	15	884.1	0	308.0			
LONG. BRIDGE FTG. STA. 895.9 (2)	216	895.9	0	404.0			
LONG. ATTACH FTG. " (2)	220	895.9	0	410.0			
LONG. BRIDGE FTG. STA. 1072.9 (2)	208	1072.9	0	404.0			
LONG. ATTACH FTG. " (2)	220	1072.9	0	410.0			
LONG. BRIDGE FTG. STA. 1175.2 (2)	322	1175.2	0	404.0			
LONG. ATTACH FTG. " (2)	62	1175.2	0	410.0			
LONG. BRIDGE FTG. STA. 1281.4 (2)	328	1281.4	0	404.0			
LONG. ATTACH FTG. " (2)	62	1281.4	0	410.0			
KEEL BRIDGE FTG. STA. 1175.2 (1)	161	1175.2	0	308.0			
KEEL ATTACH FTG. " (1)	15	1175.2	0	308.0			

WEIGHT AND BALANCE, ORBITER CARGO—ETVP MISSION NO. 1

ITEM	WEIGHT (LB)	X <sub>0</sub> (IN)	Y <sub>0</sub> (IN)	Z <sub>0</sub> (IN)	ω <sub>x</sub>	ω <sub>y</sub>	ω <sub>z</sub>
AIRBORNE SUPPORT EQUIPMENT (CONT.)							
BRIDGE FITTING KIT (ORBITER PROVIDED)	450	1148.0	25.9	395.3			
MMU FLIGHT SUPPORT STA. (2)	100	628.0	0	400.0			
MMU (2)	406	628.0	0	400.0			
MMU EXPENDABLES	80	628.0	0	415.0			
CREWMEN (2)	400	490.0	38.0	349.0			
EMU PRESS. GARMENT (2)	406	490.0	38.0	349.0			
CRYO KIT, H2 NO. 3	370	1009.8	-76.0	302.0			
CRYO KIT, H2	92	1009.8	-76.0	302.0			
CRYO KIT, O2 NO. 3	366	1115.5	78.0	306.0			
CRYO, O2	781	1115.5	78.0	306.0			
DISPLAYS AND CONTROLS	50	556.0	0	451.5			
N2 TANK SYSTEM NO. 5	90	678.0	88.0	330.0			
N2, NO. 5	60	678.0	88.0	330.0			
N2 TANK SYSTEM NO. 6	90	1115.0	40.0	287.0			
N2, NO. 6	60	1115.0	40.0	287.0			
N2 TANK SYSTEM NO. 7	90	1115.0	-40.0	287.0			
N2, NO. 7	60	1115.0	-40.0	287.0			
RMS ADDED END EFFECTOR	100	927.0	-83.0	445.0			
TV CAMERA	20	927.0	-83.0	445.0			
LIGHTS	20	927.0	-83.0	445.0			
TOOL BOX	50	494.0	48.0	340.0			
SEAT & RESTRAINT NO. 5	54	494.0	48.0	340.0			
SEAT & RESTRAINT NO. 6	54	494.0	28.0	340.0			
FLIGHT GARMENT (2)	28	494.0	38.0	349.0			
FLIGHT HELMET (2)	10	494.0	38.0	350.0			
ACCESSORIES, WEAR-ON (2)	16	494.0	38.0	350.0			
PERSONAL PREFERENCE KIT (2)	1	494.0	38.0	350.0			
LIFE VEST (2)	5	494.0	38.0	350.0			
TOWEL ASSY (2)	3	494.0	38.0	350.0			
PERSONAL HYGIENE KIT (2)	7	557.0	-43.0	356.0			
FOOD TRAY (2)	10	557.0	-43.0	356.0			
WATER GUN (2)	2	557.0	-43.0	356.0			
PERSONAL RESCUE SYST. (2)	100	500.0	0	355.0			
BIOMEDICAL (2)	18	500.0	0	355.0			
PERSONAL RESCUE ENCLOSURE (2)	49	500.0	0	355.0			
CARGO BAY SERVICE PANELS	100	827.0	0	370.0			
ORBITER INTERFACE WIRING	200	741.0	0	370.0			
TOTAL CARGO (UP)	35,507	993.9	2.7	380.6	35,291,454	96,518	13,513,777

WEIGHT AND BALANCE, ORBITER CARGO--ETVP MISSION NO. 1 (RETURN)

ITEM	WEIGHT (LB)	X <sub>CG</sub> (IN)	Y <sub>CG</sub> (IN)	Z <sub>CG</sub> (IN)	W <sub>X</sub>	W <sub>Y</sub>	W <sub>Z</sub>
CONSTRUCTION ITEMS							
CONSTRUCTION FIXTURE ITEMS	(1,795)	861.3	0	354.2	(1,545,990)	0	(635,800)
BRIDGE BEAMS	350	850.0	0	348.0			
LONGITUDINAL BEAM ROLLER SUPT. (4)	450	850.0	0	348.0			
BRIDGE BEAM (1)	250	850.0	0	348.0			
BEAM BUILDER SWING ARM (1)	150	850.0	0	360.0			
SPOOL BRACKETS	75	850.0	0	360.0			
MISC. ARMS, LATCHES, ETC.	300	850.0	0	360.0			
CABLE REEL (3)	220	942.0	0	370.0			
BEAM BUILDER	5,738	1111.2	0	427.7	6,376,066	0	2,454,143
INTERCONNECT FITTING CANISTER	200	1224.9	-20.0	360.0	244,980	-4000	72,000
SUPPORT FOR ATTACH PORTS	300	1090.9	0	332.0	327,270	0	99,600
AIRBORNE SUPPORT EQUIPMENT	11,957	900.7	7.1	361.8	10,769,898	84,738	4,325,713
LESS	(-1,073)	1053.7	53.5	313.3	(-1,130,611)	(-47,446)	(-336,130)
MMU EXPENDABLES	-80	628.1	0	415.0			
CRYO, H2	-92	1009.1	-76.0	302.0			
CRYO, O2	-781	1115.5	78.0	306.0			
N2 NO. 5 TANK	-40	678.0	88.0	330.0			
N2 NO. 6 TANK	-40	1115.0	40.0	287.0			
N2 NO. 7 TANK	-40	115.0	-40.0	287.0			
TOTAL, CARGO ( RETURN )	18,917	958.6	1.2	383.3	18,133,593	23,292	7,251,126

WEIGHT AND BALANCE, ORBITER CARGO—ETVP MISSION NO. 2

ITEM	WEIGHT (LB)	X <sub>0</sub> (IN)	Y <sub>0</sub> (IN)	Z <sub>0</sub> (IN)	ω <sub>x</sub>	ω <sub>y</sub>	ω <sub>z</sub>
PLATFORM ITEMS	(23,660)	1123.3	-0.75	379.2	26,576,786	-17,763	8,971,483
X-BRACE STRUTS (24)	578	770.0	0	438.4			
BRIDGE STRUCT., S/A END	75	898.0	-51.0	448.0			
BRIDGE THRUST STRUCT.	324	834.0	0	384.0			
MECH, THRUST STRUCT.	44	786.0	0	384.0			
MECH, FWD MODULE TRUSS STRUCT.	22	890.0	-51.0	448.0			
ATTITUDE CONTROL	172	770.0	0	414.0			
TT&C	267	679.0	-48.0	432.0			
SYSTEM CONTROL MODULE	18,507	1129.0	0	368.0			
ROTARY JOINT ASSY	968	1275.0	0	336.0			
SOLAR ARRAY ASSY	2,703	1220.0	0	448.0			
CONSTRUCTION ITEMS	(990)	743.0	8.9	429.9	735,525	8,800	425,636
X-BRACE STRUCT. CANISTER	250	770.0	0	438.4			
CANISTER DEPLOYMENT SYSTEM	40	770.0	0	438.4			
EVA WORK STATION (CHERRY PICKER)	150	679.5	0	472.0			
INERTIAL ALIGNMENT UNITS (2)	550	746.0	16.0	414.0			
AIRBORNE SUPPORT EQUIPMENT	(8,957)	794.8	9.8	355.0	7,118,698	87,286	3,180,024
BERTHING PLATFORM	1,200	681.9	0	364.0			
FWD CRADLE PALLET	575	681.6	0	360.0			
CRADLE, CHECKOUT EQUIPMENT	150	730.7	0	365.0			
CRADLE, FWD, STRUCT. SUPT.	150	770.0	0	365.0			
CRADLE, AFT, STRUCT. SUPT.	150	959.0	0	365.0			
LONGERON BRIDGE FTG. STA. 659.9 (2)	172	659.9	0	404.0			
LONGERON ATTACH FTG. " (2)	62	659.9	0	410.0			
LONGERON BRIDGE FTG. STA. 703.2 (2)	188	703.2	0	404.0			
LONGERON ATTACH FTG. " (2)	62	703.2	0	410.0			
KEEL BRIDGE FTG. STA. 659.93 (1)	59	659.9	0	308.0			
KEEL ATTACH FTG. STA. 659.93 (1)	15	659.9	0	308.0			
LONGERON BRIDGE FTG. STA. 730.73 (2)	188	730.7	0	404.0			
LONGERON ATTACH FTG. " (2)	62	730.7	0	410.0			
KEEL BRIDGE FTG. " (1)	96	730.7	0	308.0			
KEEL ATTACH FTG. " (1)	15	730.7	0	308.0			
LONGERON BRIDGE FTG. STA. 770.07 (2)	200	770.1	0	404.0			
LONGERON ATTACH FTG. " (2)	62	770.1	0	410.0			
KEEL BRIDGE FTG. " (1)	119	770.1	0	308.0			
KEEL ATTACH FTG. " (1)	15	770.1	0	308.0			
LONGERON BRIDGE FTG. STA. 958.87 (2)	244	958.9	0	404.0			
LONGERON ATTACH FTG. " (2)	62	958.9	0	410.0			
KEEL BRIDGE FTG. " (1)	144	958.9	0	308.0			
KEEL ATTACH FTG. " (1)	15	958.9	0	308.0			

WEIGHT AND BALANCE, ORBITER CARGO—ETVP MISSION NO. 2

ITEM	WEIGHT (LB)	X <sub>CG</sub> (IN)	Y <sub>CG</sub> (IN)	Z <sub>CG</sub> (IN)	ω <sub>x</sub>	ω <sub>y</sub>	ω <sub>z</sub>
AIRBORNE SUPPORT EQUIPMENT (CONT.)							
LONGERON BRIDGE FTG. STA. 1033.6 (2)	232	1033.6	0	404.0			
LONGERON ATTACH FTG. " (2)	62	1033.6	0	410.0			
KEEL BRIDGE FTG. " (1)	167	1033.6	0	308.0			
KEEL ATTACH FTG. " (1)	15	1033.6	0	308.0			
LONGERON BRIDGE FTG. STA. 1222.4 (2)	276	1222.4	0	404.0			
LONGERON ATTACH FTG. " (2)	62	1222.4	0	410.0			
KEEL BRIDGE FTG. " (1)	255	1222.4	0	308.0			
KEEL ATTACH FTG. " (1)	15	1222.4	0	308.0			
BRIDGE FITTINGS, ORBITER PROVIDED	-450	1148.0	25.9	395.3			
MMU FLIGHT SUPPORT STA. (2)	100	628.0	0	400.0			
MMU (2)	406	628.0	0	400.0			
MMU EXPENDABLES	80	628.0	0	415.0			
CRYO KIT, H <sub>2</sub> NO. 3	370	1009.8	-76.0	302.0			
CRYO, H <sub>2</sub>	92	1009.8	-76.0	302.0			
CRYO KIT, O <sub>2</sub> NO. 3	366	1115.5	78.0	306.0			
CRYO, O <sub>2</sub>	781	1115.5	78.0	306.0			
DISPLAY AND CONTROLS	50	556.0	0	451.5			
N <sub>2</sub> TANK SYSTEM NO. 5	90	678.0	88.0	330.0			
N <sub>2</sub> , NO. 5	60	678.0	88.0	330.0			
N <sub>2</sub> TANK SYSTEM NO. 6	90	1115.0	40.0	287.0			
N <sub>2</sub> , NO. 6	60	1115.0	40.0	287.0			
CREWMEN (2)	400	490.0	38.0	349.0			
EMU PRESS. GARMENT (2)	406	490.0	38.0	349.0			
RMS ADDED END EFFECTOR	100	927.0	-83.0	445.0			
TV CAMERA	20	927.0	-83.0	445.0			
LIGHTS	20	927.0	-83.0	445.0			
TOOL BOX	50	494.0	48.0	340.0			
SEAT & RESTRAINT, NO. 5	54	494.0	48.0	340.0			
SEAT & RESTRAINT, NO. 6	54	494.0	28.0	340.0			
FLIGHT GARMENT (2)	28	494.0	38.0	349.0			
FLIGHT HELMET (2)	10	494.0	38.0	350.0			
ACCESSORIES, WEAR-ON (2)	16	494.0	38.0	350.0			
PERSONAL PREFERENCE KIT (2)	1	494.0	38.0	350.0			
LIFE VEST (2)	5	494.0	38.0	350.0			
TOWEL ASSY (2)	3	494.0	38.0	350.0			
PERSONAL HYGIENE KIT (2)	7	557.0	-43.0	356.0			
FOOD TRAY (2)	10	557.0	-43.0	356.0			
WATER GUN (2)	2	557.0	-43.0	356.0			
PERSONAL RESCUE SYST. (2)	100	500.0	0	355.0			
BIOMEDICAL (2)	18	500.0	0	355.0			
PERSONAL RESCUE ENCLOSURE (2)	49	500.0	0	355.0			

WEIGHT AND BALANCE, ORBITER CARGO—ETVP MISSION NO. 2

ITEM	WEIGHT (LB)	X <sub>0</sub> (IN)	Y <sub>0</sub> (IN)	Z <sub>0</sub> (IN)	ω <sub>x</sub>	ω <sub>y</sub>	ω <sub>z</sub>
AIRBORNE SUPPORT EQUIPMENT (CONT.)							
CARGO BAY SERVICE PANELS	100	827.0	0	370.0			
ORBITER INTERFACE WIRING	200	741.0	0	370.0			
LITHIUM HYDROXIDE CANISTERS (4)	28	489.0	7.0	320.0			
FECAL BAGS	2	470.0	-41.0	335.0			
URINE BAGS	2	470.0	-41.0	335.0			
VOMITUS BAGS	2	470.0	-41.0	335.0			
TRASH CONTAINER	1	470.0	-41.0	335.0			
FOOD, NORMAL CONSUMPTION	27	465.0	-65.0	368.0			
FOOD, CONTINGENCY CONSUMPTION	20	465.0	-65.0	368.0			
LiOH, EVA RECHARGES (4)	22	494.0	38.0	349.0			
SPARE BATTERY, EVA	16	494.0	38.0	349.0			
<hr/>							
TOTAL CARGO, UP	33,607	1,024.5	2.2	374.2	34,431,009	78,323	12,577,146

WEIGHT AND BALANCE, ORBITER CARGO—ETVP MISSION NO. 2 (RETURN)

ITEM	WEIGHT (LB)	X <sub>O</sub> (IN)	Y <sub>O</sub> (IN)	Z <sub>O</sub> (IN)	ω <sub>x</sub>	ω <sub>y</sub>	ω <sub>z</sub>
CONSTRUCTION ITEMS	990	743.0	8.9	429.9	735,525	8,800	425,636
AIRBORNE SUPPORT EQUIPMENT	8,957	794.8	9.8	355.0	7,118,698	87,286	3,180,024
LESS:	(-1,033)	1051.4	57.2	314.3	-1,086,067	-59,046	-324,650
MMU EXPENDABLES	-80	628.0	0	415.0			
CRYO, H <sub>2</sub>	-92	1009.8	-76.0	302.0			
CRYO, O <sub>2</sub>	-781	1115.5	78.0	306.0			
N <sub>2</sub> , TANK NO. 5	-40	678.0	88.0	330.0			
N <sub>2</sub> , TANK NO. 6	-40	1115.0	40.0	287.0			
TOTAL CARGO, DOWN	8,914	759.3	4.2	368.1	6,768,156	37,040	3,281,010



WEIGHT AND BALANCE, ORBITER CARGO—ETVP MISSION NO. 3

ITEM	WEIGHT (LB)	X <sub>o</sub> (IN)	Y <sub>o</sub> (IN)	Z <sub>o</sub> (IN)	ω <sub>x</sub>	ω <sub>y</sub>	ω <sub>z</sub>
PLATFORM ITEMS	(18,800)	1220.0	0	399.0	22,936,000	0	7,501,200
RCS MODULE, INCL. PORT	4,700	1220.0	24.0	446.0			
RCS MODULE, INCL. PORT	4,700	1220.0	-48.0	424.0			
RCS MODULE, INCL. PORT	4,700	1220.0	48.0	374.0			
RCS MODULE, INCL. PORT	4,700	1220.0	-24.0	352.0			
AIRBORNE SUPPORT EQUIPMENT	(7,804)	947.4	-1.9	375.7	5,868,945	-11,620	2,327,669
BERTHING PLATFORM	1,200	681.9	0	364.0			
FWD PALLET (BERTHING PLATFORM)	575	681.6	0	360.0			
AFT PALLET & MECH (RCS)	2,000	1230.0	0	368.0			
LONG. BRIDGE FTG., STA. 659.9 (2)	172	659.9	0	404.0			
LONG. ATTACH FTG., " (2)	62	659.9	0	410.0			
KEEL BRIDGE FTG., " (1)	59	659.9	0	308.0			
KEEL ATTACH FTG., " (1)	15	659.9	0	404.0			
LONG. BRIDGE FTG., STA. 1159.47 (2)	228	1159.5	0	404.0			
LONG. ATTACH FTG., " (2)	62	1159.5	0	410.0			
KEEL BRIDGE FTG., " (1)	161	1159.5	0	308.0			
KEEL ATTACH FTG., " (1)	15	1159.5	0	308.0			
LONG. BRIDGE FTG., STA. 1281.4 (2)	328	1281.4	0	404.0			
LONG. ATTACH FTG., " (2)	62	1281.4	0	410.0			
DISPLAYS AND CONTROLS	25	556.0	0	451.5			
RMS ADDED END EFFECTOR	100	927.0	-83.0	445.0			
TV CAMERA	20	927.0	-83.0	445.0			
LIGHTS	20	927.0	-83.0	445.0			
CARGO BAY SERVICE PANELS	20	827.0	0	370.0			
ORBITER INTERFACING WIRING	60	942.0	0	370.0			
CHECKOUT SYSTEM	500	730.7	0	414.0			
CRADLE, CHECKOUT EQUIPMENT	150	730.7	0	365.0			
LONGERON BRIDGE FTG., STA. 730.73 (2)	188	730.7	0	404.0			
LONGERON ATTACH FTG., " (2)	62	730.7	0	410.0			
KEEL BRIDGE FTG., " (1)	96	730.7	0	308.0			
KEEL ATTACH FTG., " (1)	15	730.7	0	308.0			
CRYO KIT, H2 NO. 3	370	1009.8	-76.0	302.0			
CRYO, H2	92	1009.8	-76.0	302.0			
CRYO KIT, O2 NO. 3	366	1115.5	78.0	306.0			
CRYO, O2	781	1115.5	78.0	306.0			
TOTAL CARGO, LESS PAYLOAD	26,604	1152.4	-0.5	393.2	28,804,945	-11,620	9,828,869
PAYLOAD, INCL. ASE (MAX FOR 250 NM)	3,396	944.5	0	400.0	4,727,222	0	2,002,000
TOTAL CARGO (UP)	30,000	1117.7	-0.4	394.4	33,532,167	-11,620	11,830,869
LESS: RCS MODULES	-18,800	1220.0	0	399.0	-22,936,000	0	-7,501,200
TOTAL CARGO (RETURN)	11,200	946.1	-1.04	386.6	10,596,167	-11,620	4,329,669